

# SPILLTECH

Your Resource for Sorbent Mats, Kits & Containment Products

Over **80 NEW**  
Products Inside!

**NEW!**  
Containment  
Roll-Tops  
page 55



Fast-Response  
Spill Kits  
pages 37-44

SpillTech®  
Sorbent Mats  
pages 4-23

**NEW!**  
Poly Containment Decks  
page 53

**NEW!**  
Eco-Friendly  
Absorbent Mats  
page 20

**NEW!**  
Specialty Absorbent Mats  
pages 24-27

# Look What's NEW at SpillTech!

It's All Inside Our Biggest Catalog Ever...

SPILLTECH



## Over 80 NEW Products!

### Our Most Complete Offering to Date

Just look for the red "New" symbol, shown at left, for our latest products. You'll find two new sorbent lines, HighLoft and EcoTech™ Mat, along with other additions like TrackMat and RigMat. You'll also find an expanded Containment section offering new drum storage and spill containment products that make this our most complete offering yet!

## NEW Recycled Products!

### To Help You Create a Greener Facility

SpillTech® Products made from recycled and renewable resources can help your facility fulfill environmental initiatives and supply-chain requirements. Look for Environmentally Responsible Sorbents including EcoTech™ Mat, Booms, Socks, Pillows and more.



## NEW Technology & Equipment!

### Innovations to Boost Efficiency & Lower Cost


We are always seeking to improve your productivity and save you money. Our new modular spill decks connect to share sump capacity and lower your containment costs. And, our cutting-edge HighLoft Mat technology increases loft, sorbency and strength but decreases shipping weight. Look inside for even more examples!



Look for the green "Helps You Comply" box throughout this catalog for SpillTech® Products that can assist you with regulatory compliance.

# SpillTech® Mat Selection Guide

At SpillTech, we manufacture a wide range of Mats — each created through a distinctive process to have particular strengths and perform better in specific applications. Use this chart to browse the varieties of Mat available, then turn to the page number listed for details.

Liquids Absorbed	Primary Applications	Absorbency/Durability			Mat Name	Page
		Single	Medium	Heavy		
 <p><b>Universal</b></p> <p>For oils, coolants, solvents and water</p> <ul style="list-style-type: none"> <li>Hydraulic Oil</li> <li>Ethanol</li> <li>Gasoline</li> <li>Kerosene</li> <li>Water</li> <li>Sulfuric Acid</li> <li>Acetone</li> <li>Toluene</li> <li>Xylene</li> <li>MEK (Methyl Ethyl Ketone)</li> </ul>	<ul style="list-style-type: none"> <li>High-volume cleanups</li> <li>Economical liquid control</li> </ul>		●		<b>HighLoft</b>	4
	<ul style="list-style-type: none"> <li>Controls spills and overspray</li> <li>Keep floors safe and dry</li> </ul>	●	●	●	<b>SonicBonded Mat</b>	8
	<ul style="list-style-type: none"> <li>Foot traffic areas</li> <li>Grips floor for safer walking</li> </ul>	●	●	●	<b>FineFiber Mat</b>	12
	<ul style="list-style-type: none"> <li>Last longer in rugged applications</li> <li>Reduces replacement costs</li> </ul>		●	●	<b>MultiLaminate Mat</b>	14
	<ul style="list-style-type: none"> <li>Absorbing in tight spaces</li> <li>Wiping</li> </ul>			●	<b>AirLaid Mat</b>	16
	<ul style="list-style-type: none"> <li>High-traffic areas</li> <li>Use as a Roll, Sock or Pad</li> </ul>			●	<b>SurvivorSeries™ Mat</b>	18
<ul style="list-style-type: none"> <li>Machine leaks and overspray</li> <li>High-volume cleanups</li> </ul>	●		●	<b>EcoTech™ Mat</b>	20	

Liquids Absorbed	Primary Applications	Absorbency/Durability			Mat Name	Page
		Single	Medium	Heavy		
 <p><b>Oil-Only</b></p> <p>For absorbing oil while repelling water</p> <ul style="list-style-type: none"> <li>Motor Oil</li> <li>Hydraulic Oil</li> <li>Gasoline</li> <li>Diesel Fuel</li> <li>Jet Fuel</li> </ul>	<ul style="list-style-type: none"> <li>High-volume cleanups</li> <li>Economical liquid control</li> </ul>		●		<b>HighLoft</b>	4
	<ul style="list-style-type: none"> <li>High-volume indoor/outdoor cleanups</li> <li>Economical liquid control</li> </ul>		●		<b>HighLoft MeltBlown Mat</b>	4
	<ul style="list-style-type: none"> <li>Oil spills on land or water</li> <li>Quick, effective oil-only cleanup</li> </ul>	●	●	●	<b>MeltBlown Mat</b>	6
	<ul style="list-style-type: none"> <li>Controls spills and overspray</li> <li>Keep floors safe and dry</li> </ul>	●	●	●	<b>SonicBonded Mat</b>	8
	<ul style="list-style-type: none"> <li>Absorbing oily spills and leaks</li> <li>Fast oil-only cleanup</li> </ul>	●	●	●	<b>FineFiber Mat</b>	10
	<ul style="list-style-type: none"> <li>Last longer in rugged applications</li> <li>Reduces replacement costs</li> </ul>		●	●	<b>MultiLaminate Mat</b>	14
	<ul style="list-style-type: none"> <li>Absorbing in tight spaces</li> <li>Wiping</li> </ul>			●	<b>AirLaid Mat</b>	16
	<ul style="list-style-type: none"> <li>High-traffic areas</li> <li>Use as a Roll, Sock or Pad</li> </ul>			●	<b>SurvivorSeries™ Mat</b>	18

Liquids Absorbed	Primary Application	Absorbency/Durability			Mat Name	Page
		Single	Medium	Heavy		
 <p><b>HazMat</b></p>	<ul style="list-style-type: none"> <li>Absorbing caustic, hazardous or unknown liquids</li> </ul>	●	●	●	<b>SonicBonded Mat</b>	22
				●	<b>FineFiber Mat</b>	22

\*For further help please contact your local Distributor.

## Mats ..... 4-21



HighLoft Mat	4
MeltBlown Mat	6
SonicBonded Mat	8
FineFiber Mat	10
MultiLaminate Mat	14
AirLaid Mat	16
SurvivorSeries™ Mat	18
EcoTech™ Mat	20

Mats

## HazMat ..... 22-23



Mats	22
Socks	22
Booms	22
Pillows	22

HazMat

## Specialty Products..... 24-36



Mats & Accessories	24
Industrial Rugs	25
Socks, Pillows & Pans	28
Loose Sorbents	33
Outdoor Prevention	36

Specialty Products

## Spill Response ..... 34-35



Booms	34
PomPoms	35
NetBags	35
Folded Sweep	35
Loose Particulate	35

Spill Response

## Spill Kits..... 37-47



OverPack Kits	37-39
Recycled Kits	38
Portable Kits	41
Mercury/Battery Acid Kits	41
Repair Kits	42
Customize Your Kit	43
Accessories	44

Spill Kits

## Stormwater Mgmt..... 48-50



DrainCovers	48
Conical DrainPlugs	48
SpillBerms	49
Ultra-Dewatering Bag®	50
Ultra-GutterGuard®	50
Ultra-DrainGuard®	50

Stormwater Management

## Containment ..... 51-57



Leak Diverters	51
Prowler™ Pools	51
Burp-Free Funnels	52
Sumps	52
Spill Decks & Pallets	53
Portable Containment	56

Containment

## Product Resources..... 58-67



Product SpecSheet	58
Regulation Compliance	67

Product Resources

# HighLoft Mat High Sorbency for Less



Oil-Only HighLoft Mat also floats to clean up spills on water.

## Mat Index

You are here

Mat Name	Description	Page
<b>HighLoft Mat</b>	High sorbency for less	4
<b>MeltBlown Mat</b>	Quickly absorbs oil	6
<b>SonicBonded Mat</b>	Controls spills	8
<b>FineFiber Mat/Oil-Only</b>	Speeds cleanup	10
<b>FineFiber Mat/Universal</b>	Grips floor	12
<b>MultiLaminate Mat</b>	Lasts longer	14
<b>AirLaid Mat</b>	Our most flexible Mat	16
<b>SurvivorSeries™ Mat</b>	Our toughest Mat	18
<b>EcoTech™ Mat</b>	75% recycled content	20
<b>HazMat Mat</b>	For unknown liquids	22

For more help choosing the right sorbent Mat, see our **Mat Selection Guide** on page 3.

## HighLoft Mat — Economical Liquid Control

### HighLoft Saves You Money

Upgraded manufacturing capabilities create a Mat that's sturdy and soft but has a higher loft than standard mats for greater economy without compromising sorbency. Between SingleWeight and MediumWeight but able to take in 30 times its own weight in liquids!

### Color-Coded

Color-coding helps you visually identify the right sorbent for your needs.

Grunge-hiding Gray signifies universal sorbency for oils, coolants, solvents and water. Bright white designates Oil-Only sorbency for oil and other petroleum-based fluids — but not water; makes it easy to identify when saturated.

### Two Mat Versions to Better Match Your Application

HighLoft Mat is available in Bonded and MeltBlown. See the next page for more information on each version.


**HYC** Helps you comply with 29 CFR 1910.22(a)(2), 29 CFR 1910.107(b)(3), 29 CFR 1910.107(g)(2), 29 CFR 1910.120(j)(1) and 29 CFR 1910.1450(e). See page 67 for details.

The Technology Inside...

# HighLoft Mat


**Primary Use:**  
Economical Everyday Cleanups

**Primary Benefit:**  
Greater Economy without  
Compromising Sorbency



HighLoft

**HighLoft/Bonded** — One (1) layer of HighLoft polypropylene sorbent with bond points.



HighLoft

**HighLoft/MeltBlown** — One (1) layer of HighLoft hydrophobic (oil-only) polypropylene sorbent.

## HighLoft Bonded Mat

### Fast-Acting for Quick Response

MeltBlown polypropylene creates high surface area that enables Mat to quickly soak up liquids on contact.

### High Absorbency Keeps It on the Job Longer

A random assembly of large-diameter MeltBlown poly fibers creates a lofty Mat. Absorbs high volumes of liquid fast. Great for overspray or spills.

### Ultrasonic Bond Points Keep Mat Intact

Ultrasonic bond points fuse layers of fibers together — Mat keeps its shape even when completely saturated. “Dimples” add fast-wicking power.

### Multi-Perforations Save You Money

Rolls are perfed every 7.5" vertically and every 17" horizontally. Pads are perfed at 7.5" vertically.

## HighLoft MeltBlown Mat

### Fast-Wicking

Loose stacked-weave design increases surface area on spill. Mat starts wicking on contact to save time in critical situations. Works equally well on land or water — it even floats when fully saturated. Ideal for outdoor use — MeltBlown Mat provides quick, efficient cleanup to help protect the environment from contamination.

### High Sorbency Keeps Mat on the Job Longer

Large-diameter MeltBlown polypropylene fibers are randomly assembled to create a lofty Mat that absorbs high volumes of liquid fast.



White Oil-Only MeltBlown Mat is perfect for rolling out in front of messy machinery. The white color calls your attention to leaks or drips, and the HighLoft fibers absorb high volumes of liquid fast.



### HighLoft Bonded Mat / Universal

**Gray Universal Bonded** (for oils, coolants, solvents & water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
NEW GRB150G	HighLoft Roll	30"x150'	1	39.8 gal.
NEW GPB100GL	HighLoft Pads	15"x18"	100	19.5 gal.

### HighLoft Bonded Mat / Oil-Only

**White Oil-Only Bonded** (for oils, not water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
NEW WRB150G	HighLoft Roll	30"x150'	1	39.8 gal.
NEW WPB100GL	HighLoft Pads	15"x18"	100	19.5 gal.

### HighLoft MeltBlown Mat / Oil-Only

**White Oil-Only MeltBlown** (for oils, not water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
NEW WR150G	HighLoft Roll	30"x150'	1	41.2 gal.
NEW WP100GL	HighLoft Pads	15"x18"	100	19.7 gal.

**Keep your sorbent mat rolls off of the messy floor. See page 24 for our Free-Standing RollRack.**

# MeltBlown Mat Quickly Absorbs Oil



Ideal for outdoor use — MeltBlown Mat provides quick, efficient cleanup to help protect the environment from contamination.

## Quick, Effective Cleanup of Oil Spills on Land or Water

### Fast-Wicking

Loose stacked-weave design increases surface area on spill. Mat starts wicking on contact to save time in critical situations. Works equally well on land or water — it even floats when fully saturated.

### Absorbs Oily Liquids — Repels Water

MeltBlown polypropylene fibers are left in their natural hydrophobic state. These hydrophobic fibers repel water (and float) while only absorbing oils and other hydrocarbons.

### High Sorbency Keeps Mat on the Job Longer

Large-diameter MeltBlown polypropylene fibers are randomly assembled to create a lofty Mat that absorbs up to 42.8 oz. per 15" x 19" HeavyWeight Pad and 63.4 gallons per HeavyWeight Roll.

### Bright White Color Makes it Easy to See When Mat is Completely Saturated

Oily grunge can't hide on bright White MeltBlown Mat. Makes it easy to see when it's fully saturated — you save money by not throwing it away too soon.

## Mat Index

Mat Name	Description	Page
<b>HighLoft Mat</b>	High sorbency for less	4
<b>MeltBlown Mat</b>	Quickly absorbs oil	6
<b>SonicBonded Mat</b>	Controls spills	8
<b>FineFiber Mat/Oil-Only</b>	Speeds cleanup	10
<b>FineFiber Mat/Universal</b>	Grips floor	12
<b>MultiLaminate Mat</b>	Lasts longer	14
<b>AirLaid Mat</b>	Our most flexible Mat	16
<b>SurvivorSeries™ Mat</b>	Our toughest Mat	18
<b>EcoTech™ Mat</b>	75% recycled content	20
<b>HazMat Mat</b>	For unknown liquids	22

You are here




Helps you comply with 29 CFR 1910.22(a)(2), 29 CFR 1910.120(j)(1), 29 CFR 1910.1450(e), 40 CFR 263.30(a) and 40 CFR 263.31. See page 67 for details.

The Technology Inside...

# MeltBlown Mat

**Primary Use:**  
Oil Spills on Land or Water

**Primary Benefit:**  
Quick, Effective Oil-Only Cleanup



## Static-Dissipative Mat Also Available

**Specially Treated Mat in Easy-to-Identify Packaging**

Ideal for absorbing volatile fuels in cold applications, dry, low-humidity areas or anywhere that the potential for sparking exists. Static-Dissipative Mat comes in a blue wrapper for quick identification when you need Mat where static electricity poses a risk.



### Static-Dissipative Mats

**White Static-Dissipative** (for oils, not water; deters static charges)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
WPX25H	HeavyWeight Pads	15"x19"	25	8.4 gal.
WPX50S	SingleWeight Pads	15"x19"	50	8.9 gal.
WRX150H	HeavyWeight Roll	30"x150'	1	63.4 gal.

### MeltBlown Mats

**White Oil-Only** (for oils, not water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
WP100H	HeavyWeight Pads	15"x19"	100	33.4 gal.
WPK50H	HeavyWeight King Pads	30"x30"	50	52.8 gal.
WP100M	MediumWeight Pads	15"x19"	100	26.7 gal.
WP100S	SingleWeight Pads	15"x19"	100	17.9 gal.
WP200S	SingleWeight Pads	15"x19"	200	35.7 gal.
WR150H	HeavyWeight Roll	30"x150'	1	63.4 gal.
WRS150H	HeavyWeight Split Rolls	15"x150'	2	63.4 gal.
WR150M	MediumWeight Roll	30"x150'	1	50.7 gal.
WRS150M	MediumWeight Split Rolls	15"x150'	2	50.7 gal.
WR300S	SingleWeight Roll	30"x300'	1	67.9 gal.
WRS300S	SingleWeight Split Rolls	15"x300'	2	67.9 gal.

# SonicBonded Mat Controls Spills and Overspray



Fast-acting SonicBonded Mat starts absorbing on contact. It's the best choice for overspray and soaking up spills.

## Absorbs Overspray and Spills — Helps Keep Floors Dry and Safe

### Fast-Acting for Quick Response

A layer of MeltBlown polypropylene creates high surface area that enables SonicBonded Mat to quickly soak up liquids.

### High Absorbency Keeps It on the Job Longer

A random assembly of large-diameter MeltBlown poly fibers creates a lofty layer. Mat absorbs up to 37.3 oz. per 15" x 19" HeavyWeight Pad and 55.2 gallons per 150' HeavyWeight Roll. Choose Universal or Oil-Only.

### Ultrasonic Bond Points Keep Mat Intact

Ultrasonic bond points fuse layers of fibers together — Mat keeps its shape even when completely saturated. Top layer of SpunBond fabric provides added strength.

### Perforations Save Money

SpunBond top layer allows for better-defined perforations and cleaner, easier tear-offs. Rolls are perfed every 7.5" vertically and 17" horizontally. Pads are perfed vertically at 7.5".

## Mat Index

Mat Name	Description	Page
<b>HighLoft Mat</b>	High sorbency for less	4
<b>MeltBlown Mat</b>	Quickly absorbs oil	6
<b>SonicBonded Mat</b>	Controls spills	8
<b>FineFiber Mat/Oil-Only</b>	Speeds cleanup	10
<b>FineFiber Mat/Universal</b>	Grips floor	12
<b>MultiLaminate Mat</b>	Lasts longer	14
<b>AirLaid Mat</b>	Our most flexible Mat	16
<b>SurvivorSeries™ Mat</b>	Our toughest Mat	18
<b>EcoTech™ Mat</b>	75% recycled content	20
<b>HazMat Mat</b>	For unknown liquids	22

You are here


**HYC** Helps you comply with 29 CFR 1910.22(a)(2), 29 CFR 1910.107(b)(3), 29 CFR 1910.107(g)(2), 29 CFR 1910.120(j)(1) and 29 CFR 1910.1450(e). See page 67 for details.

*The Technology Inside...*

# SonicBonded Mat

**Primary Use:**  
Controls Spills and Overspray

**Primary Benefit:**  
Helps Keep Floors Safe and Dry



One (1) layer of lint-free SpunBond fabric is ultrasonically bonded to one (1) layer of MeltBlown sorbent.



## SonicBonded Mat

**Gray Universal** (for oils, coolants, solvents & water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
GPB100H	HeavyWeight Pads	15"x19"	100	29.1 gal.
GPB50H	HeavyWeight Pads	15"x19"	50	14.6 gal.
GPKB50H	HeavyWeight King Pads	30"x30"	50	45.3 gal.
GPB100M	MediumWeight Pads	15"x19"	100	24.7 gal.
GPB200S	SingleWeight Pads	15"x19"	200	31.1 gal.
GPB100S	SingleWeight Pads	15"x19"	100	15.6 gal.
GRB150H	HeavyWeight Roll	30"x150'	1	55.2 gal.
GRSB150H	HeavyWeight Split Rolls	15"x150'	2	55.2 gal.
GRB150M	MediumWeight Roll	30"x150'	1	46.1 gal.
GRB300S	SingleWeight Roll	30"x300'	1	59.1 gal.

**White Oil-Only** (for oils, not water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
WPB100H	HeavyWeight Pads	15"x19"	100	29.1 gal.
WPB50H	HeavyWeight Pads	15"x19"	50	14.6 gal.
WPKB50H	HeavyWeight King Pads	30"x30"	50	45.3 gal.
WPB100M	MediumWeight Pads	15"x19"	100	24.7 gal.
WPB50M	MediumWeight Pads	15"x19"	50	12.4 gal.
WPB200S	SingleWeight Pads	15"x19"	200	31.1 gal.
WPB100S	SingleWeight Pads	15"x19"	100	15.6 gal.
WRB150H	HeavyWeight Roll	30"x150'	1	55.2 gal.
WRSB150H	HeavyWeight Split Rolls	15"x150'	2	55.2 gal.
WRB150M	MediumWeight Roll	30"x150'	1	46.1 gal.
WRSB150M	MediumWeight Split Rolls	15"x150'	2	46.1 gal.
WRB300S	SingleWeight Roll	30"x300'	1	59.1 gal.

# FineFiber Mat Oil-Only, Repels Water



FineFiber Mat can be used wherever a low-profile sorbent product is needed for catching oil leaks and overspray, especially walkways, workstations and other foot-traffic areas.

## Mat Index

Mat Name	Description	Page
<b>HighLoft Mat</b>	High sorbency for less	4
<b>MeltBlown Mat</b>	Quickly absorbs oil	6
<b>SonicBonded Mat</b>	Controls spills	8
<b>FineFiber Mat/Oil-Only</b>	Speeds cleanup	10
<b>FineFiber Mat/Universal</b>	Grips floor	12
<b>MultiLaminate Mat</b>	Lasts longer	14
<b>AirLaid Mat</b>	Our most flexible Mat	16
<b>SurvivorSeries™ Mat</b>	Our toughest Mat	18
<b>EcoTech™ Mat</b>	75% recycled content	20
<b>HazMat Mat</b>	For unknown liquids	22

You are here

## FineFiber Oil-Only Mat Quickly Absorbs Oily Spills and Overspray

### High Sorbency Keeps it on the Job Longer

FineFiber Oil-Only Mat is naturally water-resistant (hydrophobic). A random assembly of large-diameter MeltBlown poly fibers creates a lofty inner layer that absorbs up to 33.7 oz. of oil — but not water — per 15" x 19" HeavyWeight Pad and 49.8 gallons per 150' HeavyWeight Roll.

### Grips Surfaces Tightly

Top and bottom layers of FineFiber are built of densely woven, small-diameter

strands of fiber to increase surface area, enabling the mat to grip surfaces securely.

### Virtually Indestructible

FineFiber Mat has a layer of MeltBlown polypropylene ultrasonically sandwiched between two FineFiber layers, so you can use it almost anywhere.

### Multi-Perforations Save You Money

Rolls are perforated every 7.5" vertically and every 17" horizontally. Pads are perforated at 7.5" vertically — saves you money!




Helps you comply with 29 CFR 1910.22(a)(2), 29 CFR 1910.107(b)(3), 29 CFR 1910.107(g)(2), 29 CFR 1910.120(j)(1) and 29 CFR 1910.1450(e). See page 67 for details.

*The Technology Inside...*


# FineFiber Mat

**Primary Use:**  
Absorbing Oily Spills and Leaks but not Water

**Primary Benefit:**  
Speeds Cleanup



Two (2) layers of FineFiber polypropylene are ultrasonically bonded around a high-loft MeltBlown core.



## FineFiber Mat/Oil-Only

**White Oil-Only Pads** (for oils, not water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
WPF100H	HeavyWeight Pads	15"x19"	100	26.3 gal.
WPF1113H	HeavyWeight Pads	11"x13"	100	18.1 gal.
WPF100H-BX	HeavyWeight Pads in Box	15"x19"	100	26.3 gal.
WPKF50H	HeavyWeight King Pads	30"x30"	50	41.6 gal.
WPF100M	MediumWeight Pads	15"x19"	100	20.8 gal.
WPF200S	SingleWeight Pads	15"x19"	200	28.1 gal.

**White Oil-Only Rolls** (for oils, not water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
WRF150H	HeavyWeight Roll	30"x150'	1	49.8 gal.
WRF24150H	HeavyWeight Roll	24"x150'	1	39.8 gal.
WRF100H-BX	HeavyWeight Roll in Box	15"x100'	1	19.3 gal.
WRSF150H	HeavyWeight Split Rolls	15"x150'	2	49.8 gal.
WRF150M	MediumWeight Roll	30"x150'	1	39.5 gal.
WRSF150M	MediumWeight Split Rolls	15"x150'	2	39.5 gal.

**Blue Oil-Only** (for oils, not water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
BPF100H	HeavyWeight Pads	15"x19"	100	26.3 gal.
BPF100H-BX	HeavyWeight Pads in Box	15"x19"	100	26.3 gal.
BPKF50H	HeavyWeight King Pads	30"x30"	50	41.6 gal.
BPF200S	SingleWeight Pads	15"x19"	200	28.1 gal.
BRF150H	HeavyWeight Roll	30"x150'	1	49.8 gal.
BRF100H-BX	HeavyWeight Roll in Box	15"x100'	1	19.3 gal.

**Universal version also available.  
See pages 12-13.**

# FineFiber Mat Grips Floor



Sturdy 3-ply construction gives FineFiber Mat durability and absorbing power for longer wear and fewer changeouts.

## Sorbency for Where You Walk to Keep Your Floors Dry

### Grips Floor for Safety

Top and bottom layers of FineFiber are built of densely woven, small-diameter strands of fiber to increase surface area — enabling the Mat to grip the floor and secure it for safer walking. Universal application for oil, coolants, solvents and water.

### Virtually Indestructible

FineFiber Mat has a layer of MeltBlown polypropylene ultrasonically sandwiched between two FineFiber layers. 3-ply construction resists heavy foot traffic.

### High Sorbency Means It Stays on the Job Longer

Large-diameter MeltBlown polypropylene fibers create a high-loft inner layer that absorbs up to 33.7 ounces per 15" x 19" HeavyWeight Pad and 49.8 gallons per 150' HeavyWeight Roll.

### Multi-Perfs Save You Money

Rolls are perfed every 7.5" vertically and every 17" horizontally. Pads are perfed vertically at 7.5". Tear off only what you need — save money!

*(GRFF50H, GRF24150H & GPF20S are perfed at different intervals.)*

## Mat Index

Mat Name	Description	Page
<b>HighLoft Mat</b>	High sorbency for less	4
<b>MeltBlown Mat</b>	Quickly absorbs oil	6
<b>SonicBonded Mat</b>	Controls spills	8
<b>FineFiber Mat/Oil-Only</b>	Speeds cleanup	10
<b>FineFiber Mat/Universal</b>	Grips floor	12
<b>MultiLaminate Mat</b>	Lasts longer	14
<b>AirLaid Mat</b>	Our most flexible Mat	16
<b>SurvivorSeries™ Mat</b>	Our toughest Mat	18
<b>EcoTech™ Mat</b>	75% recycled content	20
<b>HazMat Mat</b>	For unknown liquids	22

You are here




Helps you comply with 29 CFR 1910.22(a)(2), 29 CFR 1910.107(b)(3), 29 CFR 1910.107(g)(2), 29 CFR 1910.120(j)(1) and 29 CFR 1910.1450(e). See page 67 for details.

The Technology Inside...


# FineFiber Mat

**Primary Use:**  
Foot Traffic Areas

**Primary Benefit:**  
Grips Floor for Safer Walking



Two (2) layers of FineFiber polypropylene are ultrasonically bonded around a high-loft MeltBlown core.



Oil-Only version also available.  
See pages 10-11.

## FineFiber Mat/Universal

### Green Universal (for oils, coolants, solvents & water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
GNPF100H	HeavyWeight Pads	15"x19"	100	26.3 gal.
GNPF100H-BX	HeavyWeight Pads in Dispenser Box	15"x19"	100	26.3 gal.
<b>NEW</b> GNPF100M	MediumWeight Pads	15"x19"	100	20.8 gal.
GNRF150H	HeavyWeight Roll	30"x150'	1	49.8 gal.
<b>NEW</b> GNRSF150H	HeavyWeight Split Rolls	15"x150'	2	49.8 gal.

### Gray Universal Pads (for oils, coolants, solvents & water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
GPF100H	HeavyWeight Pads	15"x19"	100	26.3 gal.
GPF1113H	HeavyWeight Pads	11"x13"	100	18.1 gal.
GPF100H-BX	HeavyWeight Pads in Dispenser Box	15"x19"	100	26.3 gal.
GPKF50H	HeavyWeight King Pads	30"x30"	50	41.6 gal.
GPF100M	MediumWeight Pads	15"x19"	100	20.8 gal.
GPF200S	SingleWeight Pads	15"x19"	200	28.1 gal.

### Gray Universal Rolls (for oils, coolants, solvents & water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
GRF150H	HeavyWeight Roll	30"x150'	1	49.8 gal.
GRF24150H	HeavyWeight Roll	24"x150'	1	39.8 gal.
GRF100H-BX	HeavyWeight Roll in Dispenser Box	15"x100'	1	19.3 gal.
GRSF150H	HeavyWeight Split Rolls	15"x150'	2	49.8 gal.
GRFF50H	HeavyWeight Folded Roll in Dispenser Box	5"x50'	1	8.4 gal.
GRF150M	MediumWeight Roll	30"x150'	1	39.5 gal.
GRSF150M	MediumWeight Split Rolls	15"x150'	2	39.5 gal.
GRF300S	SingleWeight Roll	30"x300'	1	53.4 gal.
GRSF300S	SingleWeight Split Rolls	15"x300'	2	53.4 gal.

## Drip, Rip and Go™ Tablet

### Gray Universal (for oils, coolants, solvents & water)

Item #	Description	Size	Tablets/Pkg	Absorbs/Pkg
GPF20S	Drip, Rip and Go™ Tablet	14.25"x19"	20 pads/tablet 9 tablets/pkg	25.2 gal.

# MultiLaminate Mat Lasts Longer



Use MultiLaminate Mat in places where long life and durability are important; ideal as a liner for oily parts and tools or for use in rugged applications near machinery.

## Mat Index

Mat Name	Description	Page
<b>HighLoft Mat</b>	High sorbency for less	4
<b>MeltBlown Mat</b>	Quickly absorbs oil	6
<b>SonicBonded Mat</b>	Controls spills	8
<b>FineFiber Mat/Oil-Only</b>	Speeds cleanup	10
<b>FineFiber Mat/Universal</b>	Grips floor	12
<b>MultiLaminate Mat</b>	Lasts longer	14
<b>AirLaid Mat</b>	Our most flexible Mat	16
<b>SurvivorSeries™ Mat</b>	Our toughest Mat	18
<b>EcoTech™ Mat</b>	75% recycled content	20
<b>HazMat Mat</b>	For unknown liquids	22

You are here



## Long-Lasting and Durable for Rugged Applications

### Tear-Resistant — Outlasts Standard Mats

Outer layers of tough-skinned, HeavyWeight SpunBond material resist abrasions and tears — can withstand rough handling and won't tear apart when pulled or positioned under equipment.

### Absorbent Inner Layer

MeltBlown inner layer draws and holds liquids from outer layers. Absorbs up to 37 oz. per 15" x 19" HeavyWeight Pad and 54.9 gallons per 150' HeavyWeight Roll. Choose Universal or Oil-Only.

### Low Lint for Sensitive Jobs

Outer SpunBond layers are constructed of continuous strands of polypropylene fibers — interwoven to virtually eliminate fibers from becoming detached and contaminating equipment, tools or parts.

### Multi-Perforations Save You Money

Rolls are perfed every 7.5" vertically and every 17" horizontally. Pads are perfed vertically at 7.5". Tear off only what you need — save money!




Helps you comply with 29 CFR 1910.22(a)(2), 29 CFR 1910.120(j)(1) and 29 CFR 1910.1450(e). See page 67 for details.

*The Technology Inside...*

# MultiLaminate Mat

**Primary Use:**  
Rugged Applications

**Primary Benefit:**  
Lasts Longer to Reduce Replacement Cost



## MultiLaminate Mat

**Gray Universal** (for oils, coolants, solvents & water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
<b>GPL100H</b>	HeavyWeight Pads	15"x19"	100	28.9 gal.
<b>GPL100M</b>	MediumWeight Pads	15"x19"	100	23.4 gal.
<b>GRL150H</b>	HeavyWeight Roll	30"x150'	1	54.9 gal.
<b>GRSL150H</b>	HeavyWeight Split Rolls	15"x150'	2	54.9 gal.
<b>GRL150M</b>	MediumWeight Roll	30"x150'	1	44.4 gal.
<b>GRSL150M</b>	MediumWeight Split Rolls	15"x150'	2	44.4 gal.

**White Oil-Only** /  **Blue Oil-Only** (for oils, not water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
<b>WPL100H</b>	HeavyWeight Pads	15"x19"	100	28.9 gal.
<b>WPL100M</b>	MediumWeight Pads	15"x19"	100	23.4 gal.
<b>WRL150H</b>	HeavyWeight Roll	30"x150'	1	54.9 gal.
<b>NEW WRSL150H</b>	HeavyWeight Split Rolls	15"x150'	2	54.9 gal.
<b>WRL150M</b>	MediumWeight Roll	30"x150'	1	44.4 gal.
<b>WRSL150M</b>	MediumWeight Split Rolls	15"x150'	2	44.4 gal.
<b>BPL100H</b>	HeavyWeight Pads	15"x19"	100	28.9 gal.

To order, please contact your local Distributor.

See Complete Product SpecSheet on pages 58-66.

# AirLaid Mat For Tight Spaces & Wiping

**SpillTech  
Exclusive**



AirLaid Mat crumples and conforms to better suit your tight sorbent or wiping application.

## Conforms to Your Application — Unlimited Flexibility

### Crumples, Fits or Wraps to Any Job

Resilient, recycled polypropylene fibers are “AirLaid” between two layers of tough SpunBond; ideal for tight spots and wrapping pipes and other equipment.

### High Sorbency Stays on the Job Longer

Inner layer of air-filled polypropylene fibers creates uniform pockets of air that attract and hold liquids. Absorbs up to 39.8 ounces per 15" x 19" Pad and 60 gallons per 150' Roll.

### Durable for Everyday Use

Ultrasonic bonding of two abrasion-resistant SpunBond layers around loose fibers gives the Mat added strength.

### Perforations Save Money

Rolls are perforated vertically at 15" and horizontally every 17". Tear off only what you need — save money! AirLaid Pads are not perforated.

### Color-Coded

Use Gray for universal applications; use White for oil-only jobs.

## Mat Index

Mat Name	Description	Page
<b>HighLoft Mat</b>	High sorbency for less	4
<b>MeltBlown Mat</b>	Quickly absorbs oil	6
<b>SonicBonded Mat</b>	Controls spills	8
<b>FineFiber Mat/Oil-Only</b>	Speeds cleanup	10
<b>FineFiber Mat/Universal</b>	Grips floor	12
<b>MultiLaminate Mat</b>	Lasts longer	14
<b>AirLaid Mat</b>	Our most flexible Mat	16
<b>SurvivorSeries™ Mat</b>	Our toughest Mat	18
<b>EcoTech™ Mat</b>	75% recycled content	20
<b>HazMat Mat</b>	For unknown liquids	22


You are here

**HYC** Helps you comply with 29 CFR 1910.22(a)(2), 29 CFR 1910.120(j)(1) and 29 CFR 1910.1450(e). See page 67 for details.

*The Technology Inside...*  
**AirLaid Mat**

**Primary Use:**  
Absorbing in Tight Spaces  
and Wiping Applications

**Primary Benefit:**  
Cleans a Variety of Surfaces



Two (2) layers of laminate SpunBond polypropylene are ultrasonically bonded around a high-loft AirLaid polypropylene core.



**AirLaid Mat**

**Gray Universal** (for oils, coolants, solvents & water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
<b>GPA100H</b>	HeavyWeight Pads	15"x19"	100	31.1 gal.
<b>GPKA50H</b>	HeavyWeight King Pads	30"x30"	50	49.3 gal.
<b>GRA150H</b>	HeavyWeight Roll	30"x150'	1	60.0 gal.
<b>GRSA150H</b>	HeavyWeight Split Rolls	15"x150'	2	60.0 gal.

**White Oil-Only** (for oils, not water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
<b>WPA100H</b>	HeavyWeight Pads	15"x19"	100	31.1 gal.
<b>WPKA50H</b>	HeavyWeight King Pads	30"x30"	50	49.3 gal.
<b>WRA150H</b>	HeavyWeight Roll	30"x150'	1	60.0 gal.
<b>WRSA150H</b>	HeavyWeight Split Rolls	15"x150'	2	60.0 gal.

# SurvivorSeries™ Mat Strong for the Toughest Jobs

**SpillTech  
Exclusive**



All-In-One SurvivorSeries™ Mat is ready for your toughest jobs. Choose Universal Gray or Oil-Only White versions.

## Mat Index

Mat Name	Description	Page
<b>HighLoft Mat</b>	High sorbency for less	4
<b>MeltBlown Mat</b>	Quickly absorbs oil	6
<b>SonicBonded Mat</b>	Controls spills	8
<b>FineFiber Mat/Oil-Only</b>	Speeds cleanup	10
<b>FineFiber Mat/Universal</b>	Grips floor	12
<b>MultiLaminate Mat</b>	Lasts longer	14
<b>AirLaid Mat</b>	Our most flexible Mat	16
<b>SurvivorSeries™ Mat</b>	Our toughest Mat	18
<b>EcoTech™ Mat</b>	75% recycled content	20
<b>HazMat Mat</b>	For unknown liquids	22

You are here

For more help choosing the right sorbent Mat, see our **Mat Selection Guide** on page 3.

## Rugged Mat Survives the Punishment of Everyday Wear and Tear

### Built-in Layers for Long Lasting Reliability

This innovative Mat features a SpunBond top layer that wicks liquids away into the MeltBlown core where it is trapped to keep the Mat and floors safe and dry. The bottom layer is built of densely woven strands of FineFiber to increase surface area, enabling the Mat to grip the floor and securing it for safer walking. All layers are ultrasonically bonded together for durability and resistance to wear in high traffic areas.

Strong and long-wearing, SurvivorSeries™ Mat stays on the job so you use less and save money!

### Three Mat Versions for Any Application

Camouflage SurvivorSeries™ Mat hides leaks and drips of oils, water and solvents; All-In-One SurvivorSeries™ Mat comes in grunge-hiding Gray for universal jobs or bright White for oil-only applications.

See the next page for more information on each version of SurvivorSeries™ Mat.

**HYC** Helps you comply with 29 CFR 1910.22(a)(2), 29 CFR 1910.107(b)(3), 29 CFR 1910.107(g)(2), 29 CFR 1910.120(j)(1) and 29 CFR 1910.1450(e). See page 67 for details.

*The Technology Inside...*


# SurvivorSeries™ Mat

**Primary Use:**  
For High-Traffic Areas

**Primary Benefit:**  
Withstands Abuse from Rugged Applications



Top (SpunBond) and bottom (FineFiber) layers of polypropylene are ultrasonically bonded around a high-loft MeltBlown core.



Use All-In-One SurvivorSeries™ Mat as a Roll...



... fold along the scores to shape a Sock ...



... or tear it along the perfs to create a Pad.

## Camouflage SurvivorSeries™ Mat

**Camouflage Design Makes Leaks and Drips Disappear**

SpillTech's innovative StealthTechnology makes leaks and drips disappear by drawing and trapping liquids in the inner MeltBlown layer. The top camouflage layer stays clean and dry, so you don't have to replace the Mat as often — and that saves you money!

Pads are perfed vertically every 7.5"; Rolls are perfed every 7.5" vertically and every 17" horizontally.

**High Sorbency and Multi-Perforations**

Absorbs up to 23.6 ounces per 15" x 19" Pad and up to 49.8 gallons per 150' Roll.



### SurvivorSeries™ Mat / Universal

**Camouflage** (for oils, coolants, solvents & water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
SVP100H	HeavyWeight Pads	15"x19"	100	17.9 gal.
SVR150H	HeavyWeight Roll	30"x150'	1	35.8 gal.
SVRS150H-1	HeavyWeight Split Roll	15"x150'	1	17.9 gal.
SVRS150H-2	HeavyWeight Split Rolls	15"x150'	2	35.8 gal.

## All-In-One SurvivorSeries™ Mat

**Versatile All-In-One Mat is a Roll, Pad and Sock**

One product is all you need! Use conveniently-packaged All-in-One SurvivorSeries™ Mat Roll as a Roll, Pad or a Sock. Handy dispenser box keeps Mat clean and can be stored anywhere for easy access.

**High Sorbency and Multi-Perforations**

Absorbs up to 18.1 gallons per Roll — choose Universal or Oil-Only absorbency. Perfed every 3.75" vertically and every 17" horizontally for increased versatility.

GRSMF100H-BX



WRSMF100H-BX



### SurvivorSeries™ Mat / Universal

**Gray Universal** (for oils, coolants, solvents & water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
GRSMF100H-BX	HeavyWeight Roll in Box	15"x100'	1	18.9 gal.

### SurvivorSeries™ Mat / Oil-Only

**White Oil-Only** (for oils, not water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
WRSMF100H-BX	HeavyWeight Roll in Box	15"x100'	1	18.9 gal.

# EcoTech™ Mat

## 75% Recycled Content

**SpillTech  
Exclusive**



High-capacity EcoTech™ Mat features recycled fibers that accelerate wicking to absorb large quantities fast.

### **Strong and Sorbent for a Cleaner, Greener Facility**

#### **75% Recycled Newsprint**

Our exclusive cellulose blend is an eco-friendly alternative to polypropylene mats. The recycled fibers disperse liquid evenly, allowing mat to absorb up to 16 times its own weight!

#### **Universal Sorbency**

EcoTech™ Mat absorbs oils, coolants, solvents and water. Not recommended for use with acids, bases or other aggressive liquids.

#### **Perforated to Save Money**

Rolls are perforated every 19" horizontally and

15" vertically. Pads are perforated at 7.5" vertically. Tear off only what you need to save money.

#### **Flame Tested for Safety**

EcoTech™ Mat is tested in accordance with ASTM Standard E84-08.

#### **Reduced Waste**

Mat can be incinerated after use to reduce waste or for fuels blending; reduces the need to landfill used absorbents.

#### **Multiple Versions Available**

Choose Pads or Rolls in Light- or HeavyWeight Mat.

## Mat Index

Mat Name	Description	Page
<b>HighLoft Mat</b>	High sorbency for less	4
<b>MeltBlown Mat</b>	Quickly absorbs oil	6
<b>SonicBonded Mat</b>	Controls spills	8
<b>FineFiber Mat/Oil-Only</b>	Speeds cleanup	10
<b>FineFiber Mat/Universal</b>	Grips floor	12
<b>MultiLaminate Mat</b>	Lasts longer	14
<b>AirLaid Mat</b>	Our most flexible Mat	16
<b>SurvivorSeries™ Mat</b>	Our toughest Mat	18
<b>EcoTech™ Mat</b>	75% recycled content	20
<b>HazMat Mat</b>	For unknown liquids	22

You are here

**HYC** Helps you comply with 29 CFR 1910.22(a)(2), 29 CFR 1910.107(b)(3), 29 CFR 1910.107(g)(2), 29 CFR 1910.120(j)(1) and 29 CFR 1910.1450(e). See page 67 for details.

*The Technology Inside...*

# EcoTech™ Mat


**Primary Use:**

Soaking Up Machine Leaks and Overspray

**Primary Benefit:**

Recycled Content is Better for the Environment

EcoTech™  
Cellulose



Single layer of eco-friendly  
75% recycled cellulose.



## EcoTech™ Mat / Universal

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
<b>NEW UCP100HW</b>	HeavyWeight Pads	15"x19"	100	30.2 gal.
<b>NEW UCP100LW</b>	LightWeight Pads	15"x19"	100	21.2 gal.

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
<b>NEW UCR150HW</b>	HeavyWeight Roll	30"x150'	1	57.2 gal.
<b>NEW UCR150LW</b>	LightWeight Roll	30"x150'	1	40 gal.

To order, please contact your local Distributor.

See Complete Product  
SpecSheet on pages 58-66.

# HazMat Products For Unknown Liquids



HazMat Mat absorbs caustic, hazardous or unknown liquids quickly and efficiently, before they spread.

## HazMat Sorbents for Acids, Bases and Unknown Liquids

When hazardous or unknown liquids spill, use HazMat Sorbent Products for quick, efficient response.

### HazMat Booms

Contain and absorb large-volume spills. Choose 5" or 8" diameters in a 10' length.

### HazMat Pads and Rolls

100% polypropylene absorbs most aggressive or caustic fluids. Ultrasonically bonded "dimples" add strength and fast-wicking power.

### HazMat Pillows

Easy to deploy, quick to absorb and able to hold over a gallon of liquid each. Surface area and sizeable amount of sorbent filler lets you attack large spills with speed and efficiency.

### HazMat Socks

Used to contain and absorb hazardous or unknown spills. Keep fluids from spreading to larger areas. Available in 3" diameter with lengths of 4', 8' and 12'.

### Color-Coded

All HazMat Sorbents are color-coded in safety yellow for quick identification.

## Mat Index

Mat Name	Description	Page
<b>HighLoft Mat</b>	High sorbency for less	4
<b>MeltBlown Mat</b>	Quickly absorbs oil	6
<b>SonicBonded Mat</b>	Controls spills	8
<b>FineFiber Mat/Oil-Only</b>	Speeds cleanup	10
<b>FineFiber Mat/Universal</b>	Grips floor	12
<b>MultiLaminate Mat</b>	Lasts longer	14
<b>AirLaid Mat</b>	Our most flexible Mat	16
<b>SurvivorSeries™ Mat</b>	Our toughest Mat	18
<b>EcoTech™ Mat</b>	75% recycled content	20
<b>HazMat Mat</b>	For unknown liquids	22




Helps you comply with 29 CFR 1910.120(j)(1), 29 CFR 1910.1450(e), 40 CFR 263.31 and 40 CFR 263.30(a). See page 67 for details.

The Technology Inside...  
**HazMat Mat**

**Primary Use:**  
Absorbing Caustic and Unknown Fluids

**Primary Benefit:**  
Safety Yellow Color for Quick Identification in an Emergency



**HazMat/SonicBonded** — One (1) layer of lint-free SpunBond fabric is ultrasonically bonded to one (1) layer of MeltBlown sorbent.

**HazMat/FineFiber** — Two (2) layers of FineFiber polypropylene are ultrasonically bonded around a high-loft MeltBlown core.



Socks, Booms and Pillows are made from recycled content.



HazMat

**HazMat Mat**

**Yellow SonicBonded Mat** (for acids, bases & unknown liquids)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
YPB100H	HeavyWeight Pads	15"x19"	100	29.1 gal.
YPB50H	HeavyWeight Pads	15"x19"	50	14.6 gal.
YPB100M	MediumWeight Pads	15"x19"	100	24.7 gal.
YPB50M	MediumWeight Pads	15"x19"	50	12.4 gal.
YPB200S	SingleWeight Pads	15"x19"	200	31.1 gal.
YPB100S	SingleWeight Pads	15"x19"	100	15.6 gal.
YRB150H	HeavyWeight Roll	30"x150'	1	55.2 gal.
YRSB150H	HeavyWeight Split Rolls	15"x150'	2	55.2 gal.
YRB150M	MediumWeight Roll	30"x150'	1	46.1 gal.

**Yellow FineFiber Mat** (for acids, bases & unknown liquids)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
YPF100H	HeavyWeight Pads	15"x19"	100	26.3 gal.
YPF1113H	HeavyWeight Pads	11"x13"	100	18.1 gal.
YRF150H	HeavyWeight Roll	30"x150'	1	49.8 gal.
YRSF150H	HeavyWeight Split Rolls	15"x150'	2	49.8 gal.

**HazMat Socks, Booms and Pillows**

**Yellow Socks and Booms** (for acids, bases & unknown liquids)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
YSO410	HazMat Socks	3"x4'	10	8.33 gal.
YSO430	HazMat Socks	3"x4'	30	25 gal.
YSO815	HazMat Socks	3"x8'	15	25 gal.
YSO1210	HazMat Socks	3"x12'	10	25 gal.
HZ510SN	HazMat Booms	5"x10'	4	23.3 gal.
HZ810SN	HazMat Booms	8"x10'	4	33.9 gal.

**Yellow Pillows** (for acids, bases & unknown liquids)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
YPIL818	HazMat Pillows	8"x18"	20	26.8 gal.
YPIL1818	HazMat Pillows	18"x18"	10	29.1 gal.

**Acid Neutralizing Loose Sorbent also available.**  
See pages 33 and 46.



## DrumTop Pads

### Say Goodbye to Messy Drum Tops

Absorb drips from leaking pumps and help keep drum storage areas looking good. Pre-cut bung holes make for easy access to drum.

Pads can be removed and replaced with pumps and valves installed. Made from top-quality FineFiber Mat.

Choose Gray Universal or Blue Oil-Only version.



### DrumTop Pads

**Gray Universal** (for oils, coolants, solvents & water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
<b>GTOP</b>	Universal DrumTop Pads	23" diam.	25	8.6 gal.

**Blue Oil-Only** (for oils, not water)

<b>BTOP</b>	Oil-Only DrumTop Pads	23" diam.	25	8.6 gal.
-------------	-----------------------	-----------	----	----------

Specialty Products

## Sorbent Mat Wringer

### Wringer Reclaims Up to 90% of Fluid

Use this Wringer to squeeze and recover up to 90% of absorbed fluids from most sorbent mats. All-steel, rustproof frame is virtually indestructible. Adjustable screws balance pressure over the length of the roller.



### Sorbent Mat Wringer

Item #	Description	Size	Units/Pkg
<b>A-WRINGER</b>	Sorbent Mat Wringer	15"Wx12"H	1

## Pad Box

Some carriers upcharge for shipping bales in bags. A simple solution! Our cardboard Pad Box perfectly fits one bale of Pads to both protect the sorbents and eliminate any shipping concerns. Ships in broken down format to your location.



### Pad Box

Item #	Description	Size	Units/Pkg	Weight/Pkg
<b>A-PADBOX</b>	Pad Box	15.5"Lx19.25"Wx16"H	1	3 lbs.


## Free-Standing RollRack

This free-standing RollRack keeps rolls off messy floors for easy access when you need it. Fits any roll up to 40" wide.



### Free-Standing RollRack


Item #	Description	Size	Units/Pkg
<b>A-ROLLRACK</b>	Free-Standing RollRack	For rolls up to 40"W	1



## PolyBacked Rug Roll

### Absorbent Roll Keeps Floors Dry

A top layer of high-strength needlepunched polypropylene fibers is backed with a liquid barrier to keep fluids from seeping through — also provides non-skid characteristics for safety.



**HYC** Helps you comply with 29 CFR 1910.22(a)(2), 29 CFR 1910.107(b)(3) and 29 CFR 1910.107(g)(2). See page 67 for details.

PolyBacked Rug Roll				
Item #	Description	Size	Units/Pkg	Absorbs/Pkg
PBR100	PolyBacked Rug Roll	36"x100'	1	13.0 gal.

## RigMat Rolls

Save Your Site Costly Cleanups by Stopping Mess before It Starts!

A tough top layer of Spunbond stands up to vehicle traffic, making RigMat ideal for service rigs, sucker rod maintenance, wellhead maintenance, cleaner drilling and clean compressor houses. Lay two 12'-long pieces next to each other to create a standard-sized 9.5' x 12' Mat.

MeltBlown polypropylene is left in its natural hydrophobic state to repel water but still absorb oils.

Choose a standard roll or a roll with an impenetrable, chemical-resistant poly back to prevent liquids from seeping through.

**NEW**

RIG160H

PBRIG48H



**HYC** Helps you comply with 29 CFR 1910.22(a)(2) and 29 CFR 1910.120(j)(1). See page 67 for details.

Rig Mat				
Item #	Description	Size	Units/Pkg	Absorbs/Pkg
<b>NEW</b> RIG160H	HeavyWeight Roll	58"x160'	1	142.7 gal.
<b>NEW</b> PBRIG48H	HeavyWeight PolyBacked Roll	57"x48'	1	44.1 gal.

Specialty Products

## PolyBacked Pads and Rolls


### Added Protection for Your Floors

The strength of our signature FineFiber Mats combines with the liquid-stopping power of an impenetrable, chemical-resistant poly backing for liquid- and stain-free floors. Poly backing also provides non-skid characteristics for safety.



PBGRF100H

PBGPF50H



PBGRF100H

**PolyBacked Mat**  
**Gray Universal** (for oils, coolants, solvents & water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
PBGPF50H	HeavyWeight Pads	15"x19"	50	8.1 gal.
PBGRF100H	HeavyWeight Roll	30"x100'	1	18.0 gal.

**HYC** Helps you comply with 29 CFR 1910.22(a)(2), 29 CFR 1910.107(b)(3) and 29 CFR 1910.107(g)(2). See page 67 for details.



NPR300S-GR

## NeedlePunch Rug

### Heavy-duty Rug Even Survives Forklift Traffic

A tough nonwoven fabric constructed of 100% needle-punched polypropylene. Designed to absorb oil, coolants, solvents and water while standing up to rugged wear and tear. Perfect for areas with heavy foot traffic.

### Two Weights to Match Your Application

NeedlePunch Rug comes in 8 oz. and 16 oz. weights so you can always use the appropriate weight of Rug for your specific application. Gray color hides grunge so it stays down longer, and saves you money.

**HYC** Helps you comply with 29 CFR 1910.22(a)(2), 29 CFR 1910.107(b)(3) and 29 CFR 1910.107(g)(2). See page 67 for details.

NeedlePunch Rug				
Item #	Description	Size	Units/Pkg	Absorbs/Pkg
NPR150H-GR	NeedlePunch Rug - 16 oz. gray	36"x150'	1	54.0 gal.
NPR300S-GR	NeedlePunch Rug - 8 oz. gray	36"x300'	1	54.0 gal.



RRUG36H

## RagRug

### Sturdy — Takes a Beating Even in High-Traffic Areas

This Mat is made from recycled polypropylene and acrylic fibers, making it a great choice for use in areas where steady foot traffic might wear out an ordinary mat or rug that's become soaked with overspray.

solvents and water without looking dirty.

### Lasts Longer, so You Use and Spend Less

Because this durable Mat stands up to high-traffic abuse longer than regular mat, you can use it longer, which saves you money!

### Huge Sorbent Capacity

One 36"x150' roll is capable of taking in up to 84.6 gallons of liquid!

### Tough Rug Stands Up to Punishment

No matter where you place this Mat, the high tensile strength lets it take all types of abuse even when it's fully saturated with fluids.

### Dark Color Hides Grime

Dark-colored Mats absorb the grunge from oil, coolants,



RRUG36H


RRUG18H

RRUG100H

**NEW**

**HYC** Helps you comply with 29 CFR 1910.22(a)(2), 29 CFR 1910.107(b)(3) and 29 CFR 1910.107(g)(2). See page 67 for details.

RagRug				
Item #	Description	Size	Units/Pkg	Absorbs/Pkg
RRUG36H	RagRug Roll	36"x150'	1	84.6 gal.
RRUG18H	RagRug Split Rolls	18"x150'	2	84.6 gal.
NEW RRUGP100H	RagRug Pads	18"x18"	100	38.9 gal.



## StitchBonded Mat

### Ready for Rough Traffic

This tough Mat stays put and won't slide. Constructed from specially stitched polypropylene to withstand even the roughest foot traffic. A true performer for heavy traffic areas.

### Handles Heavy Wear

Because this Mat will take a beating while absorbing all types of fluids, it's ideal for situations where durability is an issue. Place it in walkways and areas that need to be clean, dry and safe all the time.

### Tough Construction

This Mat is tough because of its zig-zag stitching. SpillTech took its regular Mat and added tight rows of stitching to create a Mat that stands up to heavy abuse but still provides the hard-working absorption power of regular SpillTech® Mat.

### Long Life Saves Money

This is a strong, durable Mat that can stand up to heavy abuse — that means you can leave it down much longer than regular Mat, so you save money!

**HYC** Helps you comply with 29 CFR 1910.22(a)(2), 29 CFR 1910.107(b)(3) and 29 CFR 1910.107(g)(2). See page 67 for details.

StitchBonded Mat				
Item #	Description	Size	Units/Pkg	Absorbs/Pkg
MR2069	StitchBonded Mat Roll	33"x150'	1	23.0 gal.

Specialty Products


## TrackMat Rolls

Prevent Ground Contamination during Railroad Maintenance

**NEW**

Oil-Only TrackMat features a highly absorbent MeltBlown core that quickly soaks up and retains oils, lubricants and other petroleum-based liquids but repels water. Heavy-duty Spunbond top layer adds strength and durability. Thick bottom layer of polypropylene prevents liquids from leaching into the ground below; clear material shows saturation level at a glance.

TMAT57 is sized to fit between standard railroad track rails; TMAT19 is ideal for outside rails.



## RailRoad Mat

Provides Sorbency and Spill Protection in Rail-Specific Applications

A tier of sorbent MeltBlown material is top-layered with needle-punched felt for strength, and then poly-backed with a chemical-resistant material. 59"-wide Roll fits between rails; 19"-wide Rolls cover ground outside rails for total protection.

**HYC** Helps you comply with 29 CFR 1910.120(j)(1), 40 CFR 263.30(a) and 40 CFR 263.31. See page 67 for details.

**HYC** Helps you comply with 29 CFR 1910.120(j)(1), 40 CFR 263.30(a) and 40 CFR 263.31. See page 67 for details.

TrackMat				
Item #	Description	Size	Units/Pkg	Absorbs/Pkg
NEW TMAT57	HeavyWeight Roll for inside rails	57"x80'	1	63.2 gal.
NEW TMAT19	HeavyWeight Split Rolls for outside rails	19"x80'	2	41.7 gal.

RailRoad Mat				
Item #	Description	Size	Units/Pkg	Absorbs/Pkg
RRMAT60	RailRoad Mat Roll	59"x100'	1	59.0 gal.
RRMAT19	RailRoad Mat Rolls	19"x100'	2	38.0 gal.

# Sorbent Socks For Fast Containment

Specialty Products



Helps you comply with 29 CFR 1910.120(j)(1), 40 CFR 112.7(c)(1), 40 CFR 263.30(a) and 40 CFR 263.31. See page 67 for details.

## Oil-Only Socks



### Oil-Only Socks Absorb Oils, Repel Water

For oil-only cleanup, choose these Socks. By selectively absorbing oil and not water, these 100% polypropylene-filled Socks absorb more oil and can be left on the job longer.



What's Inside:

## HazMat Socks



### Use HazMat Socks for Caustic Fluids

These 100% polypropylene-filled Socks soak up nearly any type of caustic or unknown fluid — acids, bases, solvents and chemicals. Color-coded yellow so you know exactly what you're reaching for in an emergency spill situation.



What's Inside:

### Oil-Only Socks

(for oils, not water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
WS0410	Oil-Only Socks	3"x4'	10	8.33 gal.
WS0430	Oil-Only Socks	3"x4'	30	25.0 gal.
WS0815	Oil-Only Socks	3"x8'	15	25.0 gal.
WS01210	Oil-Only Socks	3"x12'	10	25.0 gal.

### HazMat Socks

(for acids, bases & unknown liquids)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
YS0410	HazMat Socks	3"x4'	10	8.33 gal.
YS0430	HazMat Socks	3"x4'	30	25.0 gal.
YS0815	HazMat Socks	3"x8'	15	25.0 gal.
YS01210	HazMat Socks	3"x12'	10	25.0 gal.

## Universal Socks

### Universal Socks — A Solid Performer in a Variety of Situations

These durable, universal-application, 100% polypropylene-filled Socks absorb oils, coolants, solvents and water. Use wherever you have a variety of spills and only want to stock one sock to cover everything. Socks easily mold to almost any shape.



### Universal Socks

(for oils, coolants, solvents & water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
<b>GS0430</b>	Universal Socks	3"x4'	30	25.0 gal.
<b>GS0815</b>	Universal Socks	3"x8'	15	25.0 gal.
<b>GS01210</b>	Universal Socks	3"x12'	10	25.0 gal.

Specialty Products

## CornCob Socks

### CornCob Socks Tackle Tough Jobs and Provide an Affordable Alternative to Messy Clay

These economical and highly efficient Socks can tackle even the toughest jobs. With a tough polypropylene skin and finely ground corn cob filler, these Socks absorb ½ gallon of oil, coolants, solvents and water — nearly twice as much as clay, but without the dust or the mess to clean up afterward. Plus they're incinerable. Unlike clay, you won't need a shovel for this cleanup!



### CornCob Socks


(for oils, coolants, solvents & water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
<b>CCS040</b>	CornCob Socks	3"x42"	40	20.0 gal.

## Cellulose Socks

### Super-Absorbent Cellulose Socks Soak Up More Than One Gallon per 4'

These are very thirsty Socks — a single 4' Sock can absorb more than a gallon of liquid, making this a true top performer. Very flexible construction allows you to place this Sock in a variety of positions around spills or leaking machinery.



### Cellulose Socks

(for oils, coolants, solvents & water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
<b>GCS0430</b>	Cellulose Socks	3"x4'	30	32.3 gal.
<b>GCS0815</b>	Cellulose Socks	3"x8'	15	32.3 gal.
<b>GCS01210</b>	Cellulose Socks	3"x12'	10	32.3 gal.

# Pillows and Pans For High-Volume Leaks

Specialty Products



### Pillows Absorb Fluids in Tight Spaces

Pillows are easy to place in hard-to-reach areas — use under machines and leaky hydraulic hoses or wedge in corners cramped for space.

### One Product for a Variety of Uses

Pulls liquids from the floor like a sock. Catches leaks like a pan. Absorbs spills like a pad. It's one versatile product that works for many different jobs.


### Absorb Large Quantities ... Quickly

Ideal for spill response. Easy to toss into action. Pillow's large surface area speeds the absorption process and shortens the overall response time.

### Color-Coded

Grunge-hiding Gray for universal applications and bright White for oil-only cleanup. Quick to identify and easy to deploy.

*See pages 22–23 for HazMat Pillows.*



**HYC** Helps you comply with 29 CFR 1910.120(j)(1), 33 CFR 154.1047(c)(2), 40 CFR 112.7(c)(1), 40 CFR 263.30(a) and 40 CFR 263.31. See page 67 for details.

## Pillows

Gray Universal (for oils, coolants, solvents & water)				
Item #	Description	Size	Units/Pkg	Absorbs/Pkg
GPIL1818	Universal Pillows	18"x18"	10	29.1 gal.
GPIL818	Universal Pillows	8"x18"	20	26.8 gal.

White Oil-Only (for oils, not water)				
Item #	Description	Size	Units/Pkg	Absorbs/Pkg
WPIL1818	Oil-Only Pillows	18"x18"	10	29.1 gal.
WPIL818	Oil-Only Pillows	8"x18"	20	26.8 gal.



GPIL1224

GPIL1010



Helps you comply with 29 CFR 1910.22(a)(2). See page 67 for details.

## Pillow in a Pan

### Reusable and Economical

For an economical solution to high-volume leaks and drips, try this Pillow in a Pan. When saturated, you simply replace the Pillow and reuse the Pan.

### Efficient, Cost-Effective

Each Pillow absorbs up to 3 quarts of liquid — oils, coolants, solvents and water. This kind of efficiency makes the Pillow in a Pan an ideal choice for catching recurring or continuous high-volume leaks.


### Makes a Great “Quick Response” Absorbent

No preparation required. Simply set it in place, and watch it go to work. With high absorbency and a holding depth of 3", the Pillow in a Pan provides the volume capacity you need to handle a variety of sorbency situations.

### Pillow in a Pan

Gray Universal (for oils, coolants, solvents & water)				
Item #	Description	Size	Units/Pkg	Absorbs/Pkg
GPIL1224	Universal Pillow in a Pan	10.5" sq. x3"H	12 pans & 24 pillows	20.7 gal.
GPIL1010	Replacement Universal Pillows	10" sq.	40	24 gal.
White Oil-Only (for oils, not water)				
WPIL1224	Oil-Only Pillow in a Pan	10.5" sq. x3"H	12 pans & 24 pillows	20.7 gal.
WPIL1010	Replacement Oil-Only Pillows	10" sq.	40	24 gal.

Specialty Products



DPU-16

## DripPan

### Low-Profile for Heavy Leaks

Use a high-volume, low-profile DripPan under machines and hydraulic hoses, or just place one under any high-volume leak or drip. If a mat becomes saturated too quickly, then use a DripPan instead.

### Much Better Than Clay

A DripPan is far more efficient than piling clay on the floor, and a snap to clean up. Just pick it up and dispose of it — no shoveling required!

### Absorb Large Amounts Fast

DripPan absorbs on contact. The large surface area and 3" depth provides the volume to handle heavy leaks or drips. And, its wide footprint keeps it stable, so you won't kick it over.

### Color-Coded

Use Gray Universal DripPan for general use around your workplace. White Oil-Only DripPan is ideal for outdoor use, where it catches oily drips but discharges rainwater.



Helps you comply with 29 CFR 1910.22(a)(2). See page 67 for details.

### DripPans


Gray Universal (for oils, coolants, solvents & water)				
Item #	Description	Size	Units/Pkg	Absorbs/Pkg
DPU-16	Universal DripPans	10.5" sq. x3"H	16	12.0 gal.
White Oil-Only (for oils, not water)				
DPO-16	Oil-Only DripPans	10.5" sq. x3"H	16	12.0 gal.

## WaterWick

**Pull Water from Fuel Tanks before it Causes Damage**

WaterWicks help preserve engine life and prevent frozen lines by removing water from fuel stores and minimizing filter-clogging rust and algae.

Ballast forces the WaterWick to bottom of your fuel tank, where unwanted water settles, and the highly absorbent filler pulls in water but repels gas and diesel fuel. The tough nylon line makes deployment and retrieval easy. Choose from four sizes.



### WaterWick

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
<b>NEW</b> WW10	WaterWick	1" Dia. x 9" L	1	3 oz.
<b>NEW</b> WW15	WaterWick	1.5" Dia. x 12" L	1	8 oz.
<b>NEW</b> WW20	WaterWick	2" Dia. x 12" L	1	12 oz.
<b>NEW</b> WW35	WaterWick	3.5" Dia. x 12" L	1	36 oz.

## Universal Boom

**Contain and Absorb Large Volumes of Liquid**

Strong mesh sleeve encases a poly sock skin filled with 100% highly sorbent polypropylene. Filler won't shed, even when saturated.

**Tough Construction**


A nylon rope and sturdy hardware ensure long-lasting durability and easy retrieval.

**Create Custom Sizes**

Metal connectors let you link Booms to create a containment system big enough to handle any spill.

**Universal Application**

Absorbs oils, coolants, solvents and water.



### Universal Boom

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
<b>NEW</b> GB510SN	Universal Booms	5" x 10'	4	23.3 gal.



## WellHead Socks

**Stop Oily Wellhead Problems at the Source**

Wrap this 5"W x 42"L Sock around a pump wellhead to stop oily leaks and drips at the wellhead pump site. Easy installation and removal — each Sock is secured in place

by an adjustable piece of hook-and-loop fastener. Oil-only Sock repels rainwater. Bright white color shows when Sock is saturated and needs to be replaced.



**HYC**



Helps you comply with 40 CFR 122.26 and 40 CFR 112.7(c)(1). See page 67 for details.

### WellHead Socks

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
<b>WSWH4210</b>	WellHead Socks	5" x 42"	10	27.5 gal.

**Gran-sorb®  
Loose Sorbent**

Recycled paper waste soaks up oils, coolants, solvents, water, fuels and antifreeze. Paper waste is completely safe, non-toxic and non-hazardous. A great alternative to clay.



**Loose CornCob**

A great all-purpose “workhorse” sorbent that works well on a variety of fluids — oils, coolants, solvents and water. Made from all-natural coarse corn cob — much lighter than clay.




**Lite-Zorb  
Loose Sorbent**

Recycled paper waste absorbs five times as much as clay, without the dust. Fast wicking, non-abrasive and non-toxic. A great choice for fast and efficient response to leaks and spills in almost any situation.



**SuperSorbent  
Loose Sorbent**

Instantly soaks up liquids to leave surfaces completely dry and reduce slip and fall injuries. Super-concentrated formula absorbs 10 to 12 times more than clay. 300% increased absorption capacity reduces cleanup time. Environmentally safe.



**Loose PeatMoss**

A natural oil-only sorbent that absorbs oil on land or hard surfaces. Made of biodegradable peat moss, which has a natural affinity for oils. This product can also be incinerated.




**Oil-Only Particulate**

White Oil-Only Particulate is made of loose polypropylene pulp for oil leaks and spills. This product floats on water, even when saturated, for absorbing oil spills on water.



**Acid Neutralizing Sorbent**

Visible color change signifies complete neutralization of acids; absorbs and solidifies liquids. Not for use with hydrofluoric acid. Environmentally friendly. Handy 5-gallon pail makes it easy to transport and dispense Sorbent.



**HYC** Helps you comply with 29 CFR 1910.22(a)(2). (Applies to all products on this page.) See page 67 for details.

**Loose Sorbents**

**Universal** (for oils, coolants, solvents & water)

Item #	Description	Size	Qty/Pallet	Absorbs/Pkg
CELL30*	Gran-sorb® Loose Sorbent	30-lb. Bag	65	4.0 gal.
COB40*	Loose CornCob	40-lb. Bag	50	8.5 gal.
MR1020*	Lite-Zorb Loose Sorbent	25-lb. Bag	80	5.4 gal.
SS12**	SuperSorbent Loose Sorbent	28-oz. Shakers (12)	60	7.0 gal.

**Oil-Only** (for oils, not water)

Item #	Description	Size	Qty/Pallet	Absorbs/Pkg
PEAT2*	Loose PeatMoss	2 cu. ft.	50	25.0 gal.
WPART*	Oil-Only Particulate	25-lb. Bag	15	58.1 gal.

**HazMat** (for acids & unknown liquids)

Item #	Description	Size	Qty/Pallet	Absorbs/Pkg
ANS5	Acid Neutralizing Sorbent	5-gal. Pail	40	2.5 gal.

\*Sold only in pallet quantities.

\*\*SS12 includes twelve 28-oz shakers; for one shaker, see SS1 on page 46.

Specialty Products

# Spill Response For Outdoor Oil Spills



Spill Response

## Take Control of Outdoor Spills with Booms, Sweeps and Special Sorbents

### Use Sock/Net Booms to Absorb and Contain Oil

Strong mesh outer sleeve encases a poly sock skin filled with highly-sorbent polypropylene. Filler won't shed and Booms won't sink, even when saturated with oil. A nylon rope and sturdy hardware ensure long-lasting durability and easy retrieval.

### Create Customized Sizes

Sock/Net Booms can be linked together to contain any size spill on water. Clip together with metal connector hardware.

### Special-Use Sorbents

Once a spill is contained, it's time for sorbents such as PomPoms, Net Bags, Sweeps and Particulates. These products are used on the surface to absorb spills and surface sheen. Because they're for oil only, they'll absorb the oil but won't become weighed down with water. This means you can leave them in place longer for maximum absorption.

*Oil-Only Pads also available. See pages 4, 6, 8, 10, 14, 16 and 18.*



WB818

WB8318

WB820SN

Durable, easy-to-use boom connectors provide a simple and efficient way to create a containment system big enough to handle almost any spill.



### Booms

(for oils, not water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
<b>NEW WB410SN</b>	Sock/Net Booms	4"x10'	4	19.5 gal.
<b>WB510SN</b>	Sock/Net Booms	5"x10'	4	30.0 gal.
<b>WB520SN</b>	Sock/Net Booms	5"x20'	2	30.0 gal.
<b>WB810SN</b>	Sock/Net Booms	8"x10'	4	38.0 gal.
<b>WB820SN</b>	Sock/Net Booms	8"x20'	2	38.0 gal.
<b>NEW WBB318</b>	Bilge Booms	3"x18"	20	6.25 gal.
<b>WBB818</b>	Bilge Booms	8"x18"	10	18.0 gal.

**HYC** Helps you comply with 33 CFR 154.1047(c)(2), 40 CFR 112.7(c)(1), 40 CFR 122.26 and 40 CFR 263.31. See page 67 for details.



## PomPoms

Thousands of thin strands of polypropylene are joined together to create this high-surface-area sorbent. Heavy oils adhere, water is repelled. Sold as 30 individual PomPoms or as 30 PomPoms connected on a 50' rope.

\*Actual color may vary.

### PomPoms

(for oils, not water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
APMPM	PomPoms/30 individual	n/a	30	11.6 gal.
APMPM-R	PomPoms/30 on 50' rope	n/a	1	11.6 gal.



## Net Bags

Polypropylene strips encased in a nylon mesh bag — used to absorb larger spills on water. Just toss it on the spill. Floats for easy retrieval — even when saturated.

### Net Bags

(for oils, not water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
WPIL10	Net Bags	6"Dx16"Wx21"H	10	37.0 gal.

Spill Response



What's Inside:

## Oil-Only Particulate

White Oil-Only Particulate is made of loose polypropylene pulp. Use to absorb oil on the surface of water bodies or on land-based oil spills.

### Oil-Only Particulate

(for oils, not water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
WPART	Oil-Only Particulate	25-lb. bag	1	58.1 gal.



## Folded Sweep

Sweep attaches to a sorbent boom to catch oily sheens that linger behind. Sturdy construction features nylon strap securely attached to durable MultiLaminate Mat.

### Folded Sweep

(for oils, not water)

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
WSWL100F	Folded Sweep	19"Wx100'L	1	16.2 gal.

## Containment Boom and Anchor System

**Non-Absorbent Boom Contains Spills and Debris above and below the Water.**


Boom floats above the water surface to contain and identify the spill location; skirt goes below the surface to contain oil and keep it from escaping. Features semi-flexible internal foam flotation with flexible PVC fabric skirt; extra-heavy hinge points provide stability, float integrity and durability in wave conditions.

Sold in 50' or 100' sections — order as much or as little as you need. Custom sizes also available (pricing may vary).

**Anchor System Keeps a Deployed Boom in Place for Optimum Containment**

Includes a 22 lb. Danforth-type anchor, 3/8" x 8' chain leader with 3/8" shackles, 80' poly rope (yellow) with thimble eyes and 1/2" shackle, Orange A2 Polyform Anchor Buoy with 1/2" shackle, 6' poly rope (yellow) painter line with thimble eyes and 1/2" shackle. Comes pre-assembled for quick and easy deployment.


*These items are drop-shipped from vendor.*



**NEW**


**C-BOOM10**

Light-weight, light-duty Boom is ideal in shallow areas with minimal flow.



**C-BOOM18**

Versatile, medium-duty Boom is ideal in areas with moderate to choppy flow.



**NEW**

**C-BOOM24**

Rugged, heavy-duty Boom is ideal in areas with fast, choppy flow.



Segmented float lets you fold Containment Boom for compact storage and easy transportation.



**C-ANCHOR**

**HYC** Helps you comply with 33 CFR 154.1047(c)(2) and 40 CFR 112.7(c)(1). (Applies to C-BOOM only.) See page 67 for details.

### Containment Boom & Anchor System

Item #	Description	Size	Units/Pkg
<b>NEW C-BOOM10-50*</b>	Containment Boom	50'Lx10"H (4" float, 6" skirt) 50'	1
<b>NEW C-BOOM10-100*</b>	Containment Boom	100'Lx10"H (4" float, 6" skirt) 100'	1
<b>C-BOOM18-50*</b>	Containment Boom	50'Lx18"H (6" float, 12" skirt) 50'	1
<b>C-BOOM18-100*</b>	Containment Boom	100'Lx18"H (6" float, 12" skirt) 100'	1
<b>NEW C-BOOM24-50*</b>	Containment Boom	50'Lx24"H (8" float, 16" skirt) 50'	1
<b>NEW C-BOOM24-100*</b>	Containment Boom	100'Lx24"H (8" float, 16" skirt) 100'	1
<b>C-ANCHOR</b>	Containment Boom Anchor System	22-lb. Anchor	1

\*Final product may be yellow or orange based on availability at time of order.

Specialty Products

# SPILL KITS FOR QUICK RESPONSE



Spill Kits



## Be Prepared for Fast Response with SpillTech® Spill Kits

### Quick Response is Key

Spills happen no matter how hard you try to avoid them. Forklifts knock over drums, tanks are punctured and transporters leak and drip. That's why it is important to have the right sorbents on-hand when these spills occur. A quick response is the first order of business — and your best weapon — in the fight against spills.

### Any Spill, Anywhere

Whether you need to clean up a dangerous chemical spill or eliminate a slip-and-fall hazard, SpillTech has a Spill

Kit for any size and type of spill — anywhere. Over the next 10 pages you'll find a wide range of Spill Kits and Accessories to meet your needs. And all SpillTech® Spill Kits are packed with quality SpillTech® Products to help you comply with the regulations listed below.

### Customized for You

If you don't see what you're looking for, we can even customize a Spill Kit to your exact specifications! See page 43 for details.

**HYC** HELPS YOU COMPLY WITH 29 CFR 1910.120(j)(1), 29 CFR 1910.1450(e), \*33 CFR 154.1047(c)(2), 40 CFR 263.30(A), 40 CFR 263.31, 49 CFR 173.3(c)(1). SEE PAGE 67 FOR DETAILS.

\* APPLIES TO OIL-ONLY SPILL KITS ONLY

## 95-Gallon Recycled Spill Kit

Contents pre-packed in a 100% Recycled polyethylene 95-Gallon OverPack. Sorbents are made with 100% Recycled Filler. Available for Universal and Oil-Only use. Refill available.

**Kit Contents:**

- 150 – 15"x19" Pads
- 6 – 3"x8' Socks
- 12 – 3"x4' Socks
- 7 – 18"x18" Pillows
- 4 – Yellow Disposal Bags & Ties
- 1 – Emergency Response GuideBook
- 1 – Spill Kit Label
- 3 – Tubs Plug & Dike
- 1 – Pair Goggles
- 2 – Pair Nitrile Gloves
- 6 – Tamper-Proof Labels

### 95-Gallon Recycled Spill Kits

Item #	Description	Refill Kit (contents only)
<b>NEW</b> <input checked="" type="checkbox"/> <b>SPKU-95-RC</b>	95-Gallon Recycled Kit/ <b>Universal</b>	<b>RSPKU-95-RC</b>
<b>NEW</b> <input type="checkbox"/> <b>SPKO-95-RC</b>	95-Gallon Recycled Kit/ <b>Oil-Only</b>	<b>RSPKO-95-RC</b>

Absorbs up to **87.0 Gallons**



SPKU-95-RC

**NEW**

## 95-Gallon Spill Kit

Contents pre-packed in X-rated DOT-approved 95-Gallon OverPack (UN 1H2/X295/S). Available for Universal, Oil-Only and HazMat use. Refill available.

**Kit Contents:**

- 150 – 15"x19" Pads
- 12 – 3"x4' Socks
- 2 – Pair Nitrile Gloves
- 3 – Tubs Plug & Dike
- 4 – Yellow Disposal Bags & Ties
- 1 – Emergency Response GuideBook
- 6 – 3"x8' Socks
- 7 – 18"x18" Pillows
- 1 – Spill Kit Label
- 1 – Pair Goggles
- 6 – Tamper-Proof Labels

### 95-GALLON SPILL KITS

Item #	Description	Refill Kit (Contents Only)
<input checked="" type="checkbox"/> <b>SPKU-95</b>	95-Gallon Kit/ <b>Universal</b>	<b>RSPKU-95</b>
<input type="checkbox"/> <b>SPKO-95</b>	95-Gallon Kit/ <b>Oil-Only</b>	<b>RSPKO-95</b>
<input checked="" type="checkbox"/> <b>SPKHZ-95</b>	95-Gallon Kit/ <b>HazMat</b>	<b>RSPKHZ-95</b>
<b>A95OVER</b>	Empty 95-Gallon OverPack (see p44)	N/A

Absorbs up to **84.0 Gallons**



SPKU-95

Spill Kits

## 95-Gallon Spill Kit with Wheels

Contents pre-packed in X-rated DOT-approved 95-Gallon OverPack (UN 1H2/X113/S) with two wheels and built-in handle. Available for Universal, Oil-Only and HazMat use. Refill available.

**Kit Contents:**

- 150 – 15"x19" Pads
- 12 – 3"x4' Socks
- 2 – Pair Nitrile Gloves
- 3 – Tubs Plug & Dike
- 4 – Yellow Disposal Bags & Ties
- 1 – Emergency Response GuideBook
- 6 – 3"x8' Socks
- 7 – 18"x18" Pillows
- 1 – Spill Kit Label
- 1 – Pair Goggles
- 6 – Tamper-Proof Labels

### 95-GALLON SPILL KITS WITH WHEELS

Item #	Description	Refill Kit (Contents Only)
<input checked="" type="checkbox"/> <b>SPKU-95-WD</b>	95-Gallon Kit/ <b>Universal</b> w/ Wheels	<b>RSPKU-95</b>
<input type="checkbox"/> <b>SPKO-95-WD</b>	95-Gallon Kit/ <b>Oil-Only</b> w/ Wheels	<b>RSPKO-95</b>
<input checked="" type="checkbox"/> <b>SPKHZ-95-WD</b>	95-Gallon Kit/ <b>HazMat</b> w/ Wheels	<b>RSPKHZ-95</b>
<b>A95OVER-WD</b>	Empty 95-Gallon OverPack w/ Wheels (see p44)	N/A

Absorbs up to **84.0 Gallons**



SPKU-95-WD

## 65-Gallon Spill Kit

Contents pre-packed in X-rated DOT-approved 65-Gallon OverPack (UN 1H2/X200/S). Available for Universal, Oil-Only and HazMat use. Content-only Refill Kit available.

**Kit Contents:**

- 40 – 15"x19" Pads
- 6 – 3"x8' Socks
- 10 – 3"x4' Socks
- 6 – 18"x18" Pillows
- 2 – Pair Nitrile Gloves
- 3 – Yellow Disposal Bags & Ties
- 1 – Pair Safety Goggles
- 1 – Spill Kit Label
- 6 – Tamper-Proof Labels

**SPKO-65**



Absorbs up to **47.4** Gallons

65-Gallon Spill Kits		
Item #	Description	Refill Kit (contents only)
SPKU-65	65-Gallon Kit/ <b>Universal</b>	RSPKU-65
SPKO-65	65-Gallon Kit/ <b>Oil-Only</b>	RSPKO-65
SPKHZ-65	65-Gallon Kit/ <b>HazMat</b>	RSPKHZ-65
A65OVER	Empty 65-Gallon OverPack (see p44)	n/a

## 50-Gallon Spill Kit

Contents pre-packed in X-rated DOT-approved 50-Gallon OverPack (UN 1H2/X125/S) with two wheels and built-in handle. Available for Universal, Oil-Only and HazMat use. Content-only Refill Kit available.

**Kit Contents:**

- 100 – 15"x19" Pads
- 6 – 3"x4' Socks
- 4 – 18"x18" Pillows
- 2 – Pair Nitrile Gloves
- 3 – Yellow Disposal Bags & Ties
- 1 – Emergency Response GuideBook
- 1 – 7" Epoxy Putty Stick
- 1 – 6" Light Stick
- 1 – Pair Safety Goggles
- 1 – Spill Kit Label
- 6 – Tamper-Proof Labels

**SPKHZ-50-WD**



Absorbs up to **45.7** Gallons

50-Gallon Spill Kits		
Item #	Description	Refill Kit (contents only)
SPKU-50-WD	50-Gallon Kit/ <b>Universal</b> w/ Wheels	RSPKU-50
SPKO-50-WD	50-Gallon Kit/ <b>Oil-Only</b> w/ Wheels	RSPKO-50
SPKHZ-50-WD	50-Gallon Kit/ <b>HazMat</b> w/ Wheels	RSPKHZ-50
A50OVER-WD	Empty 50-Gallon OverPack w/ Wheels (see p44)	n/a

## 30-Gallon Spill Kit

Contents pre-packed in X-rated DOT-approved 30-Gallon OverPack (UN 1H2/X100/S). Available for Universal, Oil-Only and HazMat use. Content-only Refill Kit available.

**Kit Contents:**

- 25 – 15"x19" Pads
- 4 – 3"x8' Socks
- 4 – 18"x18" Pillows
- 1 – Pair Nitrile Gloves
- 3 – Yellow Disposal Bags & Ties
- 1 – Pair Safety Goggles
- 1 – Emergency Response GuideBook
- 1 – Spill Kit Label
- 6 – Tamper-Proof Labels

**SPKU-30**



Absorbs up to **25.6** Gallons

30-Gallon Spill Kits		
Item #	Description	Refill Kit (contents only)
SPKU-30	30-Gallon Kit/ <b>Universal</b>	RSPKU-30
SPKO-30	30-Gallon Kit/ <b>Oil-Only</b>	RSPKO-30
SPKHZ-30	30-Gallon Kit/ <b>HazMat</b>	RSPKHZ-30
A30OVER	Empty 30-Gallon OverPack (see p44)	n/a

## 20-Gallon Spill Kit

Contents pre-packed in X-rated DOT-approved 20-Gallon OverPack (UN 1H2/X75/S). Available for Universal, Oil-Only and HazMat use. Content-only Refill Kit available.

**Kit Contents:**

- 25 – 15"x19" Pads
- 4 – 3"x4' Socks
- 2 – 18"x18" Pillows
- 1 – Pair Nitrile Gloves
- 2 – Yellow Disposal Bags & Ties
- 1 – Pair Safety Goggles
- 1 – Spill Kit Label
- 6 – Tamper-Proof Labels

**SPKU-20**



Absorbs up to **16.4** Gallons

20-Gallon Spill Kits		
Item #	Description	Refill Kit (contents only)
SPKU-20	20-Gallon Kit/ <b>Universal</b>	RSPKU-20
SPKO-20	20-Gallon Kit/ <b>Oil-Only</b>	RSPKO-20
SPKHZ-20	20-Gallon Kit/ <b>HazMat</b>	RSPKHZ-20
A20OVER	Empty 20-Gallon OverPack (see p44)	n/a

## 5-Gallon Spill Kit

Contents are pre-packaged in a DOT-approved 5-Gallon OverPack (UN 1H2/Y1.5/30) for transporting liquids. Available for Universal, Oil-Only and HazMat use.

**Kit Contents:**

- 10 – 15" x 19" Pads
- 2 – 3" x 4' Socks
- 1 – Yellow Disposal Bag & Tie
- 1 – Pair Nitrile Gloves
- 1 – Pair Safety Goggles
- 1 – Spill Kit Label
- 6 – Tamper-Proof Labels

Absorbs up to **4.6 Gallons**



### 5-Gallon Spill Kit

Item #	Description	Refill Kit (contents only)
<input checked="" type="checkbox"/> SPKU-5	5-Gallon Kit/Universal	n/a
<input type="checkbox"/> SPKO-5	5-Gallon Kit/Oil-Only	n/a
<input type="checkbox"/> SPKHZ-5	5-Gallon Kit/HazMat	n/a
A5OVER	Empty 5-Gallon Pail w/Screw-Top Lid (see p44)	n/a

Spill Kits

## Spill Kaddie Kit

Back by popular demand, this wheeled Kit makes spill response quick, while interior shelves and easy-view compartments keep supplies at-hand and organized. Features top and bottom handles for carrying or wheeling. Lockable for added safety. Fits through narrow aisles and doorways.

**Kit Contents:**

- 100 – 11" x 13" Pads (refills can be found on pages 10, 12 and 22)
- 6 – 3" x 4' Socks
- 4 – 8" x 18" Pillows
- 3 – Yellow Disposal Bags & Ties
- 1 – Pair Nitrile Gloves
- 1 – Pair Safety Goggles
- 1 – 7" Epoxy Stick
- 1 – 6" Light Stick
- 1 – Emergency Response GuideBook
- 1 – Spill Kit Label

Absorbs up to **28.5 Gallons**



SPKHZ-KAD2

### Spill Kaddie Kit

Item #	Description	Refill Kit (contents only)
<input checked="" type="checkbox"/> SPKU-KAD2	Spill Kaddie Kit/Universal	RSPKU-KAD
<input type="checkbox"/> SPKO-KAD2	Spill Kaddie Kit/Oil-Only	RSPKO-KAD
<input type="checkbox"/> SPKHZ-KAD2	Spill Kaddie Kit/HazMat	RSPKHZ-KAD
A-KADDIE	Empty Spill Kaddie (see p44)	n/a

## Spill Cart Kit

Easy-to-locate, bright-yellow 15-cubic foot wheeled container rolls quickly to a spill site. 31" width fits easily through doorways and aisles. Can also be moved with a forklift. Lockable to protect contents. UV-inhibited polyethylene Utility Box with rounded lid can be used outdoors.

Utility Box with 5" wheels is ideal for smooth or indoor surfaces; Utility Box with 8" pneumatic wheels are ideal for outdoor or rough surfaces. Content-only Refill Kits available.

Absorbs up to **109.9 Gallons**



SPKO-CART5

**Universal Kit Contents:**

- 160 – 15" x 19" Pads • 30 – 3" x 4' Socks
- 10 – 3" x 8' Socks • 112 – Wipers
- 4 – Yellow Disposal Bags & Ties • 1 – Pair Nitrile Gloves
- 1 – Pair Safety Goggles • 1 – Spill Kit Label
- 1 – Emergency Response GuideBook • 6 – Tamper-Proof Labels
- Absorbs up to 88.2 gallons

**Oil-Only Kit Contents:**

- 100 – 15" x 19" Pads • 4 – 5" x 10' Booms
- 2 – 8" x 20' Sock/Net Booms
- 4 – 8" x 18" Pillows • 2 – 6" x 16" x 21" Net Pillows
- 4 – Yellow Disposal Bags & Ties • 1 – Pair Nitrile Gloves
- 1 – Pair Safety Goggles • 1 – Spill Kit Label
- 1 – Emergency Response GuideBook • 6 – Tamper-Proof Labels
- Absorbs up to 109.9 gallons

**HazMat Kit Contents:**

- 100 – 15" x 19" Pads • 15 – 3" x 4' Socks
- 3 – 3" x 8' Socks • 2 – 5" x 10' Sock/Net Booms
- 7 – 18" x 18" Pillows • 4 – Yellow Disposal Bags & Ties
- 1 – Pair Nitrile Gloves • 1 – Pair Safety Goggles • 1 – Spill Kit Label
- 1 – Emergency Response GuideBook • 6 – Tamper-Proof Labels
- Absorbs up to 82.0 gallons

### Spill Cart Kit

Item #	Description	Refill Kit (contents only)
<input checked="" type="checkbox"/> SPKU-CART5	Spill Cart Kit/Universal w/ 5" Wheels	RSPKU-CART
<input checked="" type="checkbox"/> SPKU-CART8	Spill Cart Kit/Universal w/ 8" Wheels	RSPKU-CART
<input type="checkbox"/> SPKO-CART5	Spill Cart Kit/Oil-Only w/ 5" Wheels	RSPKO-CART
<input type="checkbox"/> SPKO-CART8	Spill Cart Kit/Oil-Only w/ 8" Wheels	RSPKO-CART
<input type="checkbox"/> SPKHZ-CART5	Spill Cart Kit/HazMat w/ 5" Wheels	RSPKHZ-CART
<input type="checkbox"/> SPKHZ-CART8	Spill Cart Kit/HazMat w/ 8" Wheels	RSPKHZ-CART
A-UTILITYBOX5	Empty Utility Box w/ 5" Wheels (p44)	n/a
A-UTILITYBOX8	Empty Utility Box w/ 8" Wheels (p44)	n/a

## Fleet Kit

Compact Kit has everything needed to handle small spills on the road. Packed in a sturdy nylon bag for security on the go. Small size is ideal for use in fleet vehicles.

**Kit Contents:**

- 50 – 11" x 13" Pads (refills sold on page 10, 12 and 22)
- 2 – 3" x 4" Socks
- 2 – Yellow Disposal Bag & Tie
- 2 – Pair Nitrile Gloves
- 1 – Pair Safety Goggles
- 1 – Tub Plug & Dike Putty
- 1 – Pack of Assorted Wooden Plugs
- 1 – Spill Kit Label



Absorbs up to **10.7 Gallons**

SPKO-FLEET

Fleet Kit		
Item #	Description	Refill Kit (contents only)
■ SPKU-FLEET	Fleet Kit/Universal	n/a
□ SPKO-FLEET	Fleet Kit/Oil-Only	n/a
■ SPKHZ-FLEET	Fleet Kit/HazMat	n/a
A-YTOTE	Empty Tote Bag (see p44)	n/a

## 5-Gallon HazMat Pouch Kit

Transporting Bottles, Vials or Containers Just Got Easier

LabPack any liquid up to moderate hazard, and the yellow HazMat particulate that is sandwiched between a heavy plastic liner and an absorbent spunbond layer will protect it. Use the included ties to close the top, seal inside the UN-approved 5-gallon overpack for transporting liquids, label it (included) and send it anywhere! Includes 5 tamper-proof labels.

Refills sold separately:  
 OP25 includes 5 pouches and 10 ties;  
 OP210 includes 10 pouches and 20 ties.



Absorbs up to **2.2 Gallons**

SPKHZ-50P



5-Gallon HazMat Pouch Kit			
Item #	Description	Units/Pkg	Absorbs/Pkg
■ SPKHZ-50P	5-Gallon Pouch Kit/HazMat	1	2.2 gal.
■ OP25	5-Gallon Pouch Kit Refill	5	11.0 gal.
■ OP210	5-Gallon Pouch Kit Refill	10	22.0 gal.
A5OVER	Empty 5-Gallon Pail (see p44)	1	n/a

## Trucker Kit

Handle All Types of Spills With This Portable Kit

This handy kit features a compact design that easily fits behind the seat of a truck for quick response. Ideal for the smaller types of spills that truckers encounter on a regular basis. Available in Universal, Oil-Only and HazMat versions.

Absorbs up to **8.3 Gallons**



**Kit Contents:**

- 20 – 15"x19" Pads
- 3 – 3"x4" Socks
- 1 – Yellow Disposal Bag & Tie
- 1 – Pair Nitrile Gloves
- 1 – Pair Safety Goggles

Trucker Spill Kit		
Item #	Description	Refill Kit (contents only)
■ SPKU-TRK	Trucker Kit/Universal	n/a
□ SPKO-TRK	Trucker Kit/Oil-Only	n/a
■ SPKHZ-TRK	Trucker Kit/HazMat	n/a

## Specialty Kits

### Mercury Spill Kit

Highly effective Kit provides outstanding mercury vapor control. Includes vapor suppressors, aspirator, PPE and disposal containers. Kit requires no mixing.



### Battery Acid Spill Kit

Contains everything needed to handle battery acid hazards — even PPE.

**Battery Acid Kit Contents:**

- 3 – 3" x 4" Socks
- 40 – 15" x 19" Pads
- 3 – 18" x 18" Pillows
- 1 – Pair Neoprene Gloves
- 1 – Pair Safety Goggles
- 2 – 2 lb. Acid Neutralizing Sorbent Shaker Cartons
- 2 – Yellow Disposal Bags & Ties
- 6 – Tamper-Proof Labels

SPKHZ-BATT

Absorbs up to **23.3 Gallons**



Specialty Kits		
Item #	Description	Refill Kit (contents only)
MERC-KIT	Mercury Spill Kit	n/a
■ SPKHZ-BATT	Battery Acid Spill Kit	RSPKHZ-BATT
A20OVER	Empty 20-Gallon OverPack (see p44)	n/a

Spill Kits

## Drum Repair Kit



### Repairs Punctures, Cracks, Gashes or Surface Rotting

Drum Repair Kit contains components to make small repairs to containers that can leak liquid or bulk hazardous material. Covers cracks, hairline cracks and small holes in any type of low-pressure vessel. Kit features screw and "T" patches, ball and taper surface plugs, epoxy putty, lead wool, barrier tape, wood plugs and all tools and hardware.

*This item is drop-shipped from vendor.*

Drum Repair Kit		
Item #	Description	Units/Pkg
R-DRUM	Drum Repair Kit	1

## Leak Repair Kit




### Our Most Advanced Leak Control Kit


This advanced Leak Repair Kit employs a quick-application "T" patch and proven ladder patch design to tackle an average forklift-caused puncture. The Kit also contains various plugs and patches for smaller holes and all necessary tools and hardware for effective leak control.

*This item is drop-shipped from vendor.*

Leak Repair Kit		
Item #	Description	Units/Pkg
R-LEAK	Leak Repair Kit	1



R-PIPE-S



R-PIPE-L

## Pipe Repair Kit


### Keep This Kit on Stand-by to Control Pipe Leaks

Contains a complete set of external pipe bandages as well as extra hard and soft neoprene rubber external pipe bandages for help where you may need it. Kit includes all necessary tools and a carrying case for easy handling and usage. Typical uses include water pipes, gas lines, air lines, fuel transfer pipes, chemical transfer lines and sewer pipes. Unlimited uses in municipal departments, chemical plants, manufacturing facilities, hospitals, oil fields, water and sewer treatment plants and anywhere a pipe or line is used.

R-PIPE-S covers pipe sizes from 1/2" - 4"; contains 10 patches.

R-PIPE-L covers pipe sizes from 5" - 8"; contains 3 patches.

*These items are drop-shipped from vendor.*




Just wrap bandage around pipe and tighten the clamp.

Pipe Repair Kit			
Item #	Description	Size	Units/Pkg
R-PIPE-L	Pipe Repair Kit	For 5" to 8" pipes	1
R-PIPE-S	Pipe Repair Kit	For .5" to 4" pipes	1

# Build a Custom Spill Kit with Just What You Need!

## Get the perfect Spill Kit for your application.

If you can't find exactly what you need in our selection of pre-packed Kits, we'll be glad to build one to your specifications. Answer 5 simple questions (at right) to help you choose the type and quantity of sorbents you require, the accessories to make the response safer and the container that will work best with your choices. There's no extra charge for this service, so it's an easy way to customize your spill response plan and stock only the sorbents and PPE you really need. After you've made your list, just contact your local Distributor and we'll do the rest!



### 1. How much do you need to absorb?

What is your worst-case scenario? You'll need enough sorbents to clean up the maximum amount, whether it's one gallon or one hundred.



### 2. What liquid are you absorbing?

For multiple everyday liquids, use Universal. To soak up oil and repel water, choose Oil-Only. To alert workers to a dangerous spill, use HazMat.



### 3. What type of spills do you deal with?

Slops and spills use pads for quick wiping and cleanup. Drum/tank leaks need more socks for diking and Plug & Dike epoxy to stop the flow. Large-volume spills require booms for containment and pillows for more sorbency.



### 4. What type of PPE and accessories will you need?

Most spills call for boots, gloves and goggles. Will you need coveralls? How much chemical protection do you need? How often will you have to replace disposable items?



### 5. What type of container will you need?

For removing saturated sorbents, use a UN-rated Overpack/Salvage Drum. Stationary Kits can go in a flat-bottom Overpack. Movable kits require a kaddie or wheeled overpack.



Large Wheeled Bin




Wheeled Kaddie



Small Carry Bag

Wheeled Overpack



Spill Kits



## OverPacks

### DOT Approved for Salvage

All SpillTech® OverPacks are DOT approved and X rated for use as salvage drums. Helps companies conform to federal regulations when shipping damaged or leaking containers of hazardous materials, or absorbents contaminated with hazardous substances.


### 100% Polyethylene Construction

OverPacks are sturdy and chemical resistant for years of use. Integrated forklift ledges and handles (on containers w/ wheels) make them easy to lift, move or carry. Avoid the extra expense of a dolly when you buy a wheeled OverPack, which provides you with great versatility in a single integrated product.

## OverPacks vs Salvage Drums

An OverPack is any container that goes over or around another intact, undamaged container. A Salvage Drum meets stricter standards that certify it for material transport. Both types of containers must meet size and volume requirements and pass stack and drop tests.

However, a Salvage Drum must also pass a pressure test and be stamped "Salvage" or "Salvage Drum."



## Spill Cart

Large, heavy-duty Carts are forkliftable and lockable. Hinged double-walled lid is sloped to shed rain; closes tightly to keep out water and dirt. Available with 5" rubber wheels for smooth surfaces or 8" pneumatic wheels for rough terrain.



A-UTILITYBOX5

## Tote Bag

Soft-sided duffel Bag is ideal for grab-and-go convenience. Nylon Bag with zipper closure. "Spill Responder" printed on one side.



A-YTOTE

## Spill Kaddie

Handy kit on wheels for quick response, even through narrow aisles and doorways. Spill Kaddie features interior shelves and compartments to keep supplies organized. Double-wall molded, lockable and water resistant.



A-KADDIE



Helps you comply with 49 CFR 173.3(c)(1), 49 CFR 173.12(b) and 49 CFR 173.12(b)(2)(iv). See page 67 for details.

### OverPacks & Containers

Item #	Description	Size	Weight/Pkg
A-KADDIE	Empty Spill Kaddie	40"Hx20"Wx20"D	38 lbs.
A-UTILITYBOX5	Empty Spill Cart w/ 5" Wheels	48"Hx31"Wx31.5"D	129 lbs.
A-UTILITYBOX8	Empty Spill Cart w/ 8" Wheels	48"Hx31"Wx31.5"D	154 lbs.
A95OVER	Empty 95-Gal. OverPack	32" diam., 41.5"H	48 lbs.
A95OVER-WD	Empty 95-Gal. OverPack w/ Wheels	32" diam., 47.5"H	56 lbs.
A65OVER	Empty 65-Gal. OverPack	28.25" diam., 37.5"H	45 lbs.
A50OVER-WD	Empty 50-Gal. OverPack w/ Wheels	24.5" diam., 45.5"H	38 lbs.
A30OVER	Empty 30-Gal. OverPack	23" diam., 30.75"H	13 lbs.
A20OVER	Empty 20-Gal. OverPack	23" diam., 19"H	10 lbs.
A5OVER	Empty 5-Gallon Pail w/ Screw-Top Lid	12" diam., 16.75"H	4.5lbs.
A-YTOTE	Empty Tote Bag	20"Lx17"Wx8"D	.06 lb.

### Tyvek Coveralls

Tyvek Coveralls help keep out moisture and particulate, including asbestos, lead, radioactive dust and more. Non-woven fabric with elastic wrists and ankles. Non-sparking zipper; biologically inert and anti-stat treated. Use wet or dry in temps up to 100°F. Meets ANSI/ISEA sizing requirements.



A-TYVEK

NEW

### Endurosaf® Apron


Composite-fabric apron offers light protection from oils, chemicals and abrasion. Durable Enduro 2000™ film is better than neoprene, nitrile or vinyl for use around food, chemicals and sensitive equipment. Light-weight, 8-oz. construction. Liquid-repellent. Plastic buckles won't corrode or spark.



A-APRON-WH

NEW

### Safety Goggles



A-GOG

Light-weight, comfortable design. ANSI compliant for impact protection. Frame made from sturdy PVC plastic; scratch-resistant polycarbonate lens.

### Neoprene Gloves



A-GLV-NEO

Fully-coated Neoprene Gloves won't fail when exposed to chemicals — even when completely submerged. 2-piece interlock liner for flexibility and integrity. Excellent wet grip. 14" fully coated gauntlet. Ideal for refinery applications, chemical handling and more.

### Nitrile Gloves




A-GLV-NIT

More chemical-resistant than rubber gloves, with better puncture and abrasion resistance than PVC gloves. Heavy-duty, non-slip grip. Light, cool and ideal for use in food and chemical processing, machine operations and maintenance applications. Choose single pair or case.

### Latex Boots

Latex Boots slip over work boots or shoes. Disposable 0.70 mm gauge yellow latex protects against harsh liquid and hazardous or toxic waste. Smooth-finished inside for easy on/off; non-skid sole.

NOTE: Not for daily wear; dispose of boots after contamination.




A-LATEXBOOTS

Spill Kits

### Spill Kit Accessory Items

Item #	Description	Size	Units/Pkg
NEW A-TYVEK-M	Coveralls	M	1
NEW A-TYVEK-L	Coveralls	L	1
NEW A-TYVEK-XL	Coveralls	XL	1
NEW A-APRON-WH	Apron - Enduro 2000™ Fabric	One Size Fits All	1
A-LATEXBOOTS	Latex Boots	X-Large	1 pair
A-GOG	Safety Goggles	One Size Fits All	1
A-GLV-NEO	Gloves - Neoprene	Large	1 pair
A-GLV-NIT	Gloves - Nitrile	One Size Fits All	1 pair
NEW A-GLV-NIT-CS	Gloves - Nitrile	One Size Fits All	144 pairs


### Acid Neutralizing Sorbent



Visible color change signifies complete neutralization of acids; absorbs and solidifies liquids. Not for use with hydrofluoric acid. Environmentally friendly.

### Emergency Response GuideBook

A-EGB



This Emergency Response GuideBook is a great source of information for responding quickly to spills of all types. Helps identify hazards and materials in an accident. Color-coded and indexed so it's quick and easy to find the information you need.

### Epoxy Putty



This versatile Putty can be used to make emergency patches and repairs to a wide variety of materials. It adheres to steel, glass, metals, masonry, wood and many plastics. Sets in 20 minutes — hard as cement in an hour. Store unused Putty in re-sealable tube. Solvent-free, non-toxic.

### Tamper-Proof Seal

Apply this self-adhesive vinyl label to any spill kit. If the kit is opened, this label breaks, alerting you that the kit may no longer contain a full supply of absorbents. Hi-viz yellow.



### Non-Sparking Shovel

Specifically designed for spill kits and industrial cleanup applications, this patented two-piece Shovel is constructed of rugged polypropylene for chemical resistance. Will not rust or corrode. Blade contains an anti-static agent to prevent sparking. Disassembles for easy storage. Extended D-grip handle.



### SuperSorbent Loose Sorbent

SS1



SuperSorbent Loose Sorbent instantly soaks up liquids to leave surfaces completely dry and reduce slip and fall injuries. Super-concentrated formula absorbs 10 to 12 times more liquid than traditional clay products. Won't harm the environment.

### Plug & Dike Epoxy



A-P&D

Non-toxic, non-flammable blend forms an immediate seal when applied. Works with fuels, solvents, paints, and water-based chemicals.

### pH Tester Kit



A-PHTEST

Direct-reading, general-purpose pH paper gives instant pH checks over the entire range as it changes to 14 brilliant, distinct colors on 1 paper. Kit includes color chart, dispenser and polyethylene case.

### Wooden Plugs



A-WOODPLUGS

Plugs are edged and pre-shaped. Can be covered with a sorbent pad and pushed into a leak zone; the wood and pad expand together to fill the hole. Assorted sizes; nine Plugs per package.

### Spill Kit Accessory Items

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
ANS1	Acid Neutralizing Sorbent	2-lb. Shaker	1	.2 gal.
ANS12	Acid Neutralizing Sorbent	2-lb. Shakers	12	2.4 gal.
ANS5	Acid Neutralizing Sorbent	5-gal. Pail	1	2.5 gal.
SS1	SuperSorbent Loose Sorbent	28-oz. Shaker	1	.6 gal.
SS12	SuperSorbent Loose Sorbent	28-oz. Shakers	12	7.0 gal.
A-PHTEST	pH Tester Kit	50'L Tape	1	n/a
A-EGB	Emergency Response GuideBook	384 Pages	1	n/a
A-EPOXY	Epoxy Putty	7" Stick	1	n/a
A-PND	Plug & Dike Epoxy	3.5" diam., 2.5"H, 1lb.	1	n/a
A-WOODPLUGS	Wooden Plugs	Assorted	9	n/a
NEW A-SEAL	Tamper-Proof Seal Labels	2"Wx6"L	6	n/a
A-SHOVNS	Non-Sparking Shovel	Blade: 10.5"Wx14"H Overall: 43.5"H	1	n/a

### FineFiber Mat

These sorbent Pads are specially sized for stocking your SpillTech® Spill Kit. FineFiber Mat has a layer of MeltBlown polypropylene ultrasonically sandwiched between two FineFiber layers, so it's virtually indestructible. Increased surface area enables the mat to grip surfaces securely.



WPF1113H

### Wall-Mount Bracket


This steel Bracket is made for 20- and 30-Gallon OverPack Spill Kits. Wall mount your spill supplies to save floor space and reduce response time. Spill Kits sold separately.



A-BRACKET

### Light Stick

Disposable Light Stick requires no batteries or electricity, and contains no toxic chemicals. Just bend Stick to illuminate; glows for hours.



A-LIGHTSTICKS

Light Stick when lit

### Temporary Disposal Bag

Large-size Disposal Bag is printed with "Caution Handle with Care". 3-mil thick to resist punctures. Ideal for use with 55-gallon drums. Compatible with oil, water and solvents. Available by the bag or as a 125-bag roll.



A-DISP BAG

### Spill Station Sign



#### A-SIGN

Vinyl construction with adhesive backing sticks to smooth, curved and irregular surfaces. Identifies spill kit locations so they can be easily located in the event of a spill.

### Wipers

General-purpose quarterfold Wiper provides cloth-like softness and excellent liquid absorption that's ideal for most tasks. Quickly absorbs spills and leaks and handles routine industrial cleaning and maintenance with ease.

#### A-WIPER



### OverPack Cover

Hi-viz Cover protects Spill Kit contents indoors and out. Impermeable material blocks water, dust, debris and damaging UV light. Place label in see-through pocket for fast identification. Hi-viz for quick location in an emergency. OverPacks sold separately on page 44.



A-COVER-LG

### Hazard Labels Set

Paper Labels with pressure-sensitive adhesive. Printed with light-fast inks for high durability. 4"x4" Labels read: "Flammable Liquid," "Flammable Solid," "Corrosive" and "Oxidizer"; 6"x6" Label reads "Hazardous Waste." Set includes one of each label.



A-LABELS

### Spill Kit Accessory Items

Item #	Description	Size	Units/Pkg	Absorbs/Pkg
WPF1113H	FineFiber/Oil-Only HeavyWeight Pads	11"x13"	100	18.1 gal.
GPF1113H	FineFiber/Universal HeavyWeight Pads	11"x13"	100	18.1 gal.
YPF1113H	FineFiber/HazMat HeavyWeight Pads	11"x13"	100	18.1 gal.
A-WIPER	Wipers	13"x12.5"	56	n/a
NEW A-BRACKET	Wall-Mount Bracket	21.75"Lx 12.5"Wx6"H	1	-n/a
NEW A-COVER-SM	OverPack Cover	for 20- & 30-gal. OverPacks	1	n/a
NEW A-COVER-LG	OverPack Cover	for 65- & 95-gal. OverPacks	1	n/a
A-LIGHTSTICKS	Light Stick	6"L	1	n/a
A-LABELS	Hazard Labels Set	Assorted	5	n/a
A-DISP BAG	Temporary Disposal Bag	30"Wx 6"Dx60"H	1	n/a
NEW A-DISP BAG-ROLL	Temporary Disposal Bag	30"Lx 12Wx12"H	125	n/a
A-SIGN	Spill Control Station Sign	7"Hx10"W	1	n/a



ADC36-CASE

Your DrainCover fits inside this optional hi-viz Case to protect it from weather, abrasion, puncture, UV and more, so it's ready to use when you need it.

## DrainCovers

### Tough, Reversible DrainCovers in Three Sizes

Tough but easy-to-handle Covers are solid polyurethane. They're tacky on both sides, so either side can form a tight seal to block contaminants.

### Reusable DrainCovers are Chemical Resistant

More chemical resistant than rubbers or plastics,

DrainCovers stand up to a wide range of chemicals, solvents and oils. Reusable; can be washed and stored in the handy, portable box.

### Hard Case Also Available

Transport and store your DrainCover in this optional polypropylene Case to better protect it from damage. A nylon strap lets you hang or carry it anywhere.



Helps you comply with \*40 CFR 112.7(c)(1) and \*40 CFR 263.30(a). See page 67 for details.

\* Applies to DrainCovers only

## DrainCovers

Item #	Description	Size	Units/Pkg
NEW ADC12-CIR	12" Dia. DrainCover	12"Dia.x.25"H	1
ADC36-R	36" DrainCover	36"Lx36"Wx.25"H	1
NEW ADC36-CASE	Case for 36" Cover	7.25"Dia.x38"L	1
ADC42-R	42" DrainCover	42"Lx42"Wx.25"H	1
NEW ADC42-CASE	Case for 42" Cover	7.25"Dia.x50"L	1

Stormwater Management



A Conical DrainPlug fits discreetly under the grate to prevent spilled oil and other pollutants from getting into your drains without disrupting traffic or creating a trip hazard.

## Conical DrainPlugs

### Confidently Block Pollution without a Permanent Seal

A reusable Conical DrainPlug fits conveniently under your drain's grate and pulls out easily to allow normal flow. Chemical-resistant polyurethane reliably seals drains to keep out liquids. A non-permanent alternative to cement.

### Easy to Use and Easy to Clean

To install, simply lift your grate, press the tapered conical Plug into the drain and replace the grate. To reopen the drain, just remove the Plug by pulling up on the metal ring using hand tools. Cleans easily with soap and water for reuse.



Helps you comply with 40 CFR 112.7(c)(1) and 40 CFR 263.30(a). See page 67 for details.

## Conical DrainPlugs

Item #	Description	Size	Units/Pkg
NEW DP2	2" Dia. DrainPlug	2"Dia.x4.75"H	1
NEW DP3	3" Dia. DrainPlug	3"Dia.x5"H	1
NEW DP4	4" Dia. DrainPlug	4"Dia.x5.75"H	1
NEW DP6	6" Dia. DrainPlug	6"Dia.x5.5"H	1



## SpillBerm Plus Containment Barrier

### Non-Absorbent Barrier Diverts Liquids

This sturdy, flexible 100% polyurethane Barrier stands up to oils, coolants, solvents and water. The tacky bottom grips smooth surfaces and keeps liquids from seeping underneath.

### Hassle-Free Customization

Built-in dovetail connectors create a leak-proof seal and let you combine SpillBerms to fit any area — without extra parts.

### Keep It Handy

Store a SpillBerm Plus close to spill-prone areas since it's quick and easy to deploy. Also cleans easily with soap and water for reuse.




The 4.5" height is great for containing deeper pools of liquid. Once a spill is under control, cleanup or reclamation is simple.

**HYC** Helps you comply with 40 CFR 122.26, 40 CFR 112.7(c)(1) and 40 CFR 263.30(a). See page 67 for details.

SpillBerm Plus			
Item #	Description	Size	Units/Pkg
NEW PBL253	SpillBerm Plus	5'Lx4"Wx4.5"H	1

## Connectable Spill Berm



Simple, versatile design makes this Berm a "snap" to use when connecting several Berms together to contain larger spills.

### Easily Bends to Fit any Angle or Curve

Made of flexible 100% polyurethane elastomer so it's non-absorbent and resistant to a wide variety of chemicals and fluids.

### Sturdy and Reusable

Interlocking ends connect individual sections to create longer lengths so you can contain almost any spill. Just clean it with soap and water and it's ready to reuse.

**HYC** Helps you comply with 40 CFR 122.26, 40 CFR 112.7(c)(1) and 40 CFR 263.30(a). See page 67 for details.

Connectable Spill Berm			
Item #	Description	Size	Units/Pkg
SPB10C	Connectable Spill Berm	10'Lx2.25"Wx1.375"H	1

## SpillCurb Containment Berm

### Non-absorbent Berm Diverts Liquids

This sturdy, flexible 100% polyurethane Berm stands up to oils, coolants, solvents and water. The tacky bottom grips smooth surfaces. Ideal for applications where you want to divert or redirect liquids without absorbing them.

### Keep it Handy

Store near spill-prone areas since it's quick and easy to deploy. Cleans easily with soap and water for reuse.

### Customize Your Curb


Combine 10' lengths of SpillCurb with Corners and Connectors to fit any area. The optional hard Case better protects your SpillCurb during transport or storage.



MR8014-CASE



Transport and store your SpillCurb Barrier in this specially designed Case. Weather-proof polyethylene Case protects your SpillCurb from damage, and its compact size allows for storage anywhere.




MR8014

**HYC** Helps you comply with 40 CFR 122.26, 40 CFR 112.7(c)(1) and 40 CFR 263.30(a). See page 67 for details.

SpillCurb			
Item #	Description	Size	Units/Pkg
MR8014	SpillCurb	10'Lx3.75"Wx2.25"H	1
MR8018	SpillCurb Corner	4"Lx4"Wx2.25"H	1
MR8019	SpillCurb Connector	4"Lx2.25"W	1
NEW MR8014-CASE	SpillCurb Case	24.75" Dia. x 4" Dia.	1

Stormwater Management

## Ultra-Dewatering Bag®



### Contain Sediment and Oil During Dewatering Jobs.

The Ultra-Dewatering Bag® captures both sediment and oil being pumped out during dewatering operations, offering a combination of benefits not available in alternative dewatering bags. Can be used as a BMP in a Stormwater Pollution Prevention Plan.

*These items are drop-shipped from vendor.*



Ultra-Dewatering Bag® accepts up to a 6" discharge hose for high-volume pumpouts of sumps, lagoons, ponds and more.

### Ultra-Dewatering Bag®

Item #	Description	Size	Units/Pkg
<b>NEW ULT9729-OS</b>	Ultra-Dewatering Bag®	3'x4'	1
<b>NEW ULT9724-OS</b>	Ultra-Dewatering Bag®	6'x6'	1
<b>NEW ULT9725-OS</b>	Ultra-Dewatering Bag®	10'x15'	1



## Ultra-GutterGuard®


Use in areas with high stormwater flow to prevent pollutants and debris from entering storm drains. Unique, multi-dimensional outer filter combined with rigid inner frame maintains a low profile

to prevent damage from vehicular traffic. Allow 12" overlap on each side of drain. *This item is drop-shipped from vendor.*

**HYC** Helps you comply with 40 CFR 122.26. See page 67 for details.

### Ultra-GutterGuard®

Item #	Description	Size	Units/Pkg
<b>ULT9320</b>	Ultra-GutterGuard®	9" dia. x 8'L	1
<b>ULT9321</b>	Ultra-GutterGuard®	9" dia. x 10'L	1
<b>ULT9322</b>	Ultra-GutterGuard®	9" dia. x 12'L	1



## Ultra-DrainGuard®

Ultra-DrainGuard® removes waste from stormwater before it can become a problem in the water system. This oil and sediment filtering product removes up to 0.87 gallons of hydrocarbons as well as dirt, sand and other contaminants.

Designed for use in industrial facilities, construction sites, retail facilities and parking lots where polypropylene geotextiles collect oil, fuel and other contaminants that drip from cars.

**HYC** Helps you comply with 40 CFR 122.26. See page 67 for details.

### Ultra-DrainGuard®

Item #	Description	Size	Units/Pkg
<b>ULT9217</b>	Ultra-DrainGuard® - Oil & Sediment	48"Lx36"Wx18"H	1
<b>ULT9218</b>	Ultra-DrainGuard® - Oil & Sediment	48"Lx36"Wx18"H	10

## Roof and Pipe Leak Diverters



### Roof Leak Diverters

Large, vinyl-coated fabric catches roof leaks and channels them away from offices and equipment through a standard hose hookup. Lightweight material is also flame retardant.

LD1010 is 10'L x 10'W;  
LD55 is 5'L x 5'W.

### Pipe Leak Diverters

Keep fluid leaks off the floor while eliminating slip hazards and chemical exposure. Large 18" diameter opening captures pipe leaks and channels them away from plant personnel and machinery.



All Leak Diverters are designed to easily connect to a standard garden hose which can be directed to a proper drainage point.

### Roof and Pipe Leak Diverters

Item #	Description	Size	Units/Pkg
LD1818	Pipe Leak Diverter	18"Lx18"W	1
LD55	Roof Leak Diverter	5'Lx5'W	1
LD1010	Roof Leak Diverter	10'Lx10'W	1

## Prowler™ Spill Containment Pools



Step 1: Remove and open Prowler™ Pool.



Step 2: Position Pool underneath spill source.



Step 3: Pool contains up to 150 gallons of liquid.

### Containment Pools

Compact and portable, Prowler™ Pools are ideal for containing spills when you're on the road or anywhere you spring a leak. Constructed of high-density polyethylene tapes, Pools offer excellent resistance to many chemicals. Available in four sizes.


*These items are drop-shipped from vendor.*



Helps you comply with 40 CFR 263.30(a).  
See page 67 for details.

### Prowler™ Pools

Item #	Description	Size	Sump Capacity
ENP5920	Prowler™ Pool	28" base x 13"H x 18" opening	20.0 gal.
ENP5966	Prowler™ Pool	48" base x 14"H x 36" opening	66.0 gal.
ENP5900	Prowler™ Pool	48" base x 18"H x 32" opening	100.0 gal.
ENP5950	Prowler™ Pool	60" base x 18"H x 44" opening	150.0 gal.



Eliminating "burps" means you can pour flammables or chemicals faster and more safely.


### Burp-Free Funnels

A built-in vent means no more splashing or "burping" liquids when you pour! A threaded brass insert screws into any 2" bung. 100% polyethylene won't rust or corrode; provides excellent chemical

resistance. Hinged, lockable lid prevents unauthorized access. Choose larger diameter for more pouring area and easier access.

*These items are drop-shipped from vendor.*

Burp-Free Funnels				
Item #	Description	Size	Units/Pkg	Weight/Pkg
<b>NEW ULT0651</b>	Funnel	13.375"Diax11"H	1	6 lbs.
<b>NEW ULT0656</b>	Large-Diameter Funnel	22"Diax11.5"H	1	8 lbs.



### Containment Sumps

Sumps offer secondary containment for large oval tanks. Eliminate costly spills while storing fuels, oils and other hazardous liquids.

100% polyethylene will not rust or corrode; provides

superior chemical and weather resistance. Offers the best protection for non-monitored containment sites. Choose with or without drain.

*These items are drop-shipped from vendor.*

Containment Sumps			
Item #	Description	Size	Sump Cap.
<b>NEW ULT2800</b>	275 Sump w/o Drain	84.5"Lx43.75"Wx29"H	360 gal.
<b>NEW ULT2801</b>	275 Sump w/ Drain	84.5"Lx43.75"Wx29"H	360 gal.
<b>NEW ULT2820</b>	550 Sump w/ Drain	87"Lx62.25x32.75"H	605 gal.
<b>NEW ULT2823</b>	550 Sump w/o Drain	87"Lx62.25x32.75"H	605 gal.



### Rack Containment Tray

Low-profile Tray slides easily under pallet racking and shelves, catching small leaks and spills from contents above to help keep floors clean and free from slip hazards. Black, all-polyethylene construction

provides excellent chemical compatibility and corrosion resistance. Includes 3 trays and 2 connectors.

*These items are drop-shipped from vendor.*

Rack Containment Tray				
Item #	Description	Size	Units/Pkg	Sump Cap.
<b>NEW ULT2372</b>	Trays w/ Connectors	72"Lx44"Wx2.75"H	1	24 gal.



### Ultra-Utility Tray®

Help keep messy drips and spills off your floors. Heavy-duty polyethylene will not rust or corrode. Ribbed bottom

keeps cans, pails and other containers elevated above small spills or leaks. Nestable for easy storage.

Ultra-Utility Tray®				
Item #	Description	Size	Units/Pkg	Sump Cap.
<b>NEW ULT1031</b>	Ultra-Utility Tray®	12"Lx48"Wx4.75"H	1	12 gal.
<b>NEW ULT1032</b>	Ultra-Utility Tray®	24"Lx48"Wx4.75"H	1	24 gal.
<b>NEW ULT1033</b>	Ultra-Utility Tray®	30"Lx48"Wx4.75"H	1	30 gal.
<b>NEW ULT1034</b>	Ultra-Utility Tray®	24"Lx36"Wx4.75"H	1	18 gal.
<b>NEW ULT1035</b>	Ultra-Utility Tray®	36"Lx36"Wx4.75"H	1	27 gal.
<b>NEW ULT1036</b>	Ultra-Utility Tray®	40"Lx36"Wx3.5"H	1	30 gal.

**NEW**

# Create Custom Drum Storage with Ultra-Spill Decks.



**ULT1089**  
Optional polyethylene Loading Ramp provides added drum handling safety and convenience.

**ULT1131**  
T-strips prevent spilled liquids from seeping between sections.

**ULT1072**  
4-Drum Deck

**ULT1086**  
2-Drum Deck

**ULT1321**  
1-Drum Deck

## Build a Containment System for 6, 8 or More Drums.

Ultra-Spill Decks® can be used alone or connected together with Bulkhead Fittings and T-Strips (both sold separately). 100% polyethylene meets a wide range of chemical compatibility needs. Low height offers safe and convenient loading/unloading. Ideal for collecting hazwaste, storing chemicals or batteries, dispensing and more.

### Bulkhead Fittings


Bulkhead Fittings lock Decks together but let spills flow between sections to help you meet regs. Use one Fitting for every 26" of connected Deck. (For example, use one per side for 1-Drum Decks and two per side for 4-Drum Decks.)

### T-Strips

T-Strips press easily between Decks to offer a smooth transition and prevent spilled liquids from going between sections. Use one T-Strip for every 26" of connected Deck.

## Assembly is fast and easy!

First, drill holes for the Bulkhead Fittings (sold separately).



Next, connect the Decks with the Bulkhead Fittings.



Insert T-Strips (sold separately) between Deck sections and you're done!



Ultra-Spill Decks®				
Item #	Description	Size	Load Cap.	Sump Cap.
<b>NEW ULT1321</b>	1-Drum Section	26"Lx26"Wx5.75"H	3,000 lbs.	11 gal.
<b>NEW ULT1086</b>	2-Drum Section	52"Lx26"Wx5.75"H	3,000 lbs.	22 gal.
<b>NEW ULT1072</b>	4-Drum Section	52"Lx52"Wx5.75"H	6,000 lbs.	42 gal.
<b>NEW ULT1073</b>	Bulkhead Fitting	3" Dia.	n/a	n/a
<b>NEW ULT1089</b>	Loading Ramp	24"Lx32"Wx5.75"H	n/a	n/a
<b>NEW ULT1131</b>	T-Strips	26"	n/a	n/a

Containment



**NEW**

### 1-Drum Bladder System

The first and only low-profile, single-drum containment unit that helps you meet EPA and UFC Containment Regulations.

Compact footprint saves valuable floor space; perfect for single-drum waste collection.


Small spills and leaks are captured in the sump. Large spills and leaks flow into the bladder through a bulkhead fitting; protective trap door opens automatically to allow bladder to unfurl and fill up.

Rugged, double-layer polyethylene bladder withstands wear and tear.

1-Drum Bladder System				
Item #	Description	Size	Load Cap.	Sump Cap.
<b>NEW ULT1320</b>	1-Drum Bladder Sys.	26"Lx30.5"Wx5.75"H	1,500 lbs.	66 gal.

### IBC Spill Pallets

Spill Pallets give you economical containment for IBCs. 1-IBC Pallets feature low height and small footprint; 2-IBC Pallets have a continuous high-capacity sump. 100% polyethylene for chemical resistance. Inner support columns easily hold fully loaded IBCs. Optional Bucket Shelf catches small leaks and channels large leaks into Pallet sump. Choose with or without drain.



**ULT1157**

**NEW**

*These items are drop-shipped from vendor.*

IBC Spill Pallets				
Item #	Description	Size	Load Cap.	Sump Cap.
<b>NEW ULT1140</b>	2-IBC w/o Drain	124.5"Lx61.625"Wx22"H	8,000 lbs. per side	535 gal.
<b>NEW ULT1144</b>	2-IBC w/ Drain	124.5"Lx61.625"Wx22"H	8,000 lbs. per side	535 gal.
<b>NEW ULT1157</b>	1-IBC w/o Drain	62"Lx62"Wx28"H	8,500 lbs.	360 gal.
<b>NEW ULT1158</b>	1-IBC w/ Drain	62"Lx62"Wx28"H	8,500 lbs.	360 gal.
<b>NEW ULT1160</b>	Bucket Shelf	19.5"Lx16"Wx14.5"H	n/a	n/a

### Ultra-SpillPallets®/Economy Model



**ULT1113**

Containment

#### Low-Profile and Heavy Load Capacity

4-Drum Pallets have a low profile (11¾"H) and can hold up to 3,000 lbs. 2-Drum Pallets stand at 16½"H and have a load capacity of 1,500 lbs.

#### Meets Containment Requirements

Each Pallet provides a 66-gallon polyethylene sump to protect and help keep you in compliance — in the event of a small leak or complete drum failure.

#### Strong, Durable and Long-Lasting

All-polyethylene construction makes these Pallets lightweight and resistant to chemicals. Won't rust or corrode.



**ULT2505**

**HYC** Helps you comply with 40 CFR 264.175. See page 67 for details.

Ultra-SpillPallets®/Economy Model				
Item #	Description	Size	Load Capacity	Sump Capacity
<b>ULT2505</b>	2-Drum w/ Drain	53"Lx29"Wx16.5"H	1,500 lbs.	66.0 gal
<b>ULT2504</b>	2-Drum w/o Drain	53"Lx29"Wx16.5"H	1,500 lbs.	66.0 gal.
<b>ULT1113</b>	4-Drum w/ Drain	53"Lx53"Wx11.75"H	3,000 lbs.	66.0 gal.
<b>ULT1112</b>	4-Drum w/o Drain	53"Lx53"Wx11.75"H	3,000 lbs.	66.0 gal.



ULT9613

**Store Drums Outdoors, Leave Pumps in Place**

Extra headspace easily accommodates rotary drum pumps and large conical funnels. 100% polyethylene will not rust or corrode.

**Built for Convenience**

Low-profile containment pallet positions drum tops at a safe level to pour wastes into funnels or use drum pumps. Roll-top covers can be easily lifted from waist height to access drum tops without bending over. Swing out lower doors provide full access to drums for loading.

**Added Security and Safety**

Lockable with a standard padlock. Safely lift unit by forklift with drums in place.

Optional drain lets you empty sump without moving drums.

*These items are drop-shipped from vendor.*




ULT0676

A light-weight poly Ramp lets you load units using a drum truck. Stores inside when not in use.

**Ultra-Hard Top Plus® / Drums**

Item #	Description	Size	Load Capacity	Sump Capacity
<b>NEW ULT9636</b>	4-Drum w/o Drain	64.5"Lx62"Wx79"H	9,000 lbs.	75 gal.
<b>NEW ULT9637</b>	4-Drum w Drain	64.5"Lx62"Wx79"H	9,000 lbs.	75 gal.
<b>NEW ULT9612</b>	2-Drum w/o Drain	67.25"Lx41.25"Wx74"H	4,500 lbs.	66 gal.
<b>NEW ULT9613</b>	2-Drum w/ Drain	67.25"Lx41.25"Wx74"H	4,500 lbs.	66 gal.
<b>NEW ULT0676</b>	Hard Top Loading Ramp	46"Lx28"Wx8.75"H	n/a	n/a

**Ultra-Hard Top Plus® for IBC Tanks**



ULT1161

**Comply with Regs while Storing IBCs Outdoors**

Upper roll-top cover and swing out lower doors combine to allow easy and convenient access to IBC.

Low-profile containment pallet allows safe material handling and dispensing. Forkliftable, lockable, all-polyethylene design will not rust or corrode.

**Optional Plug for Greater Convenience**

Available with a drain plug to let you empty sump without relocating stored containers.

*These items are drop-shipped from vendor.*



When closed, the roll-top cover and swing out lower doors effectively keep rain, snow and debris away from stored containers and out of the sump.

**Ultra-Hard Top Plus® / IBC Tanks**

Item #	Description	Size	Load Capacity	Sump Capacity
<b>NEW ULT1161</b>	IBC w/ Drain	64.5"Lx62"Wx96"H	8,500 lbs.	360 gal.
<b>NEW ULT1162</b>	IBC w/o Drain	64.5"Lx62"Wx96"H	8,500 lbs.	360 gal.

## SpillPal™ Portable Spill Containment



Grates (ENP7006)  
sold separately.


### Affordable, Convenient Temporary Storage

It's hard to find comparable products on the market that are any easier to use than flexible-sidewall SpillPal™ Portable Spill Containment. Anytime you need temporary storage in a hurry, reach for this product to meet your containment needs.

### Quick, Easy Set-up

As an alternative to hard polyurethane pallets that must be moved with a forklift, the SpillPal™ is easy to move and has light foam sidewalls that spring back to their original shape after any type of pressure is applied to the product.

### Easy Set-Up and Take-Down:



SpillPal™ Containment is reusable — when you're done, just fold and store. Versatile design frees up valuable floor space.

### Everything you Need in a Single Package

No ramps or accessories are needed with the SpillPal™

Portable Containment deck. Flexible sidewalls spring back to form, so you can drive over them safely.

### SpillPal™ Portable Spill Containment

Item #	Description	Size	Load Cap.	Sump Cap.
ENP5760	4-Drum SpillPal™	4'Lx4'Wx4'H	n/a	40.0 gal.
ENP5755	2-Drum SpillPal™	2'Lx4'Wx4'H	n/a	20.0 gal.
ENP7006	Grates	4'Lx23"Wx1.75"H	1000 lbs.	n/a

## Containment Berm and Accessories

### Containment Berm

Large-sized Berm is ideal for large-scale spill containment beneath tanker trucks, roll-off containers and more. Easy-to-assemble, one-piece design permits immediate response, compact storage and transport.

Features excellent rip, tear and puncture resistance for demanding applications and rough terrain. Durable and sturdy unit is constructed of chemical-resistant materials. Berm is repairable and portable. Compatible with acids, water, oils and solvents, the Berm can be cleaned after use and stored for future use.


*These items are drop-shipped from vendor.*

### Ground Cover

Lightweight and reusable, this Ground Cover protects Berms from truck wheels or rough terrain. The Cover is placed underneath the Berm, directly on the ground and prevents underside punctures from sharp objects.

### Track Guard

Heavy-duty and reusable Track Guards protect your Containment Berm from tire abrasion. Placed inside the Berm, Track Guards allow trucks to drive in and out while protecting the berm from punctures and tears. Includes 2 Track Guards per package.



PAK1250

Fold down the sidewalls and drive right in for immediate containment. Our largest Berm holds up to 4,488 gallons of liquid!

### Containment Berm & Accessories

Item #	Description	Size	Sump Capacity
PAC48	Containment Berm	4'Lx8'Wx12'H	239.0 gal.
PAC88	Containment Berm	8'Lx8'Wx12'H	478.0 gal.
PAC1212	Containment Berm	12'Lx12'Wx12'H	1,077.0 gal.
PAC1212-CVR	Ground Cover for 12'x12'	15'Lx14'W	n/a
PAC1212-TRK	Track Guard for 12'x12'	24"Lx12'W	n/a
PAC1225	Containment Berm	12'Lx25'Wx12'H	2,244.0 gal.
PAC1225-CVR	Ground Cover for 12'x25'	15'Lx27'W	n/a
PAC1225-TRK	Track Guard for 12'x25'	24"Lx25'W	n/a
PAC1250	Containment Berm	12'Lx50'Wx12'H	4,488.0 gal.
PAC1250-CVR	Ground Cover for 12'x50'	15'Lx52'W	n/a
PAC1250-TRK	Track Guard for 12'x50'	24"Lx50'W	n/a



Helps you comply with 40 CFR 263.30(a) and 40 CFR 264.175. See page 67 for details.

## Poly-Collector™ and Accessories



### Poly-Drum Funnel™ — ENP3004

Fits both closed-head and open-head 55-gallon drums and other containers. Just set it in place and forget it. Features a high sidewall and bung-fitting holders.

*This item is drop-shipped from vendor.*

### Poly-Collector™ — ENP8075

Strong, tough 100% polyurethane outer shell holds 66 gallons. The Poly-Collector™ with the Poly-Drum Funnel™ in place prevents overflows while allowing multiple oil filters, cans or pails to drain at the same time. UV stabilized for a long, productive work life.

*This item is drop-shipped from vendor.*

### Drum Dolly — ENP8050

Stout Drum Dolly has casters wheels to support the Poly-Collector™ even when it's fully loaded. Allows easy movement of drums for dispensing and emptying.

*This item is drop-shipped from vendor.*

### Funnel/Poly-Collector™/Dolly

Item #	Description	Size	Units/Pkg
ENP3004	Universal Poly-Drum Funnel™	26" diam., 5.5"H	1
ENP8075	Poly-Collector™	32.5" diam., 31"H	1
ENP8050	Drum Dolly	27.5" diam., 5.5"H	1

## Poly-Dolly® Portable Dispensing Station



### Makes Old-Style Dispensers Obsolete

With a built-in 80-gallon sump, this amazing product virtually eliminates the need for old-style dispensers that offer no sump capacity.

### Dispensing is no Longer a Risky Business

Poly-Dolly® provides a safe and easy way to transport and dispense from 55-gallon drums. 100% polyethylene design with 10" wheels.

*This item is drop-shipped from vendor.*



Helps you comply with 40 CFR 264.175. See page 67 for details.

### Poly-Dolly®

Item #	Description	Size	Load Capacity	Sump Capacity
ENP5300	Poly-Dolly®	69"Lx32.5"Wx26.5"H	600 lbs.	80.0 gal.

## OverPack Dolly

### Move Containers Not Compatible with Standard Trucks

This Dolly is perfect for 95-gallon OverPacks, as well as for 30- and 55-gallon steel, poly or fiber drums.

### Safer, Easier Loading

The floating axle is spring loaded to balance containers and minimize movement while loading. Unique nose pads are set far apart to help avoid punctures. A belt securely holds containers of varying shape, size and construction.

*This item is drop-shipped from vendor.*

### Convenient Transport and Storage

10" wheels easily roll over most surfaces. Dolly is self-standing for storage.

**NEW**



Containment

### OverPack Dolly

Item #	Description	Size
NEW A-DOLLY	OverPack Dolly	24"Lx24"Wx60"H

Compatibility: W-Water O-Oil S-Solvents A-Aggressive

HighLoft Bonded / Universal Mat		Gray Bonded / Universal Mat (for oils, coolants, solvents and water)					Pages 4-5	
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #
GRB150G	HighLoft Roll	30" x 150"	1	39.8	21	W, O, S	yes	4,5
GPB100GL	HighLoft Pad	15" x 18"	100	19.5	42	W, O, S	yes	4,5

HighLoft Bonded / Oil-Only Mat		White Bonded / Oil-Only Mat (for oils, not water)					Pages 4-5	
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #
WRB150G	HighLoft Roll	30" x 150"	1	39.8	21	O	yes	4,5
WPB100GL	HighLoft Pad	15" x 18"	100	19.5	42	O	yes	4,5

HighLoft Meltblown / Oil-Only Mat		White Meltblown / Oil-Only Mat (for oils, not water)					Pages 4-5	
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #
WR150G	HighLoft Roll	30" x 150"	1	41.2	21	O	yes	4,5
WP100GL	HighLoft Pad	15" x 18"	100	19.7	42	O	yes	4,5

MeltBlown Mat / Oil-Only Mat		White MeltBlown / Oil-Only Mat (for oils, not water)					Pages 6-7	
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #
WP100H	HeavyWeight Pads	15" x 19"	100	33.4	30	O	yes	6,7
WPK50H	HeavyWeight King Pads	30" x 30"	50	52.8	15	O	yes	6,7
WP100M	MediumWeight Pads	15" x 19"	100	26.7	36	O	yes	6,7
WP100S	SingleWeight Pads	15" x 19"	100	17.9	48	O	yes	6,7
WP200S	SingleWeight Pads	15" x 19"	200	35.7	30	O	yes	6,7
WR150H	HeavyWeight Roll	30" x 150"	1	63.4	15	O	yes	6,7
WRS150H	HeavyWeight Split Rolls	15" x 150"	2	63.4	15	O	yes	6,7
WR150M	MediumWeight Roll	30" x 150"	1	50.7	21	O	yes	6,7
WRS150M	MediumWeight Split Rolls	15" x 150"	2	50.7	21	O	yes	6,7
WR300S	SingleWeight Roll	30" x 300"	1	67.9	15	O	yes	6,7
WRS300S	SingleWeight Split Rolls	15" x 300"	2	67.9	15	O	yes	6,7

Static-Dissipative / Oil-Only Mat		White Static-Dissipative / Oil-Only Mat (for oils, not water; to reduce sparks)					Page 7	
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #
WPX50S	SingleWeight Pads	15" x 19"	50	8.9	120	O	yes	7
WRX150H	HeavyWeight Roll	30" x 150"	1	63.4	15	O	yes	7
WPX25H	HeavyWeight Pads	15" x 19"	25	8.4	120	O	yes	7

SonicBonded / Universal Mat		Gray SonicBonded / Universal Mat (for oils, coolants, solvents and water)					Pages 8-9	
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #
GPB100H	HeavyWeight Pads	15" x 19"	100	29.1	30	W, O, S	yes	8,9
GPB50H	HeavyWeight Pads	15" x 19"	50	14.6	48	W, O, S	yes	8,9
GPKB50H	HeavyWeight King Pads	30" x 30"	50	45.3	15	W, O, S	yes	8,9
GPB100M	MediumWeight Pads	15" x 19"	100	24.7	36	W, O, S	yes	8,9
GPB200S	SingleWeight Pads	15" x 19"	200	31.1	30	W, O, S	yes	8,9
GPB100S	SingleWeight Pads	15" x 19"	100	15.6	48	W, O, S	yes	8,9
GRB150H	HeavyWeight Roll	30" x 150"	1	55.2	15	W, O, S	yes	8,9
GRSB150H	HeavyWeight Split Rolls	15" x 150"	2	55.2	15	W, O, S	yes	8,9
GRB150M	MediumWeight Roll	30" x 150"	1	46.1	21	W, O, S	yes	8,9
GRB300S	SingleWeight Roll	30" x 300"	1	59.1	15	W, O, S	yes	8,9

SonicBonded / Oil-Only Mat		White SonicBonded / Oil-Only Mat (for oils, not water)					Pages 8-9	
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #
WPB100H	HeavyWeight Pads	15" x 19"	100	29.1	30	O	yes	8,9
WPB50H	HeavyWeight Pads	15" x 19"	50	14.6	48	O	yes	8,9
WPKB50H	HeavyWeight King Pads	30" x 30"	50	45.3	15	O	yes	8,9
WPB100M	MediumWeight Pads	15" x 19"	100	24.7	36	O	yes	8,9
WPB50M	MediumWeight Pads	15" x 19"	50	12.4	48	O	yes	8,9
WPB200S	SingleWeight Pads	15" x 19"	200	31.1	30	O	yes	8,9
WPB100S	SingleWeight Pads	15" x 19"	100	15.6	48	O	yes	8,9
WRB150H	HeavyWeight Roll	30" x 150"	1	55.2	15	O	yes	8,9
WRB150M	MediumWeight Roll	30" x 150"	1	46.1	21	O	yes	8,9
WRB150M	MediumWeight Split Rolls	15" x 150"	2	46.1	21	O	yes	8,9
WRB300S	SingleWeight Roll	30" x 300"	1	59.1	15	O	yes	8,9

FineFiber / Oil-Only Mat		White FineFiber / Oil-Only Mat (for oils, not water)					Pages 10-11	
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #
WPF100H	HeavyWeight Pads	15" x 19"	100	26.3	30	O	yes	10,11
WPF1113H	HeavyWeight Pads	11" x 13"	100	18.1	60	O	yes	10,11 & 47
WPF100H-BX	HeavyWeight Pads in Box	15" x 19"	100	26.3	30	O	yes	10,11
WPKF50H	HeavyWeight King Pads	30" x 30"	50	41.6	15	O	yes	10,11
WPF100M	MediumWeight Pads	15" x 19"	100	20.8	36	O	yes	10,11
WPF200S	SingleWeight Pads	15" x 19"	200	28.1	30	O	yes	10,11
WRF150H	HeavyWeight Roll	30" x 150"	1	49.8	15	O	yes	10,11
WRF24150H	HeavyWeight Roll	24" x 150"	1	39.8	18	O	yes	10,11
WRF100H-BX	HeavyWeight Roll in Box	15" x 100"	1	19.3	30	O	yes	10,11
WRSF150H	HeavyWeight Split Rolls	15" x 150"	2	49.8	15	O	yes	10,11
WRF150M	MediumWeight Roll	30" x 150"	1	39.5	21	O	yes	10,11
WRSF150M	MediumWeight Split Rolls	15" x 150"	2	39.5	21	O	yes	10,11

**Compatibility: W-Water O-Oil S-Solvents A-Aggressive**

<b>FineFiber / Oil-Only Mat</b>		<b>Blue FineFiber / Oil-Only Mat (for oils, not water)</b>						<b>Pages 10-11</b>	
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #	
BPF100H	HeavyWeight Pads	15" x 19"	100	26.3	30	O	yes	10,11	
BPF100H-BX	HeavyWeight Pads in Box	15" x 19"	100	26.3	30	O	yes	10,11	
BPKF50H	HeavyWeight King Pads	30" x 30"	50	41.6	15	O	yes	10,11	
BPF200S	SingleWeight Pads	15" x 19"	200	28.1	30	O	yes	10,11	
BRF150H	HeavyWeight Roll	30" x 150'	1	49.8	15	O	yes	10,11	
BRF100H-BX	HeavyWeight Roll in Box	15" x 100'	1	19.3	30	O	yes	10,11	

<b>FineFiber / Universal Mat</b>		<b>Green FineFiber / Universal Mat (for oils, coolants, solvents and water)</b>						<b>Pages 12-13</b>	
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #	
GNPF100H	HeavyWeight Pads	15" x 19"	100	26.3	30	W, O, S	yes	12,13	
GNPF100H-BX	HeavyWeight Pads in Box	15" x 19"	100	26.3	30	W, O, S	yes	12,13	
GNPF100M	MediumWeight Pads	15" x 19"	100	20.8	36	W, O, S	yes	12,13	
GNRF150H	HeavyWeight Roll	30" x 150'	1	49.8	15	W, O, S	yes	12,13	
GNRSF150H	HeavyWeight Split Rolls	15" x 150'	2	49.8	15	W, O, S	yes	12,13	

<b>FineFiber / Universal Mat</b>		<b>Gray FineFiber / Universal Mat (for oils, coolants, solvents and water)</b>						<b>Pages 12-13</b>	
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #	
GPF100H	HeavyWeight Pads	15" x 19"	100	26.3	30	W, O, S	yes	12,13	
GPF1113H	HeavyWeight Pads	11" x 13"	100	18.1	60	W, O, S	yes	12,13 & 47	
GPF100H-BX	HeavyWeight Pads in Disp Box	15" x 19"	100	26.3	30	W, O, S	yes	12,13	
GPKF50H	HeavyWeight King Pads	30" x 30"	50	41.6	15	W, O, S	yes	12,13	
GPF100M	MediumWeight Pads	15" x 19"	100	20.8	36	W, O, S	yes	12,13	
GPF200S	SingleWeight Pads	15" x 19"	200	28.1	30	W, O, S	yes	12,13	
GRF150H	HeavyWeight Roll	30" x 150'	1	49.8	15	W, O, S	yes	12,13	
GRF24150H	HeavyWeight Roll	24" x 150'	1	39.8	18	W, O, S	yes	12,13	
GRF100H-BX	HeavyWeight Roll in Disp Box	15" x 100'	1	19.3	30	W, O, S	yes	12,13	
GRSF150H	HeavyWeight Split Rolls	15" x 150'	2	49.8	15	W, O, S	yes	12,13	
GRFF50H	HeavyWeight Folded Roll in Disp Box	5" x 50'	1	8.4	42	W, O, S	yes	12,13	
GRF150M	MediumWeight Roll	30" x 150'	1	39.5	21	W, O, S	yes	12,13	
GRSF150M	MediumWeight Split Rolls	15" x 150'	2	39.5	21	W, O, S	yes	12,13	
GRF300S	SingleWeight Roll	30" x 300'	1	53.4	15	W, O, S	yes	12,13	
GRSF300S	SingleWeight Split Rolls	15" x 300'	2	53.4	15	W, O, S	yes	12,13	

<b>Drip, Rip and Go™ Tablet</b>		<b>Drip, Rip and Go™ Tablet (for oils, coolants, solvents and water)</b>						<b>Page 13</b>	
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #	
GPF20S	Drip, Rip and Go- Tablet	14.25" x 19"	9	25.2	24	W, O, S	yes	13	

<b>MultiLaminate / Univ. Mat</b>		<b>Gray MultiLaminate / Universal Mat (for oils, coolants, solvents and water)</b>						<b>Pages 14-15</b>	
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #	
GPL100H	HeavyWeight Pads	15" x 19"	100	28.9	30	W, O, S	yes	14,15	
GPL100M	MediumWeight Pads	15" x 19"	100	23.4	36	W, O, S	yes	14,15	
GRL150H	HeavyWeight Roll	30" x 150'	1	54.9	15	W, O, S	yes	14,15	
GRSL150H	HeavyWeight Split Rolls	15" x 150'	2	54.9	15	W, O, S	yes	14,15	
GRL150M	MediumWeight Roll	30" x 150'	1	44.4	21	W, O, S	yes	14,15	
GRSL150M	MediumWeight Split Rolls	15" x 150'	2	44.4	21	W, O, S	yes	14,15	

<b>MultiLaminate / Oil-Only Mat</b>		<b>White or Blue MultiLaminate / Oil-Only Mat (for oils, not water)</b>						<b>Pages 14-15</b>	
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #	
WPL100H	HeavyWeight Pads	15" x 19"	100	28.9	30	O	yes	14,15	
WPL100M	MediumWeight Pads	15" x 19"	100	23.4	36	O	yes	14,15	
WRL150H	HeavyWeight Roll	30" x 150'	1	54.9	15	O	yes	14,15	
WRL150M	MediumWeight Roll	30" x 150'	1	44.4	21	O	yes	14,15	
WRSL150M	MediumWeight Split Rolls	15" x 150'	2	44.4	21	O	yes	14,15	
WRSL150H	HeavyWeight Split Rolls	15" x 150'	2	54.9	15	O	yes	14,15	
BPL100H	HeavyWeight Pads	15" x 19"	100	28.9	30	O	yes	14,15	

<b>AirLaid / Universal Mat</b>		<b>Gray AirLaid / Universal Mat (for oils, coolants, solvents and water)</b>						<b>Pages 16-17</b>	
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #	
GPA100H	HeavyWeight Pads	15" x 19"	100	31.1	30	W, O, S	yes	16,17	
GPKA50H	HeavyWeight King Pads	30" x 30"	50	49.3	15	W, O, S	yes	16,17	
GRA150H	HeavyWeight Roll	30" x 150'	1	60.0	15	W, O, S	yes	16,17	
GRSA150H	HeavyWeight Split Rolls	15" x 150'	2	60.0	15	W, O, S	yes	16,17	

<b>AirLaid / Oil-Only Mat</b>		<b>White AirLaid / Oil-Only Mat (for oils, not water)</b>						<b>Pages 16-17</b>	
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #	
WPA100H	HeavyWeight Pads	15" x 19"	100	31.1	30	O	yes	16,17	
WPKA50H	HeavyWeight King Pads	30" x 30"	50	49.3	15	O	yes	16,17	
WRA150H	HeavyWeight Roll	30" x 150'	1	60.0	15	O	yes	16,17	
WRSA150H	HeavyWeight Split Rolls	15" x 150'	2	60.0	15	O	yes	16,17	

**Complete Product SpecSheet**

SurvivorSeries™ / Universal Mat		Camouflage SurvivorSeries™ Mat (for oils, coolants, solvents and water)						Pages 18-19	
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #	
SVP100H	HeavyWeight Pads	15" x 19"	100	17.9	30	W, O, S	yes	18,19	
SVR150H	HeavyWeight Roll	30" x 150"	1	35.8	15	W, O, S	yes	18,19	
SVRS150H-1	HeavyWeight Split	15" x 150"	1	17.9	30	W, O, S	yes	18,19	
SVRS150H-2	HeavyWeight Split Rolls	15" x 150"	2	35.8	15	W, O, S	yes	18,19	

SurvivorSeries™ / Universal Mat		Gray SurvivorSeries™ Mat (for oils, coolants, solvents and water)						Pages 18-19	
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #	
GRSMF100H-BX	HeavyWeight Roll	15" x 100"	1	18.9	30	W, O, S	yes	18,19	

SurvivorSeries™ / Oil-Only Mat		White SurvivorSeries™ Mat / Oil-Only (for oils, not water)						Pages 18-19	
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #	
WRSMF100H-BX	HeavyWeight Roll in Box	15" x 100"	1	18.9	30	O	yes	18,19	

EcoTech™ / Universal Mat		Gray EcoTech™ Mat (for oils, coolants, solvents and water)						Pages 20-21	
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #	
UCP100HW	HeavyWeight Pads	15" x 19"	100	30.2	18	W, O, S	yes	20,21	
UCP100LW	LightWeight Pads	15" x 19"	100	21.2	24	W, O, S	yes	20,21	
UCR150HW	HeavyWeight Roll	30" x 150"	1	57.2	10	W, O, S	yes	20,21	
UCR150LW	LightWeight Roll	30" x 150"	1	40	16	W, O, S	yes	20,21	

SonicBonded / HazMat Mat		Yellow SonicBonded HazMat Mat (for acids, bases and unknown liquids)						Pages 22-23	
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #	
YPB100H	HeavyWeight Pads	15" x 19"	100	29.1	30	A, W, O, S	yes	22,23	
YPB50H	HeavyWeight Pads	15" x 19"	50	14.6	48	A, W, O, S	yes	22,23	
YPB100M	MediumWeight Pads	15" x 19"	100	24.7	36	A, W, O, S	yes	22,23	
YPB50M	MediumWeight Pads	15" x 19"	50	12.4	48	A, W, O, S	yes	22,23	
YPB200S	SingleWeight Pads	15" x 19"	200	31.1	30	A, W, O, S	yes	22,23	
YPB100S	SingleWeight Pads	15" x 19"	100	15.6	48	A, W, O, S	yes	22,23	
YRB150H	HeavyWeight Roll	30" x 150"	1	55.2	15	A, W, O, S	yes	22,23	
YRSB150H	HeavyWeight Split Rolls	15" x 150"	2	55.2	15	A, W, O, S	yes	22,23	
YRB150M	MediumWeight Roll	30" x 150"	1	46.1	21	A, W, O, S	yes	22,23	

FineFiber / HazMat Mat		Yellow FineFiber HazMat Mat (for acids, bases and unknown liquids)						Pages 22-23	
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #	
YPF100H	HeavyWeight Pads	15" x 19"	100	26.3	30	A, W, O, S	yes	22,23	
YPF1113H	HeavyWeight Pads	11" x 13"	100	18.1	60	A, W, O, S	yes	22,23 & 47	
YRF150H	HeavyWeight Roll	30" x 150"	1	49.8	15	A, W, O, S	yes	22,23	
YRSF150H	HeavyWeight Split Rolls	15" x 150"	2	49.8	15	A, W, O, S	yes	22,23	

HazMat Products		Yellow HazMat Socks, Booms and Pillows (for acids, bases and unknown liquids)						Pages 22-23	
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #	
YSO410	HazMat Socks	3" x 4'	10	8.33	30	A, W, O, S	yes	22, 23	
YSO430	HazMat Socks	3" x 4'	30	25	16	A, W, O, S	yes	22, 23	
YSO815	HazMat Socks	3" x 8'	15	25	16	A, W, O, S	yes	22, 23	
YSO1210	HazMat Socks	3" x 12'	10	25	16	A, W, O, S	yes	22, 23	
HZ510SN	HazMat Booms	5" x 10'	4	23.3	16	A, W, O, S	yes	22, 23	
HZ810SN	HazMat Booms	8" x 10'	4	33.9	12	A, W, O, S	yes	22, 23	
YPIL818	HazMat Pillows	8" x 18"	20	26.8	35	A, W, O, S	yes	22,23	
YPIL1818	HazMat Pillows	18" x 18"	10	29.1	35	A, W, O, S	yes	22, 23	

DrumTop Pads		DrumTop Pads						Page 24	
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #	
GTOP	Universal DrumTop Pads	23" diam.	25	8.6	72	W, O, S	yes	24	
BTOP	Oil-Only DrumTop Pads	23" diam.	25	8.6	72	O	yes	24	

Sorbent Mat Wringer		Sorbent Wringer						Page 24	
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #	
A-WRINGER	Sorbent Mat Wringer	15"W x 12"H	1	n/a	100	n/a	no	24	

Pad Box		Flat Pad Box						Page 24	
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #	
A-PADBOX	Pad Box	15.5"L x 19.25"W x 16"H	1	n/a	150	n/a	yes	24	

Free-Standing RollRack		Free-Standing RollRack						Page 24	
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #	
A-ROLLRACK	Free-Standing RollRack	For rolls up to 40"W	1	n/a	20	n/a	no	24	

**Compatibility:** **A-Aggressive** **S-Solvents** **O-Oil** **W-Water**

Industrial Rugs								NeedlePunch, RagRug, StitchBonded, PolyBacked and RailRoad		Pages 25-27
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #		
PBR100	PolyBacked Rug Roll	36" x 100'	1	13.0	20	W, O, S	yes	25		
RIG160H	HeavyWeight Roll	58" x 160'	1	147.2	6	O	yes	25		
PBRIG48H	HeavyWeight PolyBacked Roll	57" x 48'	1	44.1	12	O	yes	25		
NPR150H-GR	NeedlePunch Rug (16oz, gray)	36" x 150'	1	54.0	12	W, O, S	yes	26		
NPR300S-GR	NeedlePunch Rug (8oz, gray)	36" x 300'	1	54.0	12	W, O, S	yes	26		
RRUG36H	RagRug Roll	36" x 150'	1	84.6	24	W, O, S	yes	26		
RRUG18H	RagRug Split Rolls	18" x 150'	2	84.6	12	W, O, S	yes	26		
RRUGP100H	RagRug Pads	18" x 18"	100	38.9	16	W, O, S	yes	26		
MR2089	StitchBonded Mat Roll	33" x 150'	1	23.0	24	W, O, S	yes	27		
TMAT57	HeavyWeight Roll for inside rails	57" x 80'	1	63.2	6	O	yes	27		
TMAT19	HeavyWeight Split Rolls for outside rails	19" x 80'	2	41.7	12	O	yes	27		
RRMAT60	RailRoad Mat Roll	59" x 100'	1	59.0	6	O	yes	27		
RRMAT19	RailRoad Mat Rolls	19" x 100'	2	38.0	6	O	yes	27		

PolyBacked FineFiber / Universal Mat								PolyBacked FineFiber / Universal Mat (for oils, coolants, solvents and water)		Page 25
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #		
PBGGPF50H	HeavyWeight Pads	15" x 19"	50	8.1	42	W, O, S	no	25		
PBGRF100H	HeavyWeight Roll	30" x 100'	1	18.0	20	W, O, S	no	25		

Socks / Oil-Only								Oil-Only Socks (for oils, not water)		Page 28
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #		
WSO410	Oil-Only Socks	3" x 4'	10	8.33	30	O	yes	28		
WSO430	Oil-Only Socks	3" x 4'	30	25.0	16	O	yes	28		
WSO815	Oil-Only Socks	3" x 8'	15	25.0	16	O	yes	28		
WSO1210	Oil-Only Socks	3" x 12'	10	25.0	16	O	yes	28		

Socks / HazMat								HazMat Socks (for acids, bases and unknown liquids)		Page 28
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #		
YSO410	HazMat Socks	3" x 4'	10	8.33	30	A, W, O, S	yes	22, 23, 28		
YSO430	HazMat Socks	3" x 4'	30	25.0	16	A, W, O, S	yes	22, 23, 28		
YSO815	HazMat Socks	3" x 8'	15	25.0	16	A, W, O, S	yes	22, 23, 28		
YSO1210	HazMat Socks	3" x 12'	10	25.0	16	A, W, O, S	yes	22, 23, 28		

Socks / Universal								Universal Socks (for oils, coolants, solvents and water)		Page 29
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #		
GSO430	Universal Socks	3" x 4'	30	25.0	16	W, O, S	yes	29		
GSO815	Universal Socks	3" x 8'	15	25.0	16	W, O, S	yes	29		
GSO1210	Universal Socks	3" x 12'	10	25.0	16	W, O, S	yes	29		

Socks / CornCob								CornCob Socks (for oils, coolants, solvents and water)		Page 29
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #		
CCSO40	CornCob Socks	3" x 42"	40	20.0	16	W, O, S	yes	29		

Socks / Cellulose								Cellulose Socks (for oils, coolants, solvents and water)		Page 29
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #		
GCSO430	Cellulose Socks	3" x 4'	30	32.3	16	W, O, S	yes	29		
GCSO815	Cellulose Socks	3" x 8'	15	32.3	16	W, O, S	yes	29		
GCSO1210	Cellulose Socks	3" x 12'	10	32.3	16	W, O, S	yes	29		

Pillows								Pillows / Universal and Oil-Only		Page 30
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #		
GPIL1818	Universal Pillows	18" x 18"	10	29.1	35	W, O, S	yes	30		
GPIL818	Universal Pillows	8" x 18"	20	26.8	35	W, O, S	yes	30		
WPIL1818	Oil-Only Pillows	18" x 18"	10	29.1	35	O	yes	30		
WPIL818	Oil-Only Pillows	8" x 18"	20	26.8	35	O	yes	30		

Pans / Pillow in a Pan								Pillow in a Pan / Universal and Oil-Only		Page 31
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #		
GPIL1224	Universal Pillow in a Pan	10.5" sq. x 3"H	12 pans & 24 pillows	20.7	35	W, O, S	yes	31		
GPIL1010	Universal Pillows	10" sq.	40	24	35	W, O, S	yes	31		
WPIL1224	Oil-Only Pillow in a Pan	10.5" sq. x 3"H	12 pans & 24 pillows	20.7	35	O	yes	31		
WPIL1010	Oil-Only Pillows	10" sq.	40	24	35	O	yes	31		

Pans / DripPan								DripPan / Universal and Oil-Only		Page 31
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #		
DPU-16	Universal DripPan	10.5" sq. x 3"H	16	12.0	20	W, O, S	no	31		
DPO-16	Oil-Only DripPan	10.5" sq. x 3"H	16	12.0	20	O	no	31		

**Complete Product SpecSheet**

WaterWick		WaterWick (for water, not oils)						Page 32
Item #	Description	Size	Units/Package	Absorbs/Pkg.	Qty./Pallet	Compatibility	Incinerable?	Page #
WW10	WaterWick	1" Dia. x 9" L	1	3 oz.	n/a	W	yes	32
WW15	WaterWick	1.5" Dia. x 12" L	1	8 oz.	n/a	W	yes	32
WW20	WaterWick	2" Dia. x 12" L	1	12 oz.	n/a	W	yes	32
WW35	WaterWick	3.5" Dia. x 12" L	1	36 oz.	n/a	W	yes	32

Booms / Universal		Universal Boom (for oils, coolants, solvents and water)						Page 32
Item #	Description	Size	Units/Package	Absorbs/Pkg.	Qty./Pallet	Compatibility	Incinerable?	Page #
GB510SN	Universal Boom	5" x 10'	4	23.3 gal.	16	W, O, S	yes	32

WellHead Socks		WellHead Socks (for oils, not water)						Page 32
Item #	Description	Size	Units/Package	Absorbs/Pkg.	Qty./Pallet	Compatibility	Incinerable?	Page #
WSWH4210	WellHead Socks	5" x 42"	10	27.5 gal.	16	O	yes	32

Loose Sorbents		Loose Sorbents / Universal and Oil-Only (*Sold only in pallet quantities)						Page 33
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #
*CELL30	Gran-sorb™ Loose Sorbent	30-lb. Bag	1	4.0	65	W, O, S	yes	33
*COB40	Loose CornCob	40-lb. Bag	1	8.5	50	W, O, S	yes	33
*MR1020	Lite-Zorb Loose Sorbent	25-lb. Bag	1	5.4	80	W, O, S	yes	33
SS12	SuperSorbent Loose Sorbent	28-oz. Shakers	12	7.0	60	W, O, S	yes	33
*PEAT2	Loose Peat Moss	2 cu. ft.	1	25.0	50	O	yes	33
*WPART	Oil-Only Particulate	25-lb. Bag	1	58.1	15	O	yes	33
ANS5	Acid Neutralizing Sorbent	5-gal. Pail	1	2.5	40	A	yes	33

Booms / Oil-Only		Booms (for oils, not water)						Page 34
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #
WB410SN	Sock/Net Booms	4" x 10'	4	19.5	20	O	yes	34
WB510SN	Sock/Net Booms	5" x 10'	4	30.0	16	O	yes	34
WB520SN	Sock/Net Booms	5" x 20'	2	30.0	16	O	yes	34
WB810SN	Sock/Net Booms	8" x 10'	4	38.0	12	O	yes	34
WB820SN	Sock/Net Booms	8" x 20'	2	38.0	12	O	yes	34
WBB318	Bilge Booms	3" x 18"	20	6.25	30	O	yes	34
WBB818	Bilge Booms	8" x 18"	10	18.0	15	O	yes	34

Spill Response Products		PomPoms, Net Bags, Loose Particulate and Sweep (for oils, not water)						Page 35
Item #	Description	Size	Units/Package	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #
APMPM	PomPoms - 30 Individual	n/a	30	11.6	30	O	yes	35
APMPM-R	PomPoms - 30 on 50ft rope	50'	1	11.6	30	O	yes	35
WPIL10	Net Bags	6"D x 16"W x 21"H	10	37.0	15	O	yes	35
WPART	Oil-Only Particulate	25-lb. Bag	1	58.1	15	O	yes	35
WSWL100F	Folded Sweep	19"W x 100'L	1	16.2	36	O	yes	35

Containment Boom & Anchor System		Containment & Anchor System						Page 36
Item #	Description	Size	Units/Package	Capacity	Qty./Pallet	Compatibility	Incinerable?	Page #
C-BOOM10-50	Containment Boom	50'L x 10"H	1	n/a	1	n/a	no	36
C-BOOM10-100	Containment Boom	100'L x 10"H	1	n/a	1	n/a	no	36
C-BOOM18-50	Containment Boom	50'L x 18"H	1	n/a	1	n/a	no	36
C-BOOM18-100	Containment Boom	100'L x 18"H	1	n/a	1	n/a	no	36
C-BOOM24-50	Containment Boom	50'L x 24"H	1	n/a	1	n/a	no	36
C-BOOM24-100	Containment Boom	100'L x 24"H	1	n/a	1	n/a	no	36
C-ANCHOR	Containment Boom Anchor System	22-lb. Anchor	1	n/a	8	n/a	no	36

Spill Kits / 95-Gallon Recycled		95-Gallon Recycled Spill Kits						Page 38
Item #	Description	Size	Refill Kit #	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #
SPKU-95-RC	95-Gal Recycled Kit/Universal	31.75" diam., 41.5"H	RSPKU-95-RC	87.0	1	W, O, S	no	38
RSPKU-95-RC	Refill Kit for 95-Gal Kit/Universal	Call for shipping info	n/a	87.0	1	W, O, S	no	38
SPKO-95-RC	95-Gal Recycled Kit/Oil-Only	31.75" diam., 41.5"H	RSPKO-95-RC	87.0	1	O	no	38
RSPKU-95-RC	Refill Kit for 95-Gal Kit/Oil-Only	Call for shipping info	n/a	87.0	1	O	no	38

Spill Kits / 95-Gallon		95-Gallon Spill Kits						Page 38
Item #	Description	Size	Refill Kit #	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #
SPKU-95	95-Gal Kit/Universal	31.75" diam., 41.5"H	RSPKU-95	84.0	1	W, O, S	no	38
RSPKU-95	Refill Kit for 95-Gal Kit/Universal	Call for shipping info	n/a	84.0	10	W, O, S	no	38
SPKO-95	95-Gal Kit/Oil-Only	31.75" diam., 41.5"H	RSPKO-95	84.0	1	O	no	38
RSPKO-95	Refill Kit for 95-Gal Kit/Oil-Only	Call for shipping info	n/a	84.0	10	O	no	38
SPKHZ-95	95-Gal Kit/HazMat	31.75" diam., 41.5"H	RSPKHZ-95	84.0	1	A, W, O, S	no	38
RSPKHZ-95	Refill Kit for 95-Gal Kit/HazMat	Call for shipping info	n/a	84.0	10	A, W, O, S	no	38
A95OVER	95-Gal Empty OverPack	32" diam., 41.5"H	n/a	n/a	Nest 4 High	n/a	no	38 & 44

Spill Kits / 95-Gallon Wheeled		95-Gallon Spill Kits with Wheels						Page 38
Item #	Description	Size	Refill Kit #	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #
SPKU-95-WD	95-Gal Kit w/ Wheels/Universal	32" diam., 47"H	RSPKU-95	84.0	1	W, O, S	no	38
RSPKU-95	Refill Kit for 95-Gal Kit/Universal	Call for shipping info	n/a	84.0	10	W, O, S	no	38
SPKO-95-WD	95-Gal Kit w/ Wheels/Oil-Only	32" diam., 47"H	RSPKO-95	84.0	1	O	no	38
RSPKO-95	Refill Kit for 95-Gal Kit/Oil-Only	Call for shipping info	n/a	84.0	10	O	no	38
SPKHZ-95-WD	95-Gal Kit w/ Wheels/HazMat	32" diam., 47"H	RSPKHZ-95	84.0	1	A, W, O, S	no	38
RSPKHZ-95	Refill Kit for 95-Gal Kit/HazMat	Call for shipping info	n/a	84.0	10	A, W, O, S	no	38
A95OVER-WD	95-Gal Empty OverPack w/ Wheels	32" diam., 47.5"H	n/a	n/a	3	n/a	no	38 & 44

**Compatibility: W-Water O-Oil S-Solvents A-Aggressive**

Spill Kits / 65-Gallon		65-Gallon Spill Kits						Page 39
Item #	Description	Size	Refill Kit #	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #
SPKU-65	65-Gal Kit/Universal	28.25" diam., 37.37"H	RSPKU-65	47.4	2	W, O, S	no	39
RSPKU-65	Refill Kit for 65-Gal Kit/Universal	Call for shipping info	n/a	47.4	12	W, O, S	no	39
SPKO-65	65-Gal Kit/Oil-Only	28.25" diam., 37.37"H	RSPKO-65	47.4	2	O	no	39
RSPKO-65	Refill Kit for 65-Gal Kit/Oil-Only	Call for shipping info	n/a	47.4	12	O	no	39
SPKHZ-65	65-Gal Kit/HazMat	28.25" diam., 37.37"H	RSPKHZ-65	47.4	2	A, W, O, S	no	39
RSPKHZ-65	Refill Kit for 65-Gal Kit/HazMat	Call for shipping info	n/a	47.4	12	A, W, O, S	no	39
A65OVER	65-Gal Empty OverPack	28.25" diam., 37.5"H	n/a	n/a	8	n/a	no	39 & 44

Spill Kits / 50-Gallon		50-Gallon Spill Kits						Page 39
Item #	Description	Size	Refill Kit #	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #
SPKU-50-WD	50-Gal Kit w/ Wheels/Universal	24.5" diam., 39.5"H	RSPKU-50	45.7	4	W, O, S	no	39
RSPKU-50	Refill Kit for 50-Gal Kit/Universal	Call for shipping info	n/a	45.7	10	W, O, S	no	39
SPKO-50-WD	50-Gal Kit w/ Wheels/Oil-Only	24.5" diam., 39.5"H	RSPKO-50	45.7	4	O	no	39
RSPKO-50	Refill Kit for 50-Gal Kit/Oil-Only	Call for shipping info	n/a	45.7	10	O	no	39
SPKHZ-50-WD	50-Gal Kit w/ Wheels/HazMat	24.5" diam., 39.5"H	RSPKHZ-50	45.7	4	A, W, O, S	no	39
RSPKHZ-50	Refill Kit for 50-Gal Kit/Oil-Only	Call for shipping info	n/a	45.7	10	A, W, O, S	no	39
A50OVER-WD	50-Gal Empty OverPack w/ Wheels	24.5" diam., 45.5"H	n/a	n/a	6	n/a	no	39 & 44

Spill Kits / 30-Gallon		30-Gallon Spill Kits						Page 39
Item #	Description	Size	Refill Kit #	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #
SPKU-30	30-Gal Kit/Universal	23" diam., 30"H	RSPKU-30	25.6	8	W, O, S	no	39
RSPKU-30	Refill Kit for 30-Gal Kit/Universal	Call for shipping info	n/a	25.6	30	W, O, S	no	39
SPKO-30	30-Gal Kit/Oil-Only	23" diam., 30"H	RSPKO-30	25.6	8	O	no	39
RSPKO-30	Refill Kit for 30-Gal Kit/Oil-Only	Call for shipping info	n/a	25.6	30	O	no	39
SPKHZ-30	30-Gal Kit/HazMat	23" diam., 30"H	RSPKHZ-30	25.6	8	A, W, O, S	no	39
RSPKHZ-30	Refill Kit for 30-Gal Kit/HazMat	Call for shipping info	n/a	25.6	30	A, W, O, S	no	39
A30OVER	30-Gal Empty OverPack	23" diam., 30.75"H	n/a	n/a	20	n/a	no	39 & 44

Spill Kits / 20-Gallon		20-Gallon Spill Kits						Page 39
Item #	Description	Size	Refill Kit #	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #
SPKU-20	20-Gal Kit/Universal	23" diam., 19"H	RSPKU-20	16.4	16	W, O, S	no	39
RSPKU-20	Refill Kit for 20-Gal Kit/Universal	Call for shipping info	n/a	16.4	32	W, O, S	no	39
SPKO-20	20-Gal Kit/Oil-Only	23" diam., 19"H	RSPKO-20	16.4	16	O	no	39
RSPKO-20	Refill Kit for 20-Gal Kit/Oil-Only	Call for shipping info	n/a	16.4	32	O	no	39
SPKHZ-20	20-Gal Kit/HazMat	23" diam., 19"H	RSPKHZ-20	16.4	16	A, W, O, S	no	39
RSPKHZ-20	Refill Kit for 20-Gal Kit/HazMat	Call for shipping info	n/a	16.4	32	A, W, O, S	no	39
A20OVER	20-Gal Empty OverPack	23" diam., 19"H	n/a	n/a	40	n/a	no	39, 41 & 44

Spill Kits / 5-Gallon		5-Gallon Spill Kits						Page 40
Item #	Description	Size	Refill Kit #	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #
SPKU-5	5-Gal Kit/Universal	12" diam., 16.75"H	n/a	4.6	24	W, O, S	no	40
SPKO-5	5-Gal Kit/Oil-Only	12" diam., 16.75"H	n/a	4.6	24	O	no	40
SPKHZ-5	5-Gal Kit/HazMat	12" diam., 16.75"H	n/a	4.6	24	A, W, O, S	no	40
A5OVER	5-Gal Pall w/ Screw-Top Lid	12" diam., 16.75"H	n/a	n/a	72	n/a	no	40, 41 & 44

Spill Kaddie Kits		Spill Kaddie Kits						Page 40
Item #	Description	Size	Refill Kit #	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #
SPKU-KAD2	Spill Kaddie Kit/Universal	40"H x 20"W x 20"D	RSPKU-KAD	28.5	8	W, O, S	no	40
RSPKU-KAD	Refill Kit for Spill Kaddie Kit/Universal	Call for shipping info	n/a	28.5	30	W, O, S	no	40
SPKO-KAD2	Spill Kaddie Kit/Oil-Only	40"H x 20"W x 20"D	RSPKO-KAD	28.5	8	O	no	40
RSPKO-KAD	Refill Kit for Spill Kaddie Kit/Oil-Only	Call for shipping info	n/a	28.5	30	O	no	40
SPKHZ-KAD2	Spill Kaddie Kit/HazMat	40"H x 20"W x 20"D	RSPKHZ-KAD	28.5	8	A, W, O, S	no	40
RSPKHZ-KAD	Refill Kit for Spill Kaddie Kit/HazMat	Call for shipping info	n/a	28.5	30	A, W, O, S	no	40
A-KADDIE	Empty Spill Kaddie	40"H x 20"W x 20"D	n/a	n/a	8	n/a	no	40 & 44

Spill Cart Kits		Spill Cart Kits						Page 40
Item #	Description	Size	Refill Kit #	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #
SPKU-CART5	Spill Cart Kit w/5" Wheels/Universal	48"H x 31"W x 31.5"D	RSPKU-CART	88.2	1	W, O, S	no	40
SPKU-CART8	Spill Cart Kit w/8" Wheels/Universal	48"H x 31"W x 31.5"D	RSPKU-CART	88.2	1	W, O, S	no	40
RSPKU-CART	Refill Kit for Cart Kit/Universal	Call for shipping info	n/a	88.2	6	W, O, S	no	40
SPKO-CART5	Spill Cart Kit w/5" Wheels/Oil-Only	48"H x 31"W x 31.5"D	RSPKO-CART	109.9	1	O	no	40
SPKO-CART8	Spill Cart Kit w/8" Wheels/Oil-Only	48"H x 31"W x 31.5"D	RSPKO-CART	109.9	1	O	no	40
RSPKO-CART	Refill Kit for Cart Kit/Oil-Only	Call for shipping info	n/a	109.9	6	O	no	40
SPKHZ-CART5	Spill Cart Kit w/5" Wheels/HazMat	48"H x 31"W x 31.5"D	RSPKHZ-CART	82.0	1	A, W, O, S	no	40
SPKHZ-CART8	Spill Cart Kit w/8" Wheels/HazMat	48"H x 31"W x 31.5"D	RSPKHZ-CART	82.0	1	A, W, O, S	no	40
RSPKHZ-CART	Refill Kit for Cart Kit/HazMat	Call for shipping info	n/a	82.0	7	A, W, O, S	no	40
A-UTILITYBOX5	Empty Spill Cart w/5" Wheels	48"H x 31"W x 31.5"D	n/a	15 Cu. Ft. Capacity	Nest 5 High	n/a	no	40 & 44
A-UTILITYBOX8	Empty Spill Cart w/8" Wheels	48"H x 31"W x 31.5"D	n/a	15 Cu. Ft. Capacity	Nest 5 High	n/a	no	40 & 44

Fleet Kits		Fleet Kits						Page 41
Item #	Description	Size	Units/Package	Absorbs/Pkg	Qty./Pallet	Compatibility	Incinerable?	Page #
SPKU-FLEET	Fleet Kit/Universal	20"H x 17"W x 8"D	1	10.7	32	W, O, S	no	41
SPKO-FLEET	Fleet Kit/Oil-Only	20"H x 17"W x 8"D	1	10.7	32	O	no	41
SPKHZ-FLEET	Fleet Kit/HazMat	20"H x 17"W x 8"D	1	10.7	32	A, W, O, S	no	41
A-YTOTE	Empty Tote Bag	20"H x 17"W x 8"D	1	n/a	1000	n/a	no	41 & 44

Trucker Spill Kits		Trucker Spill Kits						Page 41
Item #	Description	Size	Units/Package	Absorbs/Pkg	Qty./Pallet	Compatibility	Incinerable?	Page #
SPKU-TRK	Trucker Kit/Universal	18"H x 15"W x 6"D	1	8.3	60	W, O, S	no	41
SPKO-TRK	Trucker Kit/Oil-Only	18"H x 15"W x 6"D	1	8.3	60	O	no	41
SPKHZ-TRK	Trucker Kit/HazMat	18"H x 15"W x 6"D	1	8.3	60	A, W, O, S	no	41

**Complete Product SpecSheet**

Compatibility: W-Water O-Oil S-Solvents A-Aggressive

## 5-Gallon HazMat Pouch Kits Page 41

Item #	Description	Size	Refill Kit #	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #
SPKHZ-5OP	5-Gal Pouch Kit/HazMat	12" diam., 15"H	OP210 or OP25	2.2	24	A, W, O, S	no	41
OP210	5-Gal Refill Pouch	20"L x 25"W x 4"H	n/a	22.0	30	A, W, O, S	yes	41
OP25	5-Gal Refill Pouch	20"L x 25"W x 4"H	n/a	11.0	32	A, W, O, S	yes	41
A5OVER	5-Gal Empty Pail w/ Screw-Top Lid	12" diam., 16.75"H	n/a	n/a	72	n/a	no	40, 41 & 44

## Specialty Spill Kits Page 41

Item #	Description	Size	Refill Kit #	Absorbs/Pkg. (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #
MERC-KIT	Mercury Spill Kit	14"L x 5"W x 11"H	n/a	475 mL	100	Only Mercury	no	41
SPKHZ-BATT	Battery Acid Spill Kit	23" diam., 19"H	RSPKHZ-BATT	23.3	16	A, W, O, S	no	41

## Repair Kits Page 42

Item #	Description	Size	Units/Package	Absorbs/Pkg	Qty./Pallet	Compatibility	Incinerable?	Page #
R-DRUM	Drum Repair Kit	8"H x 18"W x 8"D	1	n/a	40	W, O, S	no	42
R-LEAK	Leak Repair Kit	14"H x 24"W x 5"D	1	n/a	30	W, O, S	no	42
R-PIPE-L	Pipe Repair Kit	For 5" to 8" Pipes	1	n/a	40	W, O, S	no	42
R-PIPE-S	Pipe Repair Kit	For .5" to 4" Pipes	1	n/a	30	W, O, S	no	42

## OverPacks and Containers Page 44

Item #	Description	Size	Units/Package	Sump Capacity (gal.)	Qty./Pallet	Compatibility	Incinerable?	Page #
A-KADDIE	Empty Spill Kaddie	40"H x 20"W x 20"D	1	n/a	8	n/a	no	40 & 44
A-UTILITYBOX5	Empty Spill Cart w/ 5" Wheels	48"H x 31"W x 31.5"D	1	15 Cu. Ft.	Nest 5 High	n/a	no	40 & 44
A-UTILITYBOX8	Empty Spill Cart w/ 8" Wheels	48"H x 31"W x 31.5"D	1	15 Cu. Ft.	Nest 5 High	n/a	no	40 & 44
A95OVER	Empty 95-Gal OverPack	32" diam., 41.5"H	1	95	Nest 4 High	n/a	no	38 & 44
A95OVER-WD	Empty 95-Gal OverPack w/ Wheels	32" diam., 47.5"H	1	95	3	n/a	no	38 & 44
A65OVER	Empty 65-Gal OverPack	28.25" diam., 37.5"H	1	65	8	n/a	no	39 & 44
A65OVER-WD	Empty 65-Gal OverPack w/ Wheels	24.5" diam., 45.5"H	1	50	6	n/a	no	39 & 44
A30OVER	Empty 30-Gal OverPack	23" diam., 30.75"H	1	30	20	n/a	no	39 & 44
A20OVER	Empty 20-Gal OverPack	23" diam., 19"H	1	20	40	n/a	no	39, 40 & 44
A5OVER	Empty 5-Gal Pail w/ Screw-Top Lid	12" diam., 16.75"H	1	5	72	n/a	no	40, 41 & 44
A-YTOTE	Empty Tote Bag	20"L x 17"W x 8"D	1	n/a	1000	n/a	no	41 & 44

## Spill Kit Accessory Items Page 45

Item #	Description	Size	Units/Package	Absorbs/Pkg	Qty./Pallet	Compatibility	Incinerable?	Page #
A-TYVEK-M	Coveralls	Medium	1	n/a	n/a	A, W, O, S	no	45
A-TYVEK-L	Coveralls	Large	1	n/a	n/a	A, W, O, S	no	45
A-TYVEK-XL	Coveralls	Extra Large	1	n/a	n/a	A, W, O, S	no	45
A-APRON-WH	Apron - Enduro 2000™ Fabric	One size fits all	1	n/a	n/a	A, W, O, S	no	45
A-LATEXBOOTS	Latex Boots	Size Extra Large	1	n/a	n/a	A, W, O, S	no	45
A-GOG	Safety Goggles	One size fits all	1	n/a	n/a	n/a	no	45
A-GLV-NEO	Neoprene Gloves	Large	1	n/a	n/a	A, W, O, S	no	45
A-GLV-NIT	Nitrile Gloves	One size fits all	1	n/a	n/a	A, W, O, S	no	45
A-GLV-NIT-CS	Nitrile Gloves	One size fits all	144	n/a	n/a	A, W, O, S	no	45

## Spill Kit Accessory Items Pages 46, 47

Item #	Description	Size	Units/Package	Absorbs/Pkg	Qty./Pallet	Compatibility	Incinerable?	Page #
ANS1	Acid Neutralizing Sorbent	2-lb. Shaker	1	0.2	720	A	yes	46
ANS12	Acid Neutralizing Sorbent	2-lb. Shakers	12	2.4	60	A	yes	46
ANS5	Acid Neutralizing Sorbent	5-Gal. Pail	1	2.5	40	A	yes	46
SS1	SuperSorb Loose Sorbent	28-oz. Shaker	1	0.6	720	W, O, S	yes	46
SS12	SuperSorb Loose Sorbent	28-oz. Shakers	12	7.0	60	W, O, S	yes	46
A-PHTEST	pH Tester Kit	50"L Tape	1	n/a	n/a	n/a	no	46
A-EGB	Emergency GuideBook	384 Pages	1	n/a	n/a	n/a	yes	46
A-EPOXY	Epoxy Putty	7" Stick	1	n/a	n/a	A, W, O, S	no	46
A-PND	Plug & Dike Epoxy	3.5" diam., 2.5" H	1	n/a	n/a	A, W, O, S	no	46
A-WOODPLUGS	Wooden Plugs	Assorted Sizes	9	n/a	n/a	n/a	yes	46
A-SEAL	Tamper-Proof Seal Labels	2"W x 6" L	6	n/a	n/a	n/a	yes	46
A-SHOVNS	Non-Sparking Shovel	10.5"W x 14"H x 43.5"H	1	n/a	n/a	A, W, O, S	no	46
WPF1113H	HeavyWeight Pads	11" x 13"	100	18.1	60	O	yes	10, 11 & 47
GPF1113H	HeavyWeight Pads	11" x 13"	100	18.1	60	W, O, S	yes	12, 13 & 47
YPF1113H	HeavyWeight Pads	11" x 13"	100	18.1	60	A, W, O, S	yes	22, 23 & 47
A-WIPER	Wipers	13" x 12.5"	56	n/a	n/a	W, O, S	yes	47
A-BRACKET	Wall-Mount Bracket	21.75"L x 12.5"W x 6"H	1	n/a	72	n/a	no	47
A-COVER-SM	OverPack Cover	for 20- & 30-gal. OverPacks	1	n/a	100	n/a	no	47
A-COVER-LG	OverPack Cover	for 65- & 95-gal. OverPacks	1	n/a	100	n/a	no	47
A-LIGHTSTICKS	Light Stick	6"L Stick	1	n/a	n/a	n/a	no	47
A-LABELS	Hazard Labels Set	Assorted Sizes	5	n/a	n/a	n/a	no	47
A-DISP BAG	Temporary Disposal Bag	30"W x 6"D x 60"H	1	n/a	n/a	W, O, S	no	47
A-DISP BAG ROLL	Temporary Disposal Bag	30"L x 12"W x 12"H	1	n/a	n/a	W, O, S	no	47
A-SIGN	Spill Control Station Sign	7"H x 10"W	1	n/a	n/a	n/a	no	47

## DrainCovers Page 48

Item #	Description	Size	Units/Package	Absorbs/Pkg	Qty./Pallet	Compatibility	Incinerable?	Page #
ADC12-CIR	12" Dia. DrainCover	12"Dia. x 5" Dia.	1	n/a	40	A, W, O, S	no	48
ADC36-R	36" DrainCover	36"L x 36"W x .25"H	1	n/a	18	A, W, O, S	no	48
ADC42-R	42" DrainCover	42"L x 42"W x .25"H	1	n/a	10	A, W, O, S	no	48
ADC36-CASE	Case for 36" Cover	7.25" Dia. x 38" L	1	n/a	25	n/a	no	48
ADC42-CASE	Case for 42" Cover	7.25" Dia. x 50" L	1	n/a	25	n/a	no	48

**Compatibility:** A-Aggressive S-Solvents O-Oil W-Water

Conical DrainPlugs		DrainPlugs						Page 48
Item #	Description	Size	Units/Package	Absorbs/Pkg	Qty./Pallet	Compatibility	Incinerable?	Page #
DP2	2" Dia. DrainPlug	2"Dia. x 4.75" H	1	n/a	n/a	A, W, O, S	no	48
DP3	3" Dia. DrainPlug	3"Dia. x 5" H	1	n/a	n/a	A, W, O, S	no	48
DP4	4" Dia. DrainPlug	4"Dia. x 5.75" H	1	n/a	n/a	A, W, O, S	no	48
DP6	6" Dia. DrainPlug	6"Dia. x 5.5" H	1	n/a	n/a	A, W, O, S	no	48

SpillBerm Plus		SpillBerm Plus						Page 49
Item #	Description	Size	Units/Package	Absorbs/Pkg	Qty./Pallet	Compatibility	Incinerable?	Page #
PBL253	SpillBerm Plus	5'L x 4" W x 4.5" H	1	n/a	32	A, W, O, S	no	49

Connectable Spill Berm		Connectable SpillBerm						Page 49
Item #	Description	Size	Units/Package	Absorbs/Pkg	Qty./Pallet	Compatibility	Incinerable?	Page #
SPB10C	Connectable SpillBerm	10"L x 2.25"W x 1.375"H	1	n/a	28	A, W, O, S	no	49

SpillCurb		SpillCurb						Page 49
Item #	Description	Size	Units/Package	Absorbs/Pkg	Qty./Pallet	Compatibility	Incinerable?	Page #
MR8014	SpillCurb	10"L x 3.75"W x 2.25"H	1	n/a	32	A, W, O, S	no	49
MR8018	SpillCurb Corner	4"L x 2.25"H	1	n/a	100	A, W, O, S	no	49
MR8019	SpillCurb Connector	4"L x 2.25"H	1	n/a	500	A, W, O, S	no	49
MR8014-CASE	SpillCurb Case	24.75" Dia. x 4" Dia.	1	n/a	500	A, W, O, S	no	49

Ultra-Dewatering Bag®		Ultra-Dewatering Bag®						Page 50
Item #	Description	Size	Units/Package	Absorbs/Pkg	Qty./Pallet	Compatibility	Incinerable?	Page #
ULT9729-OS	Ultra-Dewatering Bag®	3' x 4'	1	n/a	200	W, O	no	50
ULT9724-OS	Ultra-Dewatering Bag®	6' x 6'	1	n/a	80	W, O	no	50
ULT9725-OS	Ultra-Dewatering Bag®	10' x 15'	1	n/a	10	W, O	no	50

Ultra-GutterGuard®		Ultra-GutterGuard®						Page 50
Item #	Description	Size	Units/Package	Absorbs/Pkg	Qty./Pallet	Compatibility	Incinerable?	Page #
ULT9320	Ultra-GutterGuard®	9" diam. x 8'L	1	n/a	20	W, O	no	50
ULT9321	Ultra-GutterGuard®	9" diam. x 10'L	1	n/a	20	W, O	no	50
ULT9322	Ultra-GutterGuard®	9" diam. x 12'L	1	n/a	20	W, O	no	50

Ultra-DrainGuard®		Ultra-DrainGuard®						Page 50
Item #	Description	Size	Units/Package	Absorbs/Pkg	Qty./Pallet	Compatibility	Incinerable?	Page #
ULT9217	Ultra-DrainGuard® - Oil & Sediment	48"L x 36"W x 18"H	1	n/a	36	W, O	no	50
ULT9218	Ultra-DrainGuard® - Oil & Sediment	48"L x 36"W x 18"H	10	n/a	16	W, O	no	50

Roof and Pipe Leak Diverters		Roof and Pipe Leak Diverters						Page 51
Item #	Description	Size	Units/Package	Absorbs/Pkg	Qty./Pallet	Compatibility	Incinerable?	Page #
LD1818	Pipe Leak Diverter	18"L x 18"W	1	n/a	500	W	no	51
LD55	Roof Leak Diverter	5'L x 5'W	1	n/a	500	W	no	51
LD1010	Roof Leak Diverter	10'L x 10'W	1	n/a	500	W	no	51

Prowler™ Pools		Prowler™ Pools						Page 51
Item #	Description	Size	Units/Package	Absorbs/Pkg	Qty./Pallet	Compatibility	Incinerable?	Page #
ENP5920	Prowler™ Pool (20-Gallon)	28" Base x 13"H x 18" Opening	1	20	160	A, W, O, S	no	51
ENP5966	Prowler™ Pool (66-Gallon)	48" Base x 14"H x 36" Opening	1	66	48	A, W, O, S	no	51
ENP5900	Prowler™ Pool (100-Gallon)	48" Base x 18"H x 32" Opening	1	100	48	A, W, O, S	no	51
ENP5950	Prowler™ Pool (150-Gallon)	60" Base x 18"H x 44" Opening	1	150	60	A, W, O, S	no	51

Burp-Free Funnels		Burp-Free Funnels						Page 52
Item #	Description	Size	Units/Package	Sump Cap.	Qty./Pallet	Compatibility	Incinerable?	Page #
ULT0651	Funnel	13.375" Dia. x 11" H	1	n/a	40	A, W, O, S	no	52
ULT0656	Large-Diameter Funnel	22" Dia. x 11.5" H	1	n/a	20	A, W, O, S	no	52

Containment Sumps		Containment Sumps						Page 52
Item #	Description	Size	Units/Package	Sump Cap.	Qty./Pallet	Compatibility	Incinerable?	Page #
ULT2800	275 Sump w/o Drain	84.5"L x 43.5"W x 29"H	1	360	6	A, W, O, S	no	52
ULT2801	275 Sump w/ Drain	84.5"L x 43.5"W x 29"H	1	360	6	A, W, O, S	no	52
ULT2820	550 Sump w/ Drain	87"L x 62.25"W x 32.75"H	1	605	6	A, W, O, S	no	52
ULT2823	550 Sump w/o Drain	87"L x 62.25"W x 32.75"H	1	605	6	A, W, O, S	no	52

Rack Containment Tray		Rack Containment Tray						Page 52
Item #	Description	Size	Units/Package	Sump Cap.	Qty./Pallet	Compatibility	Incinerable?	Page #
ULT2372	Trays w/ Connectors	72"L x 44"W x 2.75" H	1	24	10	A, W, O, S	no	52

Ultra-Utility Tray®		Ultra-Utility Tray®						Page 52
Item #	Description	Size	Units/Package	Sump Cap.	Qty./Pallet	Compatibility	Incinerable?	Page #
ULT1031	Ultra-Utility Tray®	12"L x 48"W x 4.75"H	1	12	24	A, W, O, S	no	52
ULT1032	Ultra-Utility Tray®	24"L x 48"W x 4.75"H	1	24	15	A, W, O, S	no	52
ULT1033	Ultra-Utility Tray®	30"L x 48"W x 4.75"H	1	30	15	A, W, O, S	no	52
ULT1034	Ultra-Utility Tray®	24"L x 36"W x 4.75"H	1	18	15	A, W, O, S	no	52
ULT1035	Ultra-Utility Tray®	36"L x 36"W x 4.75"H	1	27	15	A, W, O, S	no	52
ULT1036	Ultra-Utility Tray®	40"L x 36"W x 3.5"H	1	30	15	A, W, O, S	no	52

Ultra-Spill Decks®		Ultra-Spill Decks®						Page 53
Item #	Description	Size	Load Capacity	Sump Capacity	Qty./Pallet	Compatibility	Incinerable?	Page #
ULT1321	1-Drum Section	26"L x 26"W x 5.75"H	3,000 lbs.	11	1	A, W, O, S	no	53
ULT1086	2-Drum Section	52"L x 26"W x 5.75"H	3,000 lbs.	22	1	A, W, O, S	no	53
ULT1072	4-Drum Section	52"L x 52"W x 5.75"H	6,000 lbs.	44	1	A, W, O, S	no	53
ULT1073	Bulkhead Fitting	3" Dia.	n/a	5,000	1	A, W, O, S	no	53
ULT1089	Loading Ramp	24"L x 32"W x 5.75"H	n/a	25	20	A, W, O, S	no	53
ULT1131	T-Strips	26"	n/a	5,000	20	A, W, O, S	no	53

1-Drum Bladder System		1-Drum Bladder System						Page 54
Item #	Description	Size	Load Capacity	Units/Package	Qty./Pallet	Compatibility	Incinerable?	Page #
ULT1320	1-Drum Bladder System	26"L x 30.5"W x 5.75"H	1,500 lbs.	66	20	A, W, O, S	no	54

IBC Spill Pallets		IBC Spill Pallets						Page 54
Item #	Description	Size	Load Capacity	Sump Capacity	Qty./Pallet	Compatibility	Incinerable?	Page #
ULT1140	2-IBC w/o Drain	124.5"L x 61.625"W x 22"H	8,000 lbs.	535	1	A, W, O, S	no	54
ULT1144	2-IBC w/ Drain	124.5"L x 61.625"W x 22"H	8,000 lbs.	535	1	A, W, O, S	no	54
ULT1157	1-IBC w/o Drain	62"L x 62"W x 28"H	8,500 lbs.	360	1	A, W, O, S	no	54
ULT1158	1-IBC w/ Drain	62"L x 62"W x 28"H	8,500 lbs.	360	1	A, W, O, S	no	54
ULT1160	Bucket Shelf	19.5"L x 16"W x 14.5"H	n/a	n/a	20	A, W, O, S	no	54

Ultra-Spill Pallets® / Economy Model		Ultra-Spill Pallets® / Economy Model						Page 54
Item #	Description	Size	Units/Package	Load Capacity (lb.)	Sump Capacity (gal.)	Qty./Pallet	Compatibility	Page #
ULT2505	2-Drum Pallet w/Drain	53"L x 29"W x 16.5"H	1	1500	66	1	A, W, O, S	54
ULT2504	2-Drum Pallet w/o Drain	53"L x 29"W x 16.5"H	1	1500	66	1	A, W, O, S	54
ULT1113	4-Drum Pallet w/Drain	53"L x 53"W x 11.75"H	1	3000	66	1	A, W, O, S	54
ULT1112	4-Drum Pallet w/o Drain	53"L x 53"W x 11.75"H	1	3000	66	1	A, W, O, S	54

Ultra-Hard Top Plus® / Drums		Ultra-Hard Top Plus® / Drums						Page 55
Item #	Description	Size	Load Capacity	Sump Capacity	Qty./Pallet	Compatibility	Incinerable?	Page #
ULT9636	4-Drum w/o Drain	64.5"L x 62"W x 79"H	9,000 lbs.	75	1	A, W, O, S	no	55
ULT9637	4-Drum w/ Drain	64.5"L x 62"W x 79"H	9,000 lbs.	75	1	A, W, O, S	no	55
ULT9612	2-Drum w/o Drain	67.25"L x 41.25"W x 74"H	4,500 lbs.	66	1	A, W, O, S	no	55
ULT9613	2-Drum w/ Drain	67.25"L x 41.25"W x 74"H	4,500 lbs.	66	1	A, W, O, S	no	55
ULT0676	Hard Top Loading Ramp	46"L x 28"W x 8.75"H	n/a	n/a	1	A, W, O, S	no	55

Ultra-Hard Top Plus® / IBC Tanks		Ultra-Hard Top Plus® / IBC Tanks						Page 55
Item #	Description	Size	Load Capacity	Sump Capacity	Qty./Pallet	Compatibility	Incinerable?	Page #
ULT1161	IBC w/ Drain	64.5"L x 62"W x 96"H	8,500 lbs.	360	1	A, W, O, S	no	55
ULT1162	IBC w/o Drain	64.5"L x 62"W x 96"H	8,500 lbs.	360	1	A, W, O, S	no	55

Containment		Drive-In Berm and Portable Containment						Page 56
Item #	Description	Size	Units/Package	Load Capacity (lb.)	Sump Capacity (gal.)	Qty./Pallet	Compatibility	Page #
ENP5760	4-Drum SpillPal™	4'L x 4'W x 4'H	1	n/a	40	15	A, W, O, S	56
ENP5755	2-Drum SpillPal™	2'L x 4'W x 4'H	1	n/a	20	15	A, W, O, S	56
ENP7006	Replacement Grates (2 Drums Per Grate)	4'L x 23"W x 1.75"H	1	1000	n/a	50	A, W, O, S	56
PAC48	Containment Berm	4'L x 8'W x 12"H	1	n/a	239	1	A, W, O, S	56
PAC88	Containment Berm	8'L x 8'W x 12"H	1	n/a	478	1	A, W, O, S	56
PAC1212	Containment Berm	12'L x 12'W x 12"H	1	n/a	1077	1	A, W, O, S	56
PAC1212-CVR	Ground Cover for 12' x 12'	15'L x 14'W	1	n/a	n/a	1	A, W, O, S	56
PAC1212-TRK	Track Guard for 12' x 12'	24"L x 12'W	2	n/a	n/a	1	A, W, O, S	56
PAC1225	Containment Berm	12'L x 25'W x 12"H	1	n/a	2244	1	A, W, O, S	56
PAC1225-CVR	Ground Cover for 12' x 25'	15'L x 27'W	1	n/a	n/a	1	A, W, O, S	56
PAC1225-TRK	Track Guard for 12' x 25'	24"L x 25'W	2	n/a	n/a	1	A, W, O, S	56
PAC1250	Containment Berm	12'L x 50'W x 12"H	1	n/a	4488	1	A, W, O, S	56
PAC1250-CVR	Ground Cover for 12' x 50'	15'L x 52'W	1	n/a	n/a	1	A, W, O, S	56
PAC1250-TRK	Track Guard for 12' x 50'	24"L x 50'W	2	n/a	n/a	1	A, W, O, S	56

Containment		Portable Containment						Page 57
Item #	Description	Size	Units/Package	Load Capacity (lb.)	Sump Capacity (gal.)	Qty./Pallet	Compatibility	Page #
ENP3004	Universal Poly-Drum Funnel™	26" diam. x 5.5"H	1	n/a	n/a	50	A, W, O, S	57
ENP8075	Poly-Collector™	32.5" diam. x 31"H	1	n/a	70	Stack of 5	A, W, O, S	57
ENP8050	Drum Dolly	27.5" diam. x 5.5"H	1	n/a	n/a	25	A, W, O, S	57
ENP5300	Poly-Dolly®	69"L x 32.5"W x 26.5"H	1	600	80	1	A, W, O, S	57
A-DOLLY	OverPack Dolly	24"L x 24"W x 60"H	1	n/a	n/a	18	A, W, O, S	57


**Product Information** - All information provided about SpillTech® Products is based upon testing and data believed to be accurate. However, the reliability of this information is not subject to any guarantee.

**Handling and Disposal** - Liquids absorbed by SpillTech® Products are not rendered less hazardous, less toxic or less flammable by absorption; liquids remain in their original states. Therefore, caution in the handling, storage, disposal or cleaning of SpillTech® Products after use should be in accordance with the original liquids absorbed. Consult the Material Safety Data Sheet of each liquid absorbed for proper handling. SpillTech® Products must be transported and disposed of in compliance with local, state and federal regulations. SpillTech does not recommend specific procedures due to variances in regulations, applications and liquids used.

**Warranty** - SpillTech will replace any product found to be defective in material or workmanship. This warranty shall only apply where the buyer has issued written notice to SpillTech within thirty (30) days of purchase; it does not extend to product abuse, misuse, neglect or accident, nor to product repaired or altered by any other than SpillTech. This warranty is exclusive and in lieu of all other warranties, expressed or implied.

**Limitation of Liability** - In no event will SpillTech's liability for its Products exceed the purchase price paid for its Products. SpillTech will not be liable under any circumstances for any special, indirect, consequential, or punitive damages, including, but not limited to loss of profits, loss of business opportunities, or loss of goodwill, even if advised of the possibility of such damages.

# SpillTech® Products Can Help You Comply



Below you'll find brief summaries of the regulations encountered most often by SpillTech customers, along with a list of relevant SpillTech® Products that can help

you comply. For full information on specific compliance requirements, please refer to the Code of Federal Regulations at: [www.gpoaccess.gov/cfr/index.html](http://www.gpoaccess.gov/cfr/index.html).

## 29 CFR – OSHA (Occupational Health & Safety Administration)

**SpillTech® Products that Help You Comply:** Mats & Sorbents (see pages 4–33) • OverPacks & Spill Kits (see pages 38–44)

### 29 CFR 1910.22(a)(2)

SUMMARY: Floors in your workplace should be "maintained in a clean and, so far as possible, a dry condition."

### 29 CFR 1910.107(b)(3)

SUMMARY: Combustible floors in a spray booth or work area "shall be covered with noncombustible material to facilitate the safe cleaning and removal of residues."

### 29 CFR 1910.107(g)(2)

SUMMARY: OSHA requires spraying areas to be "kept as free from the accumulation of deposits of combustible residues as practical."

### 29 CFR 1910.120(j)(1)

SUMMARY: Commonly known as HAZWOPER, requires DOT containers and proper absorbents be kept available and used wherever spills, leaks or ruptures may occur.

### 29 CFR 1910.1450(e)

SUMMARY: OSHA requires containment and cleanup materials for spills in laboratories to reduce occupational exposure to hazardous chemicals.

## 33 CFR – USCG (United States Coast Guard)

**SpillTech® Products that Help You Comply:** Booms • PomPoms • Net Bags • Sweeps (see pages 35–37)

### 33 CFR 154.1047(c)(2)

SUMMARY: Concerning navigation and navigable waters, a facility which handles, stores or transports Group V

petroleum oils must identify response plan resources such as containment booms or other methods.

## 40 CFR – EPA (Environmental Protection Agency)

**SpillTech® Products that Help You Comply:** Spill Kits (see pages 38–43) • Berms & DrainCovers (48–49) • SpillPallets® (54)

### 40 CFR 112.7(c)(1)

SUMMARY: Facilities must have "appropriate containment and/or diversionary structures to prevent discharge oil from reaching a navigable water course."

### 40 CFR 122.26

SUMMARY: Facilities must have a detailed plan in place to prevent illegal discharge of pollutants into waterways.

### 40 CFR 263.30(a)

SUMMARY: Requires immediate action, such as diking the discharge area, by transporter if hazardous waste is accidentally discharged during transportation.

### 40 CFR 263.31

SUMMARY: A transporter must clean up any hazardous waste discharges that occur during transportation.

### 40 CFR 264.175

SUMMARY: A hazardous waste container must not sit in its own spill, and it must be able to hold 10% of total volume of liquid or 100% of largest container, whichever is greater.

## 49 CFR – DOT (Department of Transportation)

**SpillTech® Products that Help You Comply:** OverPacks (see pages 38–44)

### 49 CFR 173.3(c)(1)

SUMMARY: If a container of hazardous waste is damaged or leaking, it can be placed in a compatible salvage drum that meets UN criteria for shipping by air, highway, rail or water.

### 49 CFR 173.12(b)

SUMMARY: A labpacking container must be "a UN 1A2 or UN 1B2 metal drum, a UN 1D plywood drum, a UN 1G fiber drum or a UN 1H2 plastic drum tested and marked for the Packing Group III performance level."

### 49 CFR 173.12(b)(2)(iv)

SUMMARY: When labpacking, "Inner packagings ... must be surrounded by a chemically compatible absorbent material in sufficient quantity to absorb the total liquid contents."

# SPILLTECH



## Manufacturing/Warehousing

Mobile  
Brookley Industrial Complex  
1627 O'Donoghue Street  
Mobile, AL 36615

Hastings  
Hastings Area Industrial Park  
233 Haida Avenue  
Hastings, PA 16646

Houston  
4730 Eastpark Drive  
Houston, TX 77028


Indianapolis  
450 Enterprise Drive  
Westfield, IN 46074

Seattle  
938 Valley Avenue NW  
Bldg #5 Suite 101-B  
Puyallup, WA 98371

**Sales & Marketing Offices**  
5440 McGinnis Village Place  
Suite 102  
Alpharetta, GA 30005

[www.spilltech.com](http://www.spilltech.com)

Distributed By:



**Look for SpillTech® Products  
that help you comply with  
Federal Regulations!** See page 67.